
AD-A240 608 







# Slang Reference Manual

91-11234

System for User Interface Development

Version

Date

1

May 1991

This document has been approved for public release and sale; its distribution is unlimited.

91 20 041

User's Guide CMU/SEI-91-UG-5 May 1991

## **Serpent: Slang Reference Manual**





Access	Pas for	
PITE	Tarry 🗸 🗆	
U . s.		
Jasania 	talima •••••	
Ву	enter de la companya	
Dist %	that	
/\ - <del></del> <del></del> -	ant sistem of the con-	
Dist	An Span	,
A-1		
/ n		

User Interface Project

Approved for public release.

Distribution unlimited.

**Software Engineering Institute** 

Camegie Mellon University Pittsburgh, Pennsylvania 15213 This document was prepared for the

SEI Joint Program Office ESD/AVS Hanscom AFB, MA 01731

The ideas and findings in this document should not be construed as an official DoD position. It is published in the interest of scientific and technical information exchange.

#### Review and Approval

This document has been reviewed and is approved for publication.

FOR THE COMMANDER

Charles J. Ryan, Major, USAF SEI Joint Program Office

The Software Engineering Institute is sponsored by the U.S. Department of Defense. This report was funded by the Department of Defense.

Copyright © 1991 by Carnegie Mellon University.

This document is available through the Defense Technical Information Center. DTIC provides access to and transfer of scientific and technical information for DoD personnel, DoD contractors and potential contractors, and other U.S. Government agency personnel and their contractors. To obtain a copy, please contact DTIC directly: Defense Technical Information Center, Attn: FDRA, Cameron Station, Alexandria, VA 22304-6145.

Copies of this document are also available through the National Technical Information Service. For information on ordering please contact NTIS directly: National Technical Information Service, U.S. Department of Commerce, Springfield, VA 22161.

Use of any trademarks in this document is not intended in any way to infringe on the rights of the trademark holder.

## **Table of Contents**

1	Intr	oduction	1
	1.1	This Manual	1
		1.1.1 Organization	1
		1.1.2 Typographical Conventions	1
	1.2	Documentation	1
2	Ser	pent Overview	5
	2.1	Serpent Architecture	6
	2.2	Shared Database	8
	2.3	Serpent Components	9
3	Slan	ng Overview	11
	3.1	Interaction Objects	11
		3.1.1 Attributes	11
		3.1.2 Methods	13
	3.2	Variables	14
	3.3	Data Dependencies	16
	3.4	View Controllers	16
	3.5	Shared Data	22
	3.6	Dialogue Shared Data	24
	3.7	Actions ON CREATE and ON DESTROY	25
	3.8	Dialogue Structure	
4	Lex	ical Elements	29
	4.1	Character Set	29
	4.2	Comments	29
	4.3	Tokens	30
		4.3.1 Operators and Special Characters	30
		4.3.2 Identifiers	31
		4.3.3 Reserved Words	31
		4.3.4 Constants	32
5	Data	a	35
	5.1	Different Forms of Data	35
	5.2	Assignment of Values to Data Types	35
	5.3	Object Types	36

	5.4	Data Types	36
	5.5	Base Types	37
	5.6	Dependency	37
	5.7	Scope and Visibility	39
	5.8	Extent	42
	5.9	Data Access	42
	5.10	Declared Data	43
		5.10.1 View Controllers	43
		5.10.2 Objects	44
		5.10.3 Attributes	44
		5.10.4 Methods	45
		5.10.5 Shared Data	45
		5.10.6 Dialogue Shared Data	46
		5.10.7 Application Shared Data	47
	5.11	Data Reference	47
		5.11.1 Dialogue Structure	48
		5.11.2 Direct Reference	48
		5.11.3 Indirect Reference	49 49
		5.11.4 Examples of Data Reference	47
6	Exp	ressions	53
	6.1	Undefined Values	53
	6.2	Logical AND and OR Operators	53
	6.3	Equality Operators	54
	6.4	Relational Operators	55
	6.5	Arithmetic Operators	56
	6.6	Unary Operators	58
7	Cod	e Snippets and Statements	59
	7.1	Function Call	59
	7.2	Assignment Statement	60
	7.3	Conditional Statement	60
	7.4	Loop Statement	61
8	Jnte	raction Objects	63
	8.1	Attributes	53
	8.2	Methods	64

9	View	Contr	ollers	67
	9.1	Creation	on Conditions	67
	9.2	Action	s "On Create"	69
	9.3	Action	as on Destroy	69
			dency Considerations	70
		-	gue Structure	71
	7.0		Prologue	71
			Component List	72
10	User	-Define	ed Functions	75
	10.1	Extern	al Functions	75
	10.2	Existin	ng External Functions	76
			Slang String Functions	77
			string_append	78
			string_count_chars	79
			string_delete	80
			string_index	81
			string_insert	82
			string_is_integer	83
			string_is_real	84
			string_length	85
			string_lower	86
			string_upper	87
			substring div	88
				90 91
			make_integer, truncate mod	91
		10 3 1	Existing C functions	93
			Creating New External Functions	94
			Type Equivalences	94
			Memory Allocation Considerations	95
			Linking External Functions To Slang Programs	97
11	Runt	ime Sy	stem	99
		Cycles		99
		•	g of Data Transfers to Application and Toolkit	99
			ations of Dependencies	100

12 Slang Preprocessor		101
12.1 Macı	ros and Conditional Compilation	101
Appendix A	Glossary of Terms	103
Appendix B	Slang BNF Grammar	107
Appendix C	Runtime Conversions	113
Appendix D	Data Access Routines get_bound_sd_instance get_variable_value get_name get_object get_parent_vc put_variable_value get_vc	119 120 121 122 123 124 125 126
Appendix E	Shared Data Routines create_sd_instance destroy_sd_instance get_sd_value put_sd_value	127 128 129 130 131
Appendix F	Utility Routines exit id_exists new recording_on recording_off	133 134 135 137 138 139
Appendix G	Athena Widget Set XawBboard XawBox XawCommand XawDialog XawForm XawLabel XawMenuButton XawMenuShell XawPaned XawScreenObject XawScrollbar	141 143 146 149 153 156 159 162 165 168 172

	XawSimpleMenu XawSimpleMenuBSB XawSmeLine XawText XawText XawTextentry XawToggleButton XawTopLevelShell XawViewport	176 179 182 185 190 195 199 201
Appendix H	Motif Widget Set XmArrowButton XmBulletinBoard XmCascadeButton XmCommand XmCommand XmDrawingArea XmDrawnButton XmErrorDialog XmFileSelectionBox XmForm XmFrame XmInformationDialog XmLabel XmList XmMainWindow XmMenubar	205 207 210 214 218 223 226 230 234 239 243 246 250 253 258
	XmMenuShell XmMessageBox XmMessageDialog XmOption XmPanedWindow XmPopup XmPulldown XmPushButton XmQuestionDialog XmRowColumn XmScale XmScreenObject XmScrollBar XmScrolledWindow XmSeparator	266 269 273 277 281 284 288 292 296 300 304 308 309 312

	KmText	318
	XmToggleButton	323
	XmTopLevelShell	327
	XmWarningDialog	330
	XmWorkingDialog	334
Index		339

# **List of Examples**

Example 3-1	Attributes	12
Example 3-2	Methods	13
Example 3-3	Dialogue Variables	15
Example 3-4	Menu Bar	22
Example 3-5	View Controller Template	24
Example 3-6	Calculating Aggregate Functions	26
Example 5-1	Automatic Conversion	36
Example 5-2	Fixed Data Type	36
Example 5-3	Dynamic Data Type	36
Example 5-4	Dependency Propagation	38
Example 5-5	Multiple Snippet Infinite Loop	38
Example 5-6	Snippet Dependent On Defined Variable	39
Example 5-7	Snippet Dependent On Variable Both Modified and Used	39
Example 5-8	Scope and Visibility in an Abstract Block Structured	
	Language	40
Example 5-9	Dialogue Shared Data Creation	47
Example 5-10	Dialogue Shared Data Destruction	47
Example 5-11	Direct Reference	48
Example 5-12	Employee Shared Data Definitions	49
Example 5-13	Direct Data Referencing	50
Example 5-14	Indirect Data Referencing	51
Example 6-1	Equality Comparison	55
Example 6-2	Relational Comparison	56
Example 6-3	Arithmetic Operation	57
Example 7-1	Function Call Statements	59
Example 7-2	Assignment Statements	60
Example 7-3	Conditional Statements	61
Example 7-4	While Statement	62
Example 8-1	Attributes	64
Example 8-2	Methods	65
Example 9-1	Free Creation Conditions	68
Example 9-2	Bound Creation Conditions	68
Example 9-3	Actions on Create	69
Example 9-4	Actions on Destroy	70
Example 10-1	External Declarations	76

# **List of Figures**

Figure 1-1	Serpent Documents	2
Figure 2-1	Serpent Architecture	6
Figure 2-2	Serpent Shared Database	9
Figure 3-1	Label Widget	12
Figure 3-2	Command Widget Display	14
Figure 3-3	Drop-Down Menu	17
Figure 3-4	Shared Data Definition	23

# **List of Tables**

Table 4-1	Reserved Words	32
Table 4-2	Character Escape Codes	33
Table 5-1	Base Types	37
Table 6-1	AND Operations	54
Table 6-2	OR Operations	54
Table 6-3	Equality Operators	54
Table 6-4	Relational Operators	55
Table 6-5	Arithmetic Operators	56
Table 6-6	Plus, Minus, Multiple and Exponential Operations	57
Table 6-7	Divide Operation	57
Table 6-8	Unary Operators	58
Table 6-9	Unary Operations	58
Table 10-1	Slang String Functions	77
Table 10-2	Extended Arithmetic Functions	89
<b>Table 12-1</b>	Binary Arithmetic	113
<b>Table 12-2</b>	Relational Operations	114
<b>Table 12-3</b>	Assignment Operations	115
<b>Table 12-4</b>	Unary Arithmetic Operations	116
<b>Table 12-5</b>	Equality Operations	116

# 1 Introduction

Serpent is a user interface management system (UIMS) that supports the development and execution of the user interface of a software system from the prototyping phase through production and maintenance. Serpent encourages a separation of functionality between the user interface and application portion of a system. Serpent is also easily extended to support additional input/output (I/O) toolkits.

This manual describes the model, syntax, and semantics of the Slang dialogue language, the language within Serpent used for the specification of user interfaces.

### 1.1 This Manual

This manual serves two purposes: to provide an introduction to Slang and to provide a reference manual for Slang. Readers should be familiar with general UIMS concepts, have a working knowledge of programming languages, and understand the concepts described in Serpent Overview and Serpent: System Guide.

### 1.1.1 Organization

The first three chapters provide an introduction to Slang. The remainder of the manual provides syntactic and semantic information about Slang.

### 1.1.2 Typographical Conventions

The following conventions are observed in this manual.

Code examples

Courier typeface

Variables, attributes, etc.

Courier typeface

Syntax

Courier typeface

Warnings and Cautions

Bold, italics

### 1.2 Documentation

This reference manual describes the model, syntax, and semantics of the Slang dialogue language. The following publications address other aspects of Serpent.

Serpent Overview

Introduces the Serpent system.

#### Introduction

Serpent: System Guide

Describes installation procedures, specific input/output file descriptions for intermediate sites and other information necessary to set up a Serpent application.

Serpent: Saddle User's Guide

Describes the language that is used to specify interfaces between an application and Serpent.

Serpent: Dialogue Editor User's Guide

Describes how to use the editor to develop and maintain a dialogue.


Serpent: C Application Developer's Guide Serpent: Ada Application Developer's Guide

Describe how the application interacts with Serpent. These guides describe the runtime interface library, which includes routines that manage such functions as timing, notification of actions, and identification of specific instances of the data.

Serpent: Guide to Adding Toolkits

Describes how to add user interface toolkits such as various Xt-based widget sets to Serpent or to an existing Serpent application. Currently, Serpent includes bindings to the Athena Widget Set and the Motif Widget Set.

The following figure shows Serpent documentation in relation to the Serpent system:



**Figure 1-1 Serpent Documents** 

Introduction

# 2 Serpent Overview

Serpent manages the total dynamic behavior of an interface and allows an application to be separated from the details of the user interface. Serpent is designed to manage relatively arbitrary toolkits. There is a language to describe the interface and an editor to build it. Serpent provides a runtime system that enables communication between the application and the end user.

Serpent supports the incremental development of the user interface from prototyping through production and maintenance. Serpent can be used either with an application in a production environment or without an application in a prototyping environment.

A primary goal of Serpent is to encourage the separation of a software system into an application portion and a user interface portion. This provides the application developer with a fixed application programmer's interface. One benefit of a fixed application programmer's interface is that the application programmer is insulated from the modifications to the user interface that are the most likely modifications to a completed system. Another benefit of using Serpent is that it provides the tools to develop and modify the user interface. A system developed using Serpent can be migrated to new toolkits without time-consuming reengineering of the application portion.

### 2.1 Serpent Architecture

Serpent is implemented using the standard UIMS architecture defined by the Seeheim working group on graphical interfaces (see *User Interface Management Systems*, G. E. Pfaff, ed, Eurographics Seminars, Springer-Verlag, 1985). The architecture consists of three layers: presentation, dialogue, and application (Figure 2-1).




Figure 2-1 Serpent Architecture

The architecture is intended to encourage the proper separation of functionality between the application and the user interface portions of a software system. The three different layers of the standard architecture provide differing levels of control over user input and system output. The presentation layer is responsible for layout and device issues. The dialogue layer specifies the presentation of application information and user interactions. The application layer provides the functionality for the system.

The presentation layer consists of toolkits that have been incorporated into Serpent. Toolkits are existing hardware/software systems that perform some level of generalized interaction with the end user. Serpent is distributed with an interface to the X Window System (Version 11), to the MIT Athena Widget Set, and to the OSF/Motif Toolkit. Other toolkits based on the X Window System Intrinsics can be easily integrated into Serpent, and toolkits not based on the X Window System Intrinsics can be integrated without undue difficulty. Refer to the Serpent: Guide to Adding Toolkits for a discussion of how to do this.

The end-user interface for a software system is formally specified as a *dialogue* in Serpent. The dialogue specifies both the presentation of application information and end-user interactions.

The application provides the functional portion of the software system in a presentation-independent manner. It may be developed in C, Ada, or other programming languages (only C and Ada are supported at this time). The application may be either a functional simulation for prototyping purposes or the actual application for a delivered system. The actions of the application layer are based on knowledge of the specific problem domain. Serpent: C Application Developer's Guide and Serpent: Ada Application Developer's Guide describe how an application interacts with Serpent.

One way of viewing the three levels of the architecture is by the level of functionality provided for user input. The presentation layer is responsible for lexical functionality, the dialogue layer for syntactic functionality, and the application layer for semantic functionality. For example, in processing the selection of a menu item, the presentation layer is responsible for determining which menu item was selected and for presenting some indication to the end user of which item is currently selected. The dialogue layer is responsible for deciding whether another item is to be selected and for presenting it to the end user, or whether the choice requires action by the application. The application layer is responsible for executing those functions specific to the application. In another example, in processing a change in the status of the application, the application would detect the change in status and inform the dialogue layer of the new status. The dialogue layer would decide that the change in status requires a form to appear on the display, and the presentation layer would actually make the form visible to the end user.

### 2.2 Shared Database

Serpent provides an active database model for communication among the application, the dialogue, and the toolkits. In an active database, multiple processes are allowed to update a single database. Changes are then propagated to each user. This model is implemented in Serpent by a *shared database* that logically exists between the application and toolkits. The application can add, modify, query, or remove data from the shared database. Information provided to Serpent by the application is available for presentation to the end user. The application has no knowledge of the presentation media or user interface styles used to present this information.

The application and the Slang program exchange data through the shared database. Figure 2-2 illustrates the use of the shared database in Serpent. When the application modifies data in the shared database, the portions of the Slang program that depend upon that data are automatically executed. When the Slang program modifies data in the application portion of the shared database, the application is notified. The section of the shared database that is associated with the application layer, application shared data, is accessible only from the application layer and the dialogue layer.

The presentation layer also communicates with the dialogue layer via shared data. The section of the shared database that is associated with the presentation layer, toolkit shared data, is accessible only from the presentation layer and the dialogue layer.




Figure 2-2 Serpent Shared Database

Serpent allows the specification of dependencies between elements in the shared database. These dependencies define a mapping between application data, presentation objects, and end-user input. The dialogue manager enforces the constraints implied by these dependencies by operating on the information stored in the shared database until the constraints are satisfied. Changes are then propagated to either the application or the toolkits as appropriate.

The type and structure of information that can be maintained in the shared database is defined externally in a *shared data definition* file. The structure in the shared data definition file corresponds to the database concept of schemata. A shared data definition file is required for each application; *Serpent: Saddle User's Guide* describes how to construct this file.

### 2.3 Serpent Components

Serpent consists of the following components:

• A language designed for the specification of user interfaces (Slang). This language is compiled into the dialogue layer of the Serpent architecture.

- A database-like schema language (Saddle) to define the interface between the
  application and Serpent. Applications and toolkits written in either C or Ada
  can be used with Serpent, although the interface description mechanism is
  designed to be extensible to other languages.
- A transaction processing library that is linked to the application layer to provide access to Serpent.
- An interactive editor for the specification of dialogues and for the construction and preview of displays.
- Input/output toolkits. The use of Serpent depends upon the types of toolkits that have been integrated.

# 3 Slang Overview

Serpent dialogues are specified in Slang. These dialogues define the presentation of application information to, as well as interactions with, the end user.

This chapter describes the overall dialogue model used by Serpent. The dialogue model provides the conceptual basis for dialogue specification. This model is based largely on the data-driven, rule-based approach used in production systems.

### 3.1 Interaction Objects

Interaction objects, which are defined by a given toolkit, allow user interaction with the application. Each interaction object has a particular appearance and behavior. The behavior determines how the object responds to end-user input. In a display technology, for example, text fields, circles, or rectangles may be defined as interaction objects. In voice technology, voice messages or recordings may be defined as interaction objects.

Interaction objects are specified by the designer in a dialogue and presented to the end user by the presentation layer. The objects used as examples in this document are based on Athena widgets. The Athena Widget Set is one of the initial toolkits supported by Serpent. A description of the supported Athena widget objects is provided in Appendix G. A description the OSF/Motif widgets is provided in Appendix H.

A dialogue is defined by a Slang program, and each Slang program enumerates a collection of objects to be available to the end user. Examples of interaction objects defined for the Athena Widget Toolkit are command widgets and text widgets.

Each object type has a collection of attributes that defines its presentation, as well as methods that determine the high-level interactions that the end user can have with the object. Objects are specified in a Slang program by listing the objects to be created and the attribute values to be assigned to each occurrence of the object. See Chapter 8 for details.

#### 3.1.1 Attributes

Interaction objects have attributes to define the presentation characteristics. These attributes are defined by the toolkit integrator and their values are specified by the dialogue developer.

Example 3-1 provides the Slang specification for a label widget. A label widget is an Athena widget that provides a non-selectable rectangular label. Once defined, the interaction object is displayed to the end user using the toolkit that supports this object. The object defined in Example 3-1 causes a box (label widget) containing the value 0 to be displayed as illustrated in Figure 3-1.

```
display: XawLabel {
  Attributes:
    parent: main_background;
  height: 40;
  width: 60;
  label: 0;
  font: "9xl5bold";
  vertDistance: 100;
  horizDistance: 175;
}
```

**Example 3-1 Attributes** 




Figure 3-1 Label Widget

The label widget is generated as an independent window that the end user can position.

#### 3.1.2 Methods

Interaction objects also have methods that are defined by the toolkit. Methods provide a way for handling end-user interactions in the dialogue by specifying actions to be performed for specific, end-user generated events. For example, the interaction object in Example 3-2 is declared as a command widget. A command widget is an Athena widget object that provides a display button that may be selected by the end user. The Athena Widget toolkit generates a notify event for the object when the command widget on the display is selected.

```
push button: XawCommand {
 Attributes:
    parent: main background;
   height: 40;
    width: 60;
    vertDistance: 200;
    horizDistance: 175;
    font: "9x15bold";
    label: "Push";
Methods:
   notify: {
      display.label:= display.label + 1;
}
}
```

**Example 3-2 Methods** 

The button object defined in Example 3-2 causes a command widget to be displayed that contains the value Press. When selected, the command widget will generate a notify event that causes the notify method in the button definition to be executed. In this case, execution of the method causes the text attribute of the display object defined to be incremental. Figure 3-2 illustrates the display of both objects after the command widget has been pressed.




Figure 3-2 Command Widget Display

It is interesting to note that in the preceding example the label attribute of the XawLabel is actually defined as a string, while the numeric constant 1 is an integer. All type con ersion is handled automatically by Slang.

### 3.2 Variables

Slang also allows for the specification of dialogue variables. Variables can be used for defining object attributes and for defining control flow as described later in this chapter. The preceding example can be rewritten to make use of local variables.

```
Variables:
  counter: 0;
Objects:
display: XawLabel {
  Attributes:
    parent: main_background;
  height: 40;
```

```
width: 60;
    vertDistance: 100;
    horizDistance: 175;
    font: "9x15bold";
    label: counter;
}
button: XawCommand {
 Attributes:
    parent: main background;
    height: 25;
    width:
           25;
    vertDistance: 200;
    horizDistance: 175;
    font: "9x15bold":
    label: "Push";
Methods:
    notify: {
      counter := counter + 1;
    }
}
```

Example 3-3 Dialogue Variables

Note in the example that Slang supports dynamic typing. That is, the variable counter is treated as an integer in the initial assignment and in the method, but is converted to a string for the assignment to label. Serpent automatically decides upon the appropriate type for an operation or an assignment and changes the type of a value as necessary.

Note, also, that the label attribute of the display object is dependent on the counter variable. Whenever counter is modified (in this case, as the result of a notify event), the label attribute is automatically updated by Serpent. In this manner, local variables can be used to express complex relationships between interaction object attributes.

The dependency concept is fundamental to the structure of Slang programs. Flow of information between portions of a Slang program is handled automatically based on the names used in variables and attributes. Thus, in Example 3-3, no explicit action is required by the user to communicate to Serpent the information that the label attribute of the display object depends on counter and that label should be recomputed whenever counter changes.

### 3.3 Data Dependencies

An important and powerful aspect of Slang is that it automatically supports dependencies between data items in the program. Certain data items, such as variables and interaction object attributes, may be dependent on other variable data within the dialogue. Whenever the data upon which these data items are dependent is modified, the data items are automatically updated.

All variable declarations and object attribute definitions are automatically a portion of the dependency system. Whenever a data item on the right-hand side of a variable declaration or an attribute definition is modified, the declaration or definition is recalculated. Consequently, new values are assigned to items on the right-hand side of the computation. Computations performed either within methods or within creation and deletion actions are not recalculated when an independent value is modified.

The automatic recalculation has the potential to introduce an infinite loop into a program. That is, if variable a is defined in terms of variable b and variable b is defined in terms of variable a, then an infinite loop within a program is created and the program will not execute as expected.

Data dependencies are determined for the total calculation of a variable or an attribute. That is, if the computation of an attribute is a complex statement, then the total computation is redone as a result of the triggering of a data dependency.

### 3.4 View Controllers

Interaction objects, their methods and attributes, and dialogue variables provide a great deal of power in defining relatively static interfaces, or interfaces that contain a fixed set of interaction objects for which only the attributes may change. Although this is a very powerful mechanism, it is not adequate to describe more complex interfaces where it is necessary to present and remove interaction objects as a collection from the display.

The mechanism by which objects are collected is a view controller. A view controller is used to group interaction objects and to control the circumstances under which they are presented to the end user. Interaction objects and local dialogue variables are defined within the context of view controllers. A view controller maps specific data in the application into objects on the display and controls the existence of these objects.

A dialogue is specified in terms of view controller templates. A template maintains a watch on application shared data or local dialogue data for specific conditions. When data that satisfies a view controller template is placed into application shared data or when local dialogue data attains certain values, a view controller is created.

In a Slang program, a view controller template is specified that has a collection of objects associated with it. When a view controller is instantiated from the template, the associated objects are created and communicated to the presentation layer. The presentation layer makes the objects visible to the end user.

A simple example of this is a drop-down menu. A drop-down menu consists of a menu bar that contains a number of options. Selecting an option causes a submenu to appear directly below the menu bar. Figure 3-3 illustrates a sample drop-down menu.




Figure 3-3 Drop-Down Menu

The drop-down menu can be implemented by using command widget interaction objects. Each menu item on the menu bar is represented by a command widget object. When a menu item is selected, additional command widget objects are displayed in order to produce the submenu.

View controllers have creation conditions that define the condition under which the view controller is instantiated. When a view controller is instantiated, the interaction objects defined for that view controller are displayed to the end user.

The Slang dialogue segment shown in Example 3-4 defines several interaction objects that make up the menu bar along with two dialogue variables.

The four objects that make up the menu bar are the: menu\_bar\_form, Menu\_1, Menu\_2, and Quit menu items. The menu\_bar\_form is a form widget that specifies the relative positions of objects within the form. The Menu\_1, Menu\_2, and Quit are command widgets that provide selectable menu headings for the menu bar. Besides these interaction objects, there are also three local variables defined: display\_menul\_submenu, display\_menu2\_submenu and display\_sub\_item\_submenu. These variables are initialized to FALSE and set to TRUE when their respective command buttons are selected.

```
#include "sat.ill"
\mathbf{H}
/*
** This demonstrates the use of Slang to produce
** a menu bar with two tear off menus.
** Initially, there is a menu bar presented to
** the user with two options: Menu_1 and Menu_2.
** Only Menu 1 is active. When the user selects
** Menu 1, a pull down menu will be displayed
** with additional items. When the user selects
** "Item 2 ->" another menu will be displayed.
** Each pull down has its own "Close" button and
** only affects that pull down menu. When the
** user selects the "Close" from the first pull
** down menu, the other pull down menu will
** remain on the display.
*/
Variables:
 display_menul_submenu : FALSE;
 display menu2 submenu : FALSE;
 display_sub_item_submenu : FALSE;
Objects:
menu bar form: XawBboard {
 Attributes:
    height:250;
    width: 250;
}
menu bar: XawBboard {
 Attributes:
    parent: menu bar form;
    height:200;
    width: 200;
    vertDistance:20;
    horizDistance: 20;
```

```
borderWidth: 3;
}
menul_item: XawCommand {
 Attributes:
   parent: menu_bar;
    vertDistance: 10;
   horizDistance: 10;
   height: 20;
    width: 50;
    label: "Menu_1";
Methods:
   notify: {
     display menul_submenu := TRUE;
}
menu2 item: XawCommand {
 Attributes:
    parent: menu_bar;
    vertDistance: 10;
   horizDistance: 60;
   height: 20;
    width: 50;
    label: "Menu_2";
Methods:
    notify: {
       display_menu2_submenu := TRUE;
    }
}
quit_menu_item: XawCommand {
 Attributes:
    parent: menu_bar;
    height: 20;
    width: 50;
    vertDistance: 10;
    horizDistance: 110;
    label: "QUIT";
Methods:
    notify: {
      exit ();
    }
}
/*
```

```
** menul view controller
*/
VC: menu1_submenu
Creation Condition: (display_menul_submenu)
Objects:
menul form: XawBboard {
 Attributes:
    parent: menu_bar;
    vertDistance: 30;
    horizDistance:10;
    borderWidth: 1;
    height: 65;
    width: 76;
}
iteml_menu_item: XawCommand {
 Attributes:
    parent: menul_form;
    vertDistance: 0;
    horizDistance: 2;
    height: 20;
    width: 70;
    borderWidth: 1;
    label: "Item 1";
}
item2_menu_item: XawCommand {
 Attributes:
    parent: menul form;
    vertDistance: 21;
    horizDistance: 2;
    height: 20;
    width: 70;
    borderWidth: 1;
    label: "Item 2 ->";
Methods:
    notify: {
       display_sub_item_submenu := TRUE;
   }
}
remove_menu_item: XawCommand {
 Attributes:
    parent: menul_form;
```

```
vertDistance: 42;
    horizDistance: 2;
    borderWidth: 1;
    height: 20;
    width: 70;
    label: "Close";
 Methods:
    notify:
      display_menul_submenu := FALSE;
   }
}
ENDVC menul submenu
/*
** sub_item_submenu view controller
*/
VC: sub_item_submenu
Creation Condition: (display_sub_item_submenu)
Objects:
sub_item_form: XawBboard {
Attributes:
    parent: menu_bar;
    vertDistance: 53;
    horizDistance: 88;
    borderWidth: 1;
    height: 65;
    width: 76;
itema menu item: XawCommand {
 Attributes:
    parent: sub_item_form;
    vertDistance: 0;
    horizDistance: 2;
    height: 20;
    width: 70;
    borderWidth: 1;
    label: "Item A";
}
itemb_menu_item: XawCommand {
 Attributes:
```

```
parent: sub item form;
    vertDistance: 21;
    horizDistance: 2;
    height: 20;
    width: 70;
    borderWidth: 1;
    label: "Item B";
remove_menu_item: XawCommand
Attributes:
    parent: sub_item_form;
    vertDistance: 42;
    horizDistance: 2;
    borderWidth: 1;
    height: 20;
    width: 70;
    label: "Close";
Methods:
   notify: {
      display_sub_item_submenu := FALSE;
}
ENDVC sub item submenu
```

### Example 3-4 Menu Bar

When a menu item is selected, the variable that caused the view controller to be instantiated is set to FALSE. Since the creation condition for the view controller is no longer TRUE, the view controller is destroyed and the interaction objects are removed from the display. Normally, the notify method for the menu items would perform some command-specific action, such as notifying the application of the selected command.

## 3.5 Shared Data

Often the dialogue specifier may need to display interaction objects to the end user based on the existence of a particular data item. An example is an application that provides a function to query an employee database. The end user may make multiple requests to view the data for several different employees at the same time.

To specify a user interface for this example, it is convenient to define a view controller that controls the presentation of an employee record. The creation condition for the view controller can then be based on the existence of a new employee shared data instance in the shared database. This is accomplished using the new function in the creation condition of the view controller.

Figure 3-4 illustrates the shared data definition for an employee record and three instances of the shared data element. These are added to the shared database directly from the dialogue or by the application as described in Serpent: System Guide.




Figure 3-4 Shared Data Definition

The creation condition defined in the view controller template shown in Example 3-5 is based on the existence of a new employee shared data instance in the shared database. The creation condition uses the new function that serves only as a test for existence, not the action to create anything. A separate instance of the view controller is created for each of the three employee shared data instances and added to the shared database; a separate set of interaction objects is created for each view controller.

```
VC: employee_info
Creation Condition: (new("employee"))
Objects:

name_field: XawText {
   Attributes:
     height: 20;
     width: 200;
     label: employee.name;
}
...
END VC employee_info;
```

**Example 3-5 View Controller Template** 

Each of these three view controller instances is *bound* to the shared data instance that caused it to be created. The dialogue specifier may then directly reference the specific values of each of the employee shared data instances within the scope of the view controller. For example, the label attribute of the name\_field interaction object illustrated in Example 3-5 is set directly to the name component of the employee shared data instance.

This example illustrates how Slang provides a mapping between application shared data and interaction objects. Remember, there are actually three different employee records in the shared database and three different sets of interaction objects on the display. Serpent provides a mapping between shared data instances and their corresponding interaction objects and maintains the relationship between them.

## 3.6 Dialogue Shared Data

Dialogue shared data is a mechanism that allows a dialogue to create, modify, and destroy instances of data without informing an application or a toolkit of the actions.

Slang provides predefined routines that allow for the creation and destruction of shared data elements from within the dialogue. To create dialogue shared data, the type and structure of the shared data must first be defined in a shared data definition file. The shared data definition file must be named dm. sdd. Refer to Serpent: Saddle User's Guide for further information on creating a shared data definition.

Dialogue shared data is used in exactly the same fashion as application shared data. It is treated as shared data conceptually and with the same mechanisms, but the data actually is local and not shared with anything. It is possible, for example, to instantiate view controllers from new instances of dialogue shared data and to access this shared data in the same manner as application shared data.

The exact syntax and semantics of the shared data routines are defined in Appendix E.

### 3.7 Actions ON CREATE and ON DESTROY

To specify actions to be performed whenever a view controller is created or descroyed, use ON CREATE and ON DESTROY respectively. These mechanisms provide a means for executing procedural code snippets at defined instances within the gialogue model. Actions specified conditionally with ON CREATE and ON DESTROY may be used, for example, to increment and decrement counters.

Actions ON CREATE and ON DESTROY also may be used for calculating aggregate functions such as the average salary of all the employees in the employee database. The Slang dialogue illustrated in Example 3-6 performs this function.

In Example 3-6, the variable average\_salary is defined to be total\_salary divided by employee\_count. Thus, average\_salary depends upon both total\_salary and employee\_count. When either changes, average\_salary is automatically changed. Thus, the view controller employee\_vc has no associated objects. Its only function is to increase or decrease employee\_count and total\_salary. The actual presentation to the user is through the object salary field.

```
Variables:
   employee_count: 0;
   total_salary: 0;
   average_salary: total_salary / employee_count;
/*
   ** if employee_count is 0, then average_salary
   ** becomes undefined
   */

Objecta:
salary_field: XawText {
   Attributes:
      horizDistance: 100;
      vertDistance: 100;
      height: 20;
      width: 200;
      label: average_salary;
```

```
VC: employee_vc
Creation Condition: (new("employee"))
On Create: {
  employee_count := employee_count + 1;
  total_salary := total_salary + employee.salary;
}
On Destroy: {
  employee_count := employee_count - 1;
  total_salary := total_salary - employee.salary;
}
END VC employee_vc;
```

**Example 3-6 Calculating Aggregate Functions** 

## 3.8 Dialogue Structure

A Slang dialogue contains the specification of a user interface for a single application. The dialogue contains information about the application shared data (and by implication, the application) and the toolkits that are associated with the dialogue. The structure of the dialogue is:

- · a list of application and toolkit shared data
- a list of view controllers used in the dialogue

The dialogue itself is always the outermost view controller and, consequently, all of the components of a view controller can be used in the dialogue as well as in explicitly declared view controllers.

The components of a view controller are:

- variables
- objects
- actions on CREATE
- actions on delete
- nested view controllers

Variable declarations serve two purposes: naming the variables for future reference and giving a definition of the variable which will be reevaluated whenever the independent variables in the definition are modified. The declaration of average salary in Example 3-6 shows the use of variable declarations as a constraint definition. Whenever total salary or employee\_count are modified, average\_salary is automatically reevaluated.

Objects declarations define the interaction objects that will be instantiated whenever a view controller instance is created. Each object that is declared has a collection of attributes that defines its presentation and a collection of methods that defines the response of the dialogue to end-user actions. Attributes are dependent on the variables that are used to define them (and consequently are reevaluated whenever the independent variables change), but methods are not a portion of the dependency analysis.

Actions ON CREATE and ON DELETE are code snippets that are executed once whenever a view controller is created (deleted). They are not subject to dependency analysis and are only evaluated when the relevant events occur.

Slang Overview

## 4 Lexical Elements

This chapter describes the lexical components of Slang, including the characters that may appear in a Slang dialogue and the lexical units or tokens that they may form.

### 4.1 Character Set

Characters used in a Slang dialogue may consist of any characters from the standard ASCII character set. Slang is not case sensitive, except for characters written within string constants, preprocessor commands, and comments.

There are also special characters that are used in Slang either to separate adjacent tokens for the preprocessor or to format Slang dialogue text in a string. These characters include a blank space, end of line, formfeed, and horizontal tab.

Line termination is also a special character, but is generally ignored in Slang. It is important, however, in the recognition of preprocessor control lines, where the first character of the line must be a "#" character. The character following a line break character is considered the first character of the next line.

### 4.2 Comments

Comments begin with the characters /\* and end with the first subsequent occurrence of the characters \*/. Comments, which are removed from the Slang program by the Slang preprocessor before a Slang dialogue is compiled, cannot be nested. For example, the following line:

```
/* /* Slang Source Commentary */
```

would be treated as a single comment and would generate a compiler error.

Another way to comment out dialogue lines is to use the preprocessor's conditional commands. For example the following lines:

```
#if 0
#endif
```

would effectively comment out any section of the dialogue, including nested comments. For more information about the preprocessor refer to Chapter 12.

### 4.3 Tokens

The characters making up a Slang program are collected into lexical units called *tokens*. Tokens are the smallest lexical units that are recognized by the Slang compiler. When collecting characters into tokens, the Slang compiler always forms the longest token possible. For example, vc\_fred is interpreted as a single identifier instead of the reserved word VC followed by the identifier \_fred.

Adjacent tokens must be separated by white space or comments. In a macro body, separating tokens with comments rather than white space will cause the tokens to be merged. For example,

```
#define concat(x,y)
x/**/y
concat(A,B) => AB
```

Slang tokens are case insensitive, except for string constants. This means, for example, that the identifiers Fred, fred, and FRED are the same.

There are five classes of tokens in Slang: operators, special characters, identifiers, reserved words, and constants. Each of these classes is discussed in the following sections.

NOTE: Tokens that appear together in Slang, such as Creation and Condition, are accepted with or without a separator character. For example, Creation condition and Creation Condition are both legal.

### 4.3.1 Operators and Special Characters

Slang has operators and special characters. Each operator has an associated precedence level that controls the order of operations in an expression. If parentheses are not used to indicate the grouping of operands with operators, the operand is grouped with the operator that has the higher precedence. For example, a + b \* c would be grouped as a + (b \* c).

Relative Precedence	Operator	Description
9	names, literals	simple tokens
8	func()	function call
8	•	component selection
7	not	logical negation
7	-	arithmetic negation
6	**	exponentiation
5	*,/	multiplicative

4	+, -	additive
3	<,>,<=,>=	relational
2	<b>=</b> , <b>&lt;&gt;</b>	equality/inequality
1	and, or	logical
0	:=	assignment

Slang supports the following special characters;

- # delineates preprocessor instructions
- identifies an escape character inside of text used for output
- { } delineates blocks of code
- separates parameters in a function call
- ; terminates a statement
- : declares an attribute or variable

### 4.3.2 Identifiers

An identifier is a sequence of letters, digits, and underscore characters. An identifier cannot begin with a digit or an underscore and cannot have the same spelling as a reserved word. Identifiers may be of any length.

### 4.3.3 Reserved Words

The following are reserved words in Slang and may not be used as identifiers:

- AdiMethods
- AndNot
- AttributesNull
- Boolean Objects
- BufferOn Create
- CreateOn Destroy
- Creation ConditionOr
- DoReal
- ElseSelf
- ElsifString

#### Lexical Elements

- · End IfThen
- · End VcTrue
- · End WhileUndefined
- ExitVariables
- FalseVc
- · IdVoid
- · IfWhile
- · Integer

#### Table 4-1 Reserved Words

#### 4.3.4 Constants

Constants are lexical elements that are characterized by having both a value and a type. There are four types of user-definable constants in Slang: boolean, integer, real, and string. There is also a system-defined type of constant which is an id.

There are also five predefined constants: Undefined, Null, True, False, and Self.

### 4.3.4.1 Integer Constant

An integer constant consists of a sequence of digits, 0-9. An integer constant may optionally include a leading + or -. Integer constants may not include commas or other non-digit characters. Examples of integer constants are: 1989, 0, and 1.

#### 4.3.4.2 Real Constant

A real constant consists of a sequence of digits containing a single decimal point character. A real constant may optionally include a leading + or –. Examples of real constants are: .5, 1989., and 3.14.

### 4.3.4.3 String Constant

String constants consist of any arbitrary text delimited by double quotes. Examples of string constants are: "Fred," "1989," "string examples," and "\$%^&".

String constants may also contain character or numeric escape codes. Escape characters are used to either represent characters that would be awkward to enter directly or to represent some particular formatting.

Escape characters consist of the backslash character followed by a character escape codes. Table 4-2 lists the character escape codes used in Slang.

**b** backslash

\f form feed

\n new line

x carriage return

\t horizontal tab

\\ backslash

### **Table 4-2 Character Escape Codes**

Numeric escape codes allow any character to be expressed by writing its octal code in the target character set. For instance, using the ASCII character set, the character a may be written as \141 and the NULL character as \0. Numeric escape codes terminate when either three characters have been read or a non-octal character is encountered. For example, the string \0111 consists of two characters: the character corresponding to octal code 011 and the character 1. The string \operatorname{0}80 consists of three characters: the character corresponding to octal code 0 and the literal characters 8 and 0.

### **Predefined Constants**

The UNDEFINED constant is used to represent a distinguished value which is recognized as undefined.

The NULL constant is an ID constant. It is used to specify that a given ID, while not undefined, does not identify any specific data item. The Null constant may be used, for example, to identify the end of a list.

The Self constant is an ID constant that is used to specify the ID of the current view controller or object, whichever is the local context.

Lexical Elements

## 5 Data

A Slang dialogue can be thought of as a mapping between application data and interaction objects. As such, the ability to declare and manipulate data in Slang is crucial to developing a dialogue. This chapter describes the different kinds of data that can exist in a Slang dialogue and how to declare and reference those data.

### 5.1 Different Forms of Data

Slang recognizes three forms of data:

- 1. Entities. These are data items such as shared data, Vc, Object, Variable, Attributes, and Methods, which have a predefined meaning within a Slang dialogue. Some entities have names (shared data, Vc, object, and Variable) and some have components that have names (shared data components, Attributes, and Methods).
- 2. Object type. This is the declaration type of an object entity. Each object is declared to be of a type. Admissible types are defined by the particular toolkits that have been included into a Slang dialogue. For example, an object can be declared to be a xawCommand widget. XawCommand is a type which is defined within the Athena Widget binding to Serpent.
- 3. Data type. This is the type of the value of shared data components, attributes, and variables. Components of application shared data, components of dialogue shared data, attributes, and constants all have fixed type. The type of a shared data component is specified in the shared data definition, the type of an attribute component is specified by the toolkit integrator, and the type of a constant is determined at compile time. Each variable has a dynamic data type that is determined at runtime for each assignment of value to the variable. The data value of a data type is its current value.

## 5.2 Assignment of Values to Data Types

When a data value is assigned to something with a fixed data type, its value is converted (if possible) to the fixed type. Appendix C presents the allowable conversions. When a data value is assigned to a variable (with dynamic type), the new type of the variable becomes the type of the data value.

For example, if year has a fixed data type of integer, the following assignments will yield equivalent values for year.

```
year := "1984"; year := 1984;
```

### **Example 5-1 Automatic Conversion**

Alternatively, if year has dynamic type, the first assignment will result in a value typed as string and the second will result in a value typed as integer.

## 5.3 Object Types

An object is the only data item that has an object type. Variables, attributes, and shared data items have data types. Data types are discussed in more detail in the following paragraphs.

## 5.4 Data Types

Data items in Slang have either fixed or dynamic data type. For fixed data type, the type of the data item is determined at compile time. For dynamic data types, the type is determined dynamically at runtime. Examples of data items with fixed type are dialogue, application shared data, and object attributes. The only data items with dynamic type are dialogue variables.

Although fixed data types cannot change type, it is possible to assign data of a different type to a fixed data type if there is an appropriate conversion. This automatic conversion is illustrated in Example 5-2 The value 1984 is automatically converted to an integer so that it can be stored as the fixed typed integer 1984.

```
year : integer; (described in Saddle file)
year := "1984";
```

### Example 5-2 Fixed Data Type

Alternately, dynamic type data items can change type dynamically at runtime. In Example 5-3, the variable year is set to the integer value 1. This means that the type of the variable is set to integer and the value assigned is 1. In the following line, when the value 1984 is assigned to the variable, the type of the variable is set to string and the value is assigned 1984.

```
year := 1;
year := "1984";
```

Example 5-3 Dynamic Data Type

## 5.5 Base Types

There are six base data types supported in Serpent. These types are defined in Table 5-1. For more detailed information refer to Serpent: Saddle User's Guide.

Type	Description
boolean	true, false
integer	32 bits, from $-2^{31}$ to $2^{31}$ -1
real	64 bits, approximately 15 significant figures
string	variable length to maximum specified in Saddle
	description
id	data item identifier
buffer	n bytes of data together with length and type identifier

Table 5-1 Base Types

## 5.6 Dependency

An extremely important concept in Slang, dependency is one of the main ways in which the state of a Slang dialogue is modified at runtime.

A data item in Slang is dependent on another data item when the expression or code snippet (see Chapter 7) corresponding to the former data item references the latter. For example, if the variable x were assigned the value 2 \* y in the declaration statement, x would be automatically reevaluated whenever y changed. Expressions that are used in the evaluation of attributes of objects or in the declarations of variables are reevaluated whenever the independent variables in those expressions are modified. The independent variables can be either variables, attributes, or shared data components.

Data dependencies are determined dynamically at runtime. In Example 5-4, if the value of w is true, x is dependent on y and the expression will only be reevaluated if y changes or if w changes. If the value of w becomes false, then the expression would be dependent on z and will only be reevaluated if z or w changes. Determining dependencies dynamically helps to optimize runtime performance by reducing the situations in which the reevaluation of variables and attributes is necessary.

```
x: {
If (w) Then
  x := y;
Else
  x := z;
End If;}
```

### **Example 5-4 Dependency Propagation**

It is possible when doing runtime dependency propagation to have infinite loops in dependent calculation. Potentially infinite loops within a Slang program are dealt with in one of two ways, depending upon how many snippets are used in the loop. The granularity of dependency calculations is at the snippet or expression level. That is, a snippet is determined to be dependent upon particular data items during execution. An infinite loop is suspected to exist (and execution is terminated) when a particular snippet is evaluated a number (currently 10) of times for the same data items. In Example 5-5, where variable var1 is dependent upon variable var2 and vice versa, the definitions are two independent snippets.

```
var1: var2;
var2: var1;
```

#### Example 5-5 Multiple Snippet Infinite Loop

There are cases in which it is possible to have a snippet dependent upon a variable that is also defined within the snippet. In these cases, the runtime system does not propagate dependencies. In Example 5-4, the snippet used in the definition of x depends upon the value of x (from the boolean expression "x = y"). The snippet also modifies the value of x. Thus, if snippets were always reevaluated when the independent value is modified, the definition of x would cause an infinite loop. Because, however, dependency granularity is at the snippet level, this snippet is treated as a dependency on x, but not as a modification of x. If x is modified from outside this snippet, the declaration is reevaluated but it is not reevaluated as a result of the modification of x from within the snippet.

```
x: {
If (x = y) Then
   x := y + 1;
Else
x := y;
End If; ?
```

Example 5-6 Snippet Dependent On Defined Variable

Example 5-7 shows another potential infinite loop. In this case, the variable temp is referenced within the snippet (from the second statement). Thus, if the granularity were at the statement rather than the snippet level, an infinite loop would result the second time the snippet is executed (the snippet depends upon the variable temp and temp is modified by the first statement in the snippet). Because the granularity is at the snippet level, this case is treated as a modification of temp but not as a use of temp. That is, if temp is modified, the snippet is not reevaluated and no infinite loop results.

```
temp := 3 * var1 + var2;
x := temp * temp;
```

Example 5-7 Snippet Dependent On Variable Both Modified and Used

#### 5.7 Scope and Visibility

The scope of a data item in Slang is the set of statements and expressions in which the use of the identifier is associated with that particular data item. Slang supports block structured scoping in a fashion similar to that of programming languages such as Pascal.

Scopes are defined by view controllers and interaction objects. This could be alternately stated by saying that view controllers and interaction objects provide context for data items. Within the context in which they are defined, data items are said to have local scope. With respect to the other children of the parent, data items are said to have global scope. All data items declared in the same context must have unique names.

Data items are said to be visible if the identifier for that data item can be associated with the value. Data items are typically visible within their scope unless they are hidden. Hiding occurs when a data item having local scope has the same name as a data item with global scope.

The dialogue itself can be thought of as a view controller with a creation condition of true. Data items declared at the topmost level of the dialogue are then local to the dialogue and global to all other view controllers defined within the dialogue.

The following example illustrates the concepts of scope and visibility within Slang in terms of an abstract block structured language. The blocks can be thought of as being either view controllers or interaction objects in Slang.

```
VC: A
Variables:
 x:
 y;
 VC: B
 Variables:
    x;
    z;
 On Create: {
                          /* assigns B.x */
   x := 1;
                          /* assigns A.y */
    y := 2;
    z := 3;
                           /* assigns B.z */
 END VC B;
 VC: C
 On Create: {
    z := 1; /* illegal */
 END VC C;
END VC A;
```

### Example 5-8 Scope and Visibility in an Abstract Block Structured Language

In this example, view controllers B and C are defined inside the context of view controller A. Since both x and y are declared within view controller A, they are considered to be local to A and global to both B and C. Data items declared within view controller B or C cannot be referenced from view controller A since they are outside the scope of A.

There are three assignment statements within view controller B. The first assignment assigns the value of 1 to data item x declared in view controller B. This is because the name of the data item (y in this case) is hiding the identically named data item declared in view controller A. The second assignment assigns the value of 2 to the data item y declared in view controller A. The assignment of the value of 3 to data item z is a simple assignment to the data item declared locally in view controller B.

The assignment in view controller C of the value of 1 to data item z would be an error condition since data item z is outside the context of view controller c and will result in a compiler error message.

Data items can be referenced outside their scope if they exist and the exact path is known. A path is a description of the location of a data item in the dialogue structure. Referencing data using a path is described in Section 5.9.

### 5.8 Extent

The extent of a data item refers to the period of time for which storage is allocated for the data item. Data items in Slang may have either local or dynamic extent.

A data item with local extent is created at the same time as either a view controller or an interaction object. Examples of data items with local extent are variables and object attributes.

Data items with dynamic extent may be created or destroyed at any time by either the dialogue or application program. Only shared data has dynamic extent.

### 5.9 Data Access

Each instance of a named entity in a Slang program (view controller, variable, object, and shared data element) is assigned a Serpent identifier when the instance is created. This identifier is of type ID. The identifier, for the most part, is unnecessary for the Slang programmer since the data items are within the scope of their use and can be referenced directly by name. It is possible, however, to reference data items by using their identifier. This is a useful feature when it is necessary to access a value that is out of the current context. Values of variables, attributes of objects, and shared data components can be set or retrieved through the use of the data access routines described in Appendix E.

Several different methods exist to determine the identifier for a data object:

At creation time: The creation of a shared data element through use of the create\_sd\_instance returns an identifier for the shared data element that has been created.

Special functions:

The function get\_parent\_vc returns the identifier of a view controller.

The function get\_object returns the identifier of an object within a view controller.

The special SELF constant can be used to refer to the identification of objects, variables, and view controllers:

- When used within an object attribute or method specification, SELF refers to the ID for that object.
- When used within a variable specification, SELF refers to the ID for that variable.

 When used within the actions on create or destroy code snippets, SELF refers to the ID of the enclosing view controller.

The use of data access routines to set or retrieve identifiers or values requires explicit knowledge of the access path to the data item from the current context and, consequently, should only be used when absolutely necessary. For example, the addition of an intermediate view controller may change the access path from one compilation to another and a section of code that worked correctly prior to the addition may no longer work correctly.

### 5.10 Declared Data

This section describes data types that are declared within the dialogue.

### 5.10.1 View Controllers

View controllers serve two functions. At runtime, they provide a visibility mechanism for a collection of objects. When an instance of a view controller is created, those objects declared within the view controller are created and are thus made visible to the end user.

At compile time, view controllers provide context for variables, interaction objects, and bound shared data instances. A shared data instance is bound to a view controller when the creation condition for the view controller references the shared data element and the creation condition becomes true.

View controller instances are data items within a dialogue that have unique instance IDs. View controller IDs can be obtained using either the SELF constant or data access routines and can then be used to reference data items within the dialogue using the data access routines.

#### 5.10.1.1 Declaration

A view controller may be referenced directly within its scope using the name of the view controller.

### 5.10.1.2 Extent

Variables have local extent. This means they exist only for the period of time in which the view controller instance that contains them exists.

### 5.10.1.3 Scope

Variables have local scope within the view controller in which they are declared and global scope within the subview controllers of that view controller. Being in scope within a view controller (whether local or global) means that the variable can be referenced within objects, subview controllers or variables declared within the view controller. Thus, in Example 5-8, variable y can be referenced from anywhere within View Controller A.

The order of declaration of variables is unimportant. Assume x is declared to be y + 1 and y is declared to be 10. If the declaration of x precedes the declaration of y, x is initially evaluated to be undefined and then y is evaluated to be 10. The evaluation of y changes an independent variable in the declaration of x and, consequently, x is reevaluated to be given the value 11.

### **5.10.2** Objects

Object declarations within Slang are templates that are instantiated when a particular view controller is instantiated. Object instances are data elements and have unique instance identifiers. Object identifiers can be determined using the SELF constant or data access routines. Objects provide context for attributes.

An object may be referenced directly within its extent, using its name.

Objects have the extent of the containing view convoller. When the view controller is instantiated, an instance of the object is created and when the view controller is destroyed, the instance is destroyed.

#### 5.10.3 Attributes

Attributes are used to define the presentation characteristics of interaction objects.

Attributes are similar to shared data components in that they have fixed type. The type of the attributes is defined by the toolkit integrator.

An object attribute is declared to be either an expression or a code snippet in which the attribute is assigned (similarly to variables). The declaration generates a set of dependencies that are associated with the attribute. Every time any of the data items referenced in the declaration is modified, the attribute is reevaluated.

### 5.10.3.1 Type

An object attribute has a fixed type, either boolean, integer, real, string, buffer, or ID. Since

attributes are used to communicate with input/output toolkits, the values of attributes also have semantic meaning that is defined by the toolkit.

#### 5.10.3.2 Extent

Attributes are created and destroyed with the object in which they are declared.

#### 5.10.3.3 Scope

The scope of an attribute is limited to the object in which it is defined. Attributes may also be accessed from outside their scope if the exact path is known.

### **5.10.4** Methods

Methods provide a way of handling end-user interactions by specifying actions to be performed for specific end-user generated events. Each object type has a fixed collection of valid methods declared by the toolkit integrator. Methods are executed once for each enduser generated event.

### 5.10.5 Shared Data

Shared data is information that is communicated between the application and dialogue, solely within the dialogue, or between the dialogue and a toolkit. It consists of instances of shared data templates. Shared data is segmented: each application process communicating with Serpent has a segment, the dialogue has a segment, and each toolkit being used has a segment. The application segments are called application shared data, the dialogue segment is called dialogue shared data, and the toolkit segments are called toolkit shared data. The Slang programmer does not access toolkit shared data directly. Instead, the Slang programmer manipulates objects, object attributes, and methods; Serpent handles these objects internally through shared data.

Shared data resides in the shared database, is defined externally in a shared data definition file, and is instantiated at runtime by either the application or dialogue. Application and dialogue shared data instances can be bound to a view controller. A shared data instance is bound to a view controller when two conditions exist:

- 1. The creation condition for the view controller references the shared data element.
- 2. The creation condition is true.

### 5.10.5.1 Type

Shared data is different from dialogue internal data items in that it is declared externally to the dialogue. The type and structure of shared data is defined in a shared data definition file. A separate shared data definition file must be created for each Serpent application as well as for dialogue shared data.

A shared data definition file consists of aggregate data structures. The aggregate structures are referred to as *shared data elements*. Elements have components, each of which is declared to be one of the primitive types of Slang.

See Serpent: Saddle User's Guide for a complete description of shared data definitions.

#### 5.10.5.2 Extent

Shared data has dynamic extent. It is created by either the application or dialogue and exists until it is explicitly destroyed.

#### 5.10.5.3 Scope

The scope of a shared data instance includes any bound view controllers and any interaction objects and/or subview controllers defined within the scope of that view controller. Shared data items may be referenced directly within its scope using the name of the element or component.

Shared data can also be referenced from anywhere in the dialogue, if the ID is known, using the shared data routines defined in Appendix E.

### 5.10.6 Dialogue Shared Data

It is often useful in dialogue specification to be able to instantiate multiple instances of local data. For example, it is possible to create a dialogue without an application for prototyping purposes and, subsequently, to add the application. In such a situation, application shared data cannot exist because there is no application.

Dialogue shared data is like application shared data in that it is defined externally in a shared data definition file, can have view controllers bound to it, and must be explicitly instantiated and destroyed. It differs from application shared data only in that it is kept locally in the dialogue and not communicated to any external process.

The shared data definition file used to declare dialogue shared data must be named dialogue\_name.sdd, where dialogue name is the name of the file containing the dialogue, and the file name must be included in the prologue section of the Slang dialogue (see Section 9.5.1 for a discussion of prologues).

Dialogue shared data can be instantiated at runtime using the create sd instance function described in Appendix E. The create\_sd\_instance function returns a unique Serpent identifier that is used to reference, and later destroy, the shared data instance. In Example 5-9, the shared data element dial elem sd is instantiated and the identifier stored in dial elem id.

```
dial_elem_id := create_sd_instance("elem_name", "DM_BOX");
```

### Example 5-9 Dialogue Shared Data Creation

The dialogue shared data element may be destroyed using the destroy sd instance function show in Example 5-7.

```
destroy_sd_instance(dial_elem id);
```

### **Example 5-10 Dialogue Shared Data Destruction**

### 5.10.7 Application Shared Data

Application shared data is used to communicate between the dialogue and an application. Shared data instances can be created by the application and communicated to the dialogue or created in the dialogue with the arcallo and instance function (described in Appendix E) and then communicated to the application.

Application shared data is specified using Saddle and is specific to an application. These concepts are discussed in detail in Serpent: C Application Developer's Guide, Serpent: Ada Application Developer's Guide, and Serpent: Saddle User's Guide.

### 5.11 Data Reference

In order to understand how data is referenced in a Slang dialogue, it is important to understand the dialogue structure.

### 5.11.1 Dialogue Structure

Dialogues have both a static specification-time structure and a dynamic, runtime structure. At specification time, the dialogue structure is a hierarchical tree of view controller and object templates. This static structure can be thought of as being the dialogue tree skeleton. At runtime, some of the templates have been instantiated (possibly multiple times). The runtime dialogue structure then consists of this tree skeleton plus whichever nodes on the tree skeleton have been instantiated. Since view controllers can instantiate multiple times, there may be multiple instances of the various nodes associated with a particular node on the skeleton. Each node in the dynamic structure has a unique path from the base of the structure.

Data reference can be performed in Slang using both direct and indirect referencing. The following subsections describe how each of these data referencing mechanisms are used.

### 5.11.2 Direct Reference

Data items in the dynamic structure can be referenced directly by path name from within their scope. The scope rules can be thought of as allowing upward referencing within the instance tree (as long as a name is not overloaded).

A path name consists of a series of tokens separated by the "." symbol. The first symbol is considered the anchor, and determines the location from which the remainder of the path is determined. The anchor is bound to the first data item encountered in the dialogue structure, starting with the current context and working towards the dialogue base. Each of the following tokens must be defined in the context of the preceding token or a syntax error will occur. The rightmost token is the name of the actual data item being referenced.

The following are examples of referencing data using pathnames:

```
a_vc.a_subvc.a_variable
visible_vc.presentation_object.attribute
employee.name
```

**Example 5-11 Direct Reference** 

#### 5.11.3 Indirect Reference

Occasionally, it is necessary to reference other than upward in the instance tree. In this case, the Serpent identifier of the particular data item to be referenced must be determined. Once the identifier has been determined, the value of the data item can be set or retrieved using the data access and shared data routines defined in Appendix E.

In order to use indirect referencing, the identifier of the data item must be determined. A technique to use is to have the data item retrieve its identifier and save it in a variable within scope of the location where it is to be referenced. Example 5-14 shows a use of this te hnique.

### 5.11.4 Examples of Data Reference

To better illustrate data reference in Slang, some further examples from the employee database application are presented in this section. These examples assume two different shared data elements: one contains basic employee information and the other has information from the employees' previous reviews. These shared data records, specified in Saddle, are illustrated in Example 5-12.

```
employee: record
             string[50];
name:
address:
             string[50];
             string[10];
phone:
salary:
             integer;
end record;
review: record
name:
             string[50];
             id type; /*id of employee data element*/
ptr:
year:
             integer;
             string[50];
last_raise:
level:
             string[20];
end record;
```

**Example 5-12 Employee Shared Data Definitions** 

The requirement is to provide a dialogue that will examine the database of employees and review information and display an employee bonus. Two dialogues (Example 5-13 and Example 5-14) show how to accomplish this function.

Example 5-13 is written using nested view controllers. The creation condition of employee\_vc is based on the existence of a new employee shared data instance in the database. The sub-view controller review\_vc is then created when a review shared data instance is found for the specified employee with a date field value of 1989. In this example, it is possible to directly reference shared data information from both the employee and review shared data instances from within the review\_vc view controller to determine the employee bonus. Data references are automatically bound to the correct shared data instance of both shared data instances. The top level view control is instantiated whenever a new employee is added to shared data. The nested view controller is instantiated whenever a new review is added to the shared data that describes the employee referenced in the top most view controller. Thus, in the second view controller there are two conditions: one to add a new review to the shared data and the other to insure that the correct employee is referenced.

```
VC: employee vc
Creation Condition: (new("employee"))
Variables:
                 /*local variable is initialized*/
 name: employee.name;
 VC: review vc
 Creation Condition:
    (new("review"and name = review.name)
 Objects:
 due for raise: label widget {
 ** omit most attributes
 */
 label {
    If (employee.salary < 20000)</pre>
      review.level = "superstar")
    Then
      label := "Merry Xmas.";
      label := "Forget it.";
   End If;
END VC review vc;
END VC employee vc;
```

Example 5-13 Direct Data Referencing

In the second version of this problem, Example 5-14, a single view controller is used for the solution. The assumption is that the application places the Serpent identifier for the correct employee shared data instance into the ptr component within the review element. The creation condition for the single view controller causes a new view controller to be created whenever a new record element is added with the desired year. The ptr component within the review element is used to reference the correct employee. Data access routines must be used to reference the values.

```
VC: review vc
Creation Condition:
 (new("review") And review.date = 1989)
Objects:
due_for_raise: XawLabel {
Attributes:
** omit most attributes
*/
label: {
 If(employee[review.ptr].salary < 20000)</pre>
    review.level = "superstar")
 Then
    label := "Merry Xmas.";
 Else
    label := "Forget it.";
 End If;
 }
END VC review_vc;
```

Example 5-14 Indirect Data Referencing

Data

# 6 Expressions

Slang supports a standard set of unary and binary operators. Expression operands may have any underlying type (see Chapter 5). The resulting type and value of the expression is a function of both the operator and the type and value of each operand. The type results and conversions tables in Appendix C define the exact conversions that are performed at runtime. In general, operations on different types first try to coerce the types to integer, real, and string, in that order, in order to perform the operation. If no conversion can be performed then a runtime error occurs.

### **6.1 Undefined Values**

Slang allows values of data items to be undefined. When an undefined value is used in an expression, the undefined value propagates outward during expression processing. For most operations, whenever an operand value is undefined, the resulting value is also undefined. The only exception is the equality operation in which two undefined operands are treated as being equal.

## 6.2 Logical AND and OR Operators

The logical AND and OR operators are used to provide logical operations on boolean values. Logical operators are not defined for anything other than boolean values and UNDEFINED.

A complete formal syntax for expressions is given in Appendix A. The following is the formal syntax for logical AND and OR expressions:

```
expression ::=
[expression logical_operator] boolean expression
logical operator ::=
And
1 '&'
1 Or
1 1/
```

Logical operations can return one of three values: true, false, or undefined. The following tables contain the values of logical operations.

AND	false	true	undefined
false	false	false	undefined
true	false	true	undefined
undefined	undefined	undefined	undefined

**Table 6-1 AND Operations** 

The value of the first argument is read down the left column, the value of the second argument is read across the top, and the value of the result can be determined by finding the indicated entry in the table.

OR	false	true	undefined
false	false	true	undefined
true	true	true	undefined
undefined	undefined	undefined	undefined

Table 6-2 OR Operations

The value of the first argument is read down the left column, the value of the second argument is read across the top, and the value of the result can be determined by finding the indicated entry in the table.

## 6.3 Equality Operators

The equality operators are used to determine whether two data items are equal or not equal to each other. Data items can be compared for equality if both data items are of the same type or can be converted to the same type. Data items are considered equal if they have the same value in type to which they are converted. The following operators are used for comparing expressions

<=	equal	
<>	not equal	

**Table 6-3 Equality Operators** 

The following is the formal syntax for equality expressions:

```
boolean expression ::=
[boolean_expression equality_operator] relational_expression
equality operator ::= '=' | '<>'
```

Equality operations can return one of two values: true or false. The following are some examples of eq ality comparisons

Operation	Value
1 = 5	false
"7" = 7	true
3.4 = 3	false
3 = 3.0	true
5<> UNDEFINED	true
"Fred" = "Tom"	false

**Example 6-1 Equality Comparison** 

All operands of the same type can be compared for equality or inequality. In general, operands of mixed type may be compared when there is a defined conversion between the types. ID operands can only be compared with other ID operands. The exact semantics of equality operations is defined in Appendix C.

## 6.4 Relational Operators

Relational operators are used to compare two data items to determine their relative values; that is, if one data item has greater or lesser value than the other. Relational operators can only be used to make numerical comparisons. They cannot be used, for example, to alphabetize a list. Strings can only be compared if they can first be converted to a numerical type.

The following operators are used for comparing expressions:

less than <= less than/equal greater than greater than/equal

**Table 6-4 Relational Operators** 

The following is the tormal syntax for relational expressions:

```
relational_expression ::=
[relational_expression relational_operator]
arithmetic_expression
relational_operator ::= '<' | '<=' | '>' | '>= '
```

Relational operations can return one of three values: true, false, or undefined. The following are some examples of relational comparisons.

Operation	Value
1 < 5	false
"7"> = 7	true
3.4 > = 3	true
3 < = 3.0	true
5 > UNDEFINED	UNDEFINED

**Example 6-2 Relational Comparison** 

Operands used in relational operations must be either integers or real numbers or convertible to these two types. When one or both operands used in a relational operation is UNDEFINED, the result of the operation is also UNDEFINED. The exact semantics of relational operations are defined in Appendix C.

## **6.5** Arithmetic Operators

Arithmetic operators provide basic math functions. Arithmetic operations are only defined for numerical values. They cannot be used, for example, to add or concatenate strings. Arithmetic operations on strings are performed by converting the strings to a numeric type and then performing the arithmetic.

The following arithmetic operators are used for performing arithmetic operations on expression pairs.

Operator	Operation
+	addition
-	subtraction
*	multiplication
/	division
* *	exponentiation

**Table 6-5 Arithmetic Operators** 

Addition and subtraction have lower precedence than multiplication and division, which in turn have lower precedence than exponentiation. The following is the formal syntax for arithmetic expressions:

```
arithmetic_expression ::=
[arithmetic_expression addition_operator] term
term ::=
  [term multiplication_operator] factor
factor ::=
  [factor '**'] signed_id
arithmetic operator ::= '+' | '-'
multiplication_operator ::= '*' | '/'
```

Arithmetic operations can return values of two types: integer or real. They may also return UNDEFINED if either of the operands is UNDEFINED. The following tables give the type of arithmetic operations:

+,-,*,**	real	integer	undefined
real	real	real	undefined
integer	real	integer	undefined
undefined	undefined	undefined	undefined

Table 6-6 Plus, Minus, Multiple and Exponential Operations

/	real	real	undefined
real	undefined	undefined	undefined
integer	real	real	undefined
undefined	undefined	undefined	undefined

**Table 6-7 Divide Operation** 

The exact semantics of arithmetic operations are defined in Appendix C. The following are some examples of arithmetic operations:

Operation	Value
1 + 5	6
<b>"7" *</b> 8	56
3.4 - 3	0.4
3 + 3.0	6.0
5/ UNDEFINED	UNDEFINED

**Example 6-3 Arithmetic Operation** 

# **6.6 Unary Operators**

There are two unary operators in Slang: unary negation and logical complement. Unary negation is used to negate a single, numeric operand. Logical complement is used to negate a single, logical operand. It is only defined for boolean values and undefined.

```
unary_operator ::=
    NOT
    '-'
```

**Table 6-8 Unary Operators** 

The following is the formal syntax for unary expressions:

```
signed_id ::=
[ unary_operator ] id
unary_operator ::=
NOT | '-'
```

Unary negation can return values of two types: integer or real. Unary negation also returns an UNDEFINED value when the operand is undefined. Logical complement can return one of three values: true, false or UNDEFINED. The following are examples of the unary operations:

Unary Operations	Types
-5	integer
- "3.14"	real
-UNDEFINED	UNDEFINED
not true	false
not UNDEFINED	UNDEFINED

**Table 6-9 Unary Operations** 

# 7 Code Snippets and Statements

A code snippet is a fragment of procedural code within a dialogue specification that is executed in response to specific conditions. Code snippets are used to specify actions on create, actions on destroy, object attributes, object methods, and variable declarations. A code snippet consists of a collection of Slang statements.

The following is the formal syntax for code snippets:

```
code snippet :: = '{' [statements] '}'
statement :: =
function call |
assignment statement |
conditional statement |
loop statement
```

Slang statements are all terminated by the semicolon character.

#### 7.1 Function Call

A function call is a transfer of control to a procedure that exists outside of the Slang language but within the Serpent runtime system. Functions in Slang may or may not return a value but must not modify any of the actual parameters to the function. A function call may be a statement by itself (an imperative statement) or it may be a component of an expression. Predefined functions are defined in Appendix D and Appendix E.

The following is the formal syntax for imperative statements and functions:

```
function call ::=
function_name '(' [expressions] ')'
expressions ::= {expression ','} expression
```

The following are some examples of function call statements:

```
destroy sd instance(id);
put_variable_value(vc_id, "fred", 17);
```

**Example 7-1 Function Call Statements** 

# 7.2 Assignment Statement

The assignment statement is used to set the value, and possibly type, of the data item on the left-hand side of the assignment operator to the value and type of the expression on the right-hand side of the operator.

The following is the formal syntax for assignment statements:

```
assignment_statement ::=
qualifed name \':=' expression
```

The following are some examples of assignment statements.

```
a := "string";
a := 7;
id := create_sd instance(element name);
```

**Example 7-2 Assignment Statements** 

When the named identifier on the left-hand side of the assignment statement corresponds to a dialogue variable, both the type and value of the variable are set to the type and value of the expression. When the identifier corresponds to a shared data item or an object attribute, the value of the expression is converted to the type of the shared data item or attribute. The exact semantics of the assignment operation when the left-hand side of the statement is a shared data element or object attribute is defined in Table 12-3.

## 7.3 Conditional Statement

The conditional statement is used to provide optional execution of statements.

The following is the formal syntax for If statements:

The following are examples of If statements:

```
If (a > 0) Then
value = "positive";
Elsif (a = 0) Then
 value = "zero";
Else
value = "negative"
End If;
If (b > 5) Then
printf("b greater than five.");
Elsf (b > 0) Then
 printf("B greater than zero but less than five.");
End If;
```

**Example 7-3 Conditional Statements** 

When evaluating a conditional statement, the condition after the IF part and any conditions after the ELSIF parts are evaluated in lexical order (treating the final ELSE as an ELSIF true THEN) until one of the conditions is true or all the conditions are false. If one of the conditions evaluates to true the corresponding statements are executed; otherwise, none of the statements is executed.

# 7.4 Loop Statement

The loop statement is used to perform controlled iteration of Slang dialogue statements. All of the statements contained within the while loop are executed as long as the boolean condition evaluates to true.

The following is the formal syntax for the while statement.

```
loop_statement ::=
While boolean condition [DO]
            statements
End While
```

The following is an example of a while loop that calculates the value of 5! (5 factorial).

```
i := 1;
x := 1;
While (i < 5) DO
i := i+1;
x := x * i;
End While;</pre>
```

#### **Example 7-4 While Statement**

The boolean condition of a loop statement is checked before the loop is entered. This means that the statements contained within the loop may not execute at all if the condition is not initially true.

### 8 Interaction Objects

Interaction objects are the means by which an end user visualizes and interacts with an application system. Interaction objects are instances, in the toolkit layer, of objects specified in a Slang dialogue. Objects in a Slang specification are object templates (for example, a label widget in the Motif toolkit binding). When the specification is executed. object instances are created within the dialogue. These object instances are passed to the toolkit layer and become interaction objects. Object instances are created when the view controller containing the object template is instantiated. An instance of an object is assigned an identifier when it is created and the identifier can be retrieved using the data access routines described in Appendix D.

Each object template has a collection of attributes that define the presentation of instances created from it, as well as methods that determine the high level interactions that the end user can have with the object. The syntax for object templates is:

```
objects ::=
Objects ':' object_declaration { object_declaration }
object declaration ::=
object name ':' object_type_name
 11 /
   [ Attributes ':' { attribute_value } ]
   [ Methods ':' { method_handler } ]
1 1/
```

## 8.1 Attributes

Attributes are used to define the presentation characteristics of object templates. Object attributes have fixed types of boolean, integer, real, string, buffer, or ID. Since attributes are used to communicate with toolkits, they also have semantic meaning that is defined by the toolkit integrator.

Attributes are created and destroyed along with the object instance in which they are defined. The scope of an attribute is identical to the scope of the object template in which it is defined. Attributes may be accessed from outside their scope if the exact path is known. Access is accomplished using the data access routines described in Appendix D.

Object attributes allow the specification of either code snippets or expressions that are associated with the attribute. Each specification is executed initially when the object instance is created and every time any of the data items (if any) referenced in the specification is modified. That is, the value of an attribute that depends upon certain data items is recalculated whenever those data items are modified.

The following is the formal syntax for attributes:

```
attribute_value ::= attribute_name \':' av_choice
av_choice ::=
code_snippet
| expression
```

The following are some examples of attribute definitions.

#### **Example 8-1 Attributes**

Both the color and the label attributes, in the above example, are reevaluated whenever temperature changes. In the latter case, the integer value of temperature is automatically converted to the type of the label attribute (string).

## 8.2 Methods

Methods provide a way for handling end-user interactions in the dialogue by specifying actions to be performed for specific end-user generated events. Methods are executed once for each generated event and are procedural in nature. The number of and names of the methods for a given interaction object are defined by the toolkit integrator.

The following is the formal syntax for methods:

```
method_handler ::= method_name ':' code_snippet
```

The following are some examples of method definitions:

```
Methods:
 notify: {
  display_sizes_submenu := True;
 send: {
  file_name := text_buffer;
  new_file_name := True;
```

**Example 8-2 Methods** 

Interaction Objects

# View Controllers

A view controller template is used to control which interaction objects are presented to the end user under which circumstances. A view controller is an instance of a view controller template. View controllers provide a means of logically grouping interaction objects that are displayed and removed as a unit. When a view controller template is instantiated, the associated object templates are instantiated as object instances and passed to the toolkit layer as interaction objects. An example of this is a form containing multiple fields. Each field in the form is represented by a separate object template, but the entire form would most likely either be displayed or removed as a unit. View controllers may contain other view controllers nested to an arbitrary depth.

The following is the formal syntax for view controllers:

```
VC ':' vc name creation_condition
component list
{ vc }
ENDVC vc_name [;]
component list ::=
[variables]
[objects]
[actions on create]
[actions on destroy]
```

View controller instances are assigned identifiers in the same fashion as shared data element instances. The identifiers can be retrieved by means of the data access routines described in Appendix D.

### 9.1 Creation Conditions

Each view controller has a creation condition that defines the condition under which the view controller is instantiated.

The following is the formal syntax for creation conditions:

```
creation_condition ::=
Creation Condition ':' boolean condition
```

There are two different classes of creation conditions in Slang: free and bound. Free creation conditions are boolean conditions that may reference existing data items. View controllers with a free creation condition can only be instantiated as many times as the surrounding view controller. The following are examples of free creation conditions:

```
Creation Condition: (True)
Creation Condition: (a < 5)
Creation Condition: (x = 1)
```

#### **Example 9-1 Free Creation Conditions**

Both a and x must be either variables or previously bound shared data items.

The second class of creation conditions causes the instantiated view controller to be bound to an instance of shared data. A bound creation condition must reference a single shared data item. It causes the view controller to be instantiated when an instance of the shared data element is created that is not currently bound to an instance of the view controller. This is accomplished by using the new function within the creation condition. The new function does not create new shared data; rather, it returns true when a new shared data item is created and becomes false when the shared data item is deleted.

A binding creation condition can also reference a component of a shared data element to cause the view controller to be instantiated only when a particular component assume a particular value.

Creation conditions are within the scope of the enclosing view controller. Thus, only data items within the scope of the parent view controller can be used in a creation condition. References to shared data elements that have been bound in a parent view controller are not bound by the current creation condition.

The following are examples of bound creation conditions:

```
Creation Condition: (new("employee"))
Creation Condition: (new("employee") and display=true)
Creation Condition: (employee.location = "Pittsburgh")
```

#### **Example 9-2 Bound Creation Conditions**

Creation conditions cannot reference more than one non-bound shared data element. They can, however, reference any number of constants, variables, or attributes as long as they exist at the time the creation condition is evaluated. This does not include variables and attributes defined within the view controller for which the creation condition applies.

A view controller can only be instantiated if its parent already exists. In other words, in order for the creation condition for any view controller to be true, the creation condition for all the view controller's ancestors must also be true.

A view controller is destroyed when its creation condition becomes false, or the shared data instance that caused it to be instantiated is removed from the shared database. When a view controller is destroyed, all view controllers nested below it and child interaction objects of that view controller are also destroyed.

### 9.2 Actions "On Create"

Actions "on create" are used to specify a code snippet to be executed upon the creation of a view controller. Actions on create are executed once when the view controller is created; they are not reevaluated if the variables on which the code snippet is dependent change. The specification of an action on create code snippet is optional.

The following is the formal syntax for actions on create:

```
actions on_create ::= On Create ':' [code_snippet]
```

The following is an example of an action on create:

```
On Create: {
counter := counter + 1;
```

**Example 9-3 Actions on Create** 

# 9.3 Actions on Destroy

Actions on destroy are used to specify a code snippet to be executed upon the destruction of a view controller. Actions on destroy are executed once, when the view controller is destroyed. The specification of an actions on destroy code snippet is optional.

The following is the formal syntax for actions on destroy:

```
actions on destroy ::= On Destroy ':' [code snippet]
```

The following is an example of an action on destroy:

```
On Destroy: {
  counter := counter - 1;
}
```

**Example 9-4 Actions on Destroy** 

# 9.4 Dependency Considerations

The interaction of three concepts within Slang can be important and confusing in some dialogues. The three concepts are: automatic reevaluation of some snippets (those used in variable declarations and those used in attribute definitions), the one-time evaluation of other snippets (those used within on create and on delete), and the timing of the creation of variables and objects within an instantiated view controller. In particular:

- Variables are evaluated before actions on create are executed. Thus, an action on creation can use the value of a variable set in its specification.
- Variable declarations are reevaluated when any independent variable within it is changed. Thus, a variable can be defined in terms of an attribute of an object created within the same view controller. When the attribute is modified or given a value, the variable declaration will be re-executed and a new value of a variable calculated.
- Actions on create are executed prior to the evaluation of attributes for objects. Thus, an action on create may depend on a variable declared in the same view controller, as indicated above. If that variable depends only on items outside the scope of the current view controller, or on other variables within the scope of the current view controller, then the expected behavior will be observed. On the other hand, if the variable depends upon an attribute of an object declared in the current view controller, the action on create will not yield the expected result. The sequence that causes the problem is:
  - Evaluate variable (since attributes of objects are not yet defined, the variable will use an UNDEFINED value for the attribute).
  - Perform the actions on create.
  - Evaluate the attributes of the object.

Since the variable depends on one of the attributes, it is reevaluated. Since actions on create are only performed once, they are not reevaluated.

# 9.5 Dialogue Structure

A Slang dialogue contains the specification of a user interface for a single application. The dialogue may be either a prototype or the user interface of a final product. Dialogues cannot be called or included from other dialogues.

The following is the formal syntax for a Slang dialogue:

```
Slang dialogue = prologue [externals] component list {vc}
```

The dialogue, as such, consists of the prologue, external declarations, a list of top level components, and a list of view controllers. Each of these top-level components is discussed in the following sections.

#### 9.5.1 Prologue

Each Slang program must indicate the shared data files and toolkits that it uses. This is done in a prologue to the actual Slang program.

The prologue section of the dialogue is used to include the various .ill files required by the dialogue. An .ill file is a file that is generated when an application or toolkit shared data definition file is run through the Saddle preprocessor. Serpent: Saddle User's Guide contains more information on this process.

The prologue lists the shared data definitions and toolkit shared data. The form of this list is:

```
#include "name.ill"
#include "dm.ill"
#include "tech1.ill"
#include "techn.ill"
111
```

where name is the name of the application shared data . sdd file. This can be omitted if there is no application shared data. The special name dm.ill is the name of the dialogue shared data. This can also be omitted if there is no dialogue shared data. The special delimiter "III" is used to indicate the end of the prologue.

Each toolkit being used requires its own entry in the list. For the Athena X toolkit, the entry is:

```
#include "sat.ill"
```

For the Motif toolkit, the entry is:

```
#include "smo.ill"
```

The dialogue must include the .ill files for each toolkit referenced in the dialogue, the application .ill file if communication is required between the dialogue and application, and the dm.ill file if dialogue shared data is to be used.

The following is the formal syntax for the prologue section of the dialogue:

```
prologue ::= ill_file_contents { ill_file_contents } '|||'
```

The following lines provide a sample prologue section of a dialogue.

### Prologue

## 9.5.2 Component List

The top-level dialogue structure can also be thought of as a view controller with a creation condition of true, with certain exceptions—the inclusion of both a prologue and externals section. As such, the dialogue can have almost all the same components as a view controller.

The following is the formal syntax for the component list:

```
component_list ::= [variables] [objects] [actions_on_create]
[actions_on_destroy]
```

Objects declared directly in the top level of the dialogue are always visible. Actions on create are executed immediately during execution of the dialogue. Actions on destroy are executed on dialogue exit.

View Controllers

# 10 User-Defined Functions

Slang provides a mechanism for invoking externally defined C functions from within a dialogue. The C function must be declared as an external in the Slang dialogue. The limitations on the C functions are:

- 1. They must be true functions; that is, a function should not modify any of its parameters. Thus, for example, the C library function streat cannot be used directly since it returns the result in the first argument.
- 2. Functions that return arguments of type string or real must allocate static memory to hold the results.

#### 10.1 External Functions

The following is the formal syntax for the externals section of the dialogue:

```
externals ::= {Externals ':' {external declaration}}
external declaration ::= external_type
function_name '(' [parm_list] ')'
external_type ::= Boolean
                 Buffer
                 Id
                 Integer
                 Real
                 String
                 Void
parm list ::= {parm ','} parm
parm ::=
               Boolean
                 Buffer
                 Integer
                 Real
                 String
```

The function\_name can be any valid Slang name. Note that Slang can only bind to external functions whose names consist entirely of lower case letters and digits. The der laration void FUNC (string, string); is identical to void func (string, string); and maps into external function func. This restriction exists primarily because Slang is case insensitive while C is case sensitive.

The number of parameters accepted by the function should match the number and types given in the parm\_list. It is possible to have functions with no parameters. For example, there is no character type in Slang. C functions that accept or return values of type character cannot be used.

Object files for external functions may be placed in a UNIX archive library (see UNIX ar(1) command) and the library may be passed to the Serpent command using the -L option to force the routines to link with the dialogue. Object files for external functions may also be linked directly using the -L option of the Serpent command. See Serpent: System Guide for a description of the Serpent command.

Note: not all valid C types have a defined conversion.

Example 10-1 shows external declarations in a Slang dialogue.

```
/* string processing */
integer strlen(string);
integer strcmp(string, string);
   /* mathematical functions */
integer abs(integer);
real cos(real);
real pow(real, real);
```

Example 10-1 External Declarations

Once declared, the function can be used anywhere a function statement is valid in a Slang dialogue.

# **10.2 Existing External Functions**

An external library of Slang-callable functions is supplied with Serpent. The serpent command ensures that this library is linked with Slang programs that require it. (See Serpent: System Guide for more information on the serpent command.) The definitions for each set of functions are available by including the appropriate header file. These header files, described in this section, reside in the directory externs/include under the installed Serpent directory; each one specifies the EXTERNALS keyword followed by a series of documented function definitions.

Each function package is described more completely in this section. Note that Slang forces references to a function to lower case and searches for the lower case version of the name.

### **10.2.1 Slang String Functions**

The Slang string functions provide useful string manipulation routines. These functions are made available by including header file sstring.ext. In Slang, as opposed to C, strings are indexed starting from 1. The following is a list of the available functions, with a brief description of each one. A more complete description follows the list with examples showing how one might use the functions.

Function	Description
string_append	Appends one string to another, returning the new string.
string_count_chars	Counts the number of occurrences of a single character or a set of characters in a string.
string_delete	Deletes a substring from a string.
string_index	Finds the first occurrence of a substring within another string, returning the position of the substring.
string_insert	Inserts one string inside another.
string_is_integer	Determines whether a string represents a valid integer.
string_is_real	Determines whether a string represents a valid real number.
string_length	Returns the length of a string.
string_lower	Converts each upper-case character in a string to lower case.
string_upper	Converts each lower-case character in a string to upper case.
substring	Returns the specified "slice" from a string.

**Table 10-1 Slang String Functions** 

# string\_append

Description	The string_append function appends one string to the end of another string.	
Syntax	string_append (initial_string,terminal_string)	
Parameters	initial_string The string on which to append terminal_string.	
	terminal_string The string to append to initial_string.	
Returns	A new string is returned containing the result. The original strings are left unchanged.	

# string\_count\_chars

Description	The string_count_chars function counts the number of occurrences of a single character or a set of characters in a string.  string_count_chars (the_string, char_set)	
Syntax		
Parameters	the_string	The string to be checked.
	char_set	A string containing characters to be counted. The function counts the number of times any character from this string appears in the_string. That is, to count only occurrences of a single character, this string should only contain one character.
Returns	A count (integer) of the number of times that characters from char_set were found in the string. 0 means none were found.	

# string\_delete

Description	The string_delete function deletes a substring from a string.  string_delete (target_string, starting_position, substring_length)	
Syntax		
Parameters	target_string	The string from which to delete.
	starting_position	The start of the substring to be deleted.  This value must be between 1 and the length oftarget_string.
	substring_length)	The length of the substring to be deleted Cannot extend past the end of target_string.
Returns	A new string is returned containing the result. If any error is detecte (e.g., starting_position or substring_length is incorrect) null string is returned. The original string is left unchanged.	

# string\_index

Description The string\_index function finds the first occurrence of a substring

within another string, returning the position of the substring.

**Syntax** string\_index (source\_string, substring)

**Parameters** source\_string The string in which to search.

> The string to locate. substring

Returns If the substring exists within source string, its location, offset

from 1, is returned. Otherwise, a 0 is returned.

NOTE: Specifying a substring that is longer than the source string is not treated as an error. Since the substring can never be found, an 0 is returned in this case.

# $string\_insert$

Description	The string_insert function inserts one string inside another at the specified position.		
Syntax	string_insert (base_string,insert_string,position)		
Parameters	base_string	The string in which to insert.	
	insert_string	The string to be inserted.	
	position	The position (integer) in base_string at which to insert. The restrictions on this argument are:  1. Position must be greater than 0.  2. If position is 1 past the last character in base_string, insert_string is appended to base_string. (See string_append.)  3. Position cannot be greater than string_length (base_string + 1).	

### Returns

A new string is returned containing the result. If position is in error, a null string ("") is returned. The original strings are left unchanged.

# string\_is\_integer

Description	The string_is_integer function determines whether a string contains only decimal digits.		
Syntax	string_is_integer ( the_string)		
Parameters	the_string The string to be checked.		
Returns	FALSE – The string does not represent a valid decimal integer.		
	TRUE - The string represents a valid decimal integer.		

# string\_is\_real

Description	The string_is_real function determines whether a string represents a valid real number.  string_is_real ( the_string)  the_string The string to be checked.	
Syntax		
Parameters		
Returns	· ·	s not represent a valid real number.

# string\_length

Description	The string_length function returns the length of a string.		
Syntax	string_length (target_string)		
Parameters	target_string The string to examine.		
Returns	The length (integer) of the string. 0 means that the string was empty.		

# $string\_lower$

Description	The string_lower function converts every uppercase alphabetic character in a string to lower case, leaving all other characters untouched.  string_lower (the_string)	
Syntax		
Parameters	the_string The string to be converted.	
Returns	A new string is returned containing the result. The original string is le unchanged.	

# string\_upper

Description	The string_upper function converts every lowercase alphabetic character in a string to uppercase, leaving all other characters untouched.	
Syntax	string_upper(the_string)	
Parameters	the_string	The string to be converted.
Returns	A new string is retuunchanged.	rned containing the result. The original string is lef

# substring

Description	The substring function returns the specified portion of a string.		
Syntax	substring (source_string, position, length)		
Parameters	source_string	The string from which to extract a substring	
	position	The starting position (integer) of the substring.  This value must be between 1 and  string_length (source_string).	
	string_length	The length (integer) of the substring. This value must be greater than position and must not result in a value greater than string_length source_string) when added to position.	
Returns	A new string is returned containing the result. If the length values are inconsistent, a null string ("") is returned. The original string is left unchanged.		

### 10.2.2 Extended Arithmetic Functions

The extended arithmetic functions provide additional arithmetic functionality not already available in Slang. The following is a list of the available functions, with a brief description of each one. A more complete description follows the list. These functions are available by including header file arith.ext.

Function	Description	
div	A function-oriented integer division operator.	
make_integer	Converts a Slang expression to an integer, forcing truncation if necessary.	
mod	A function-oriented integer modulo operator.	
truncate	Converts a Slang expression to an integer, forcing truncation if necessary.	

**Table 10-2 Extended Arithmetic Functions** 

# div

The div function provides an integer division operator.	
div(dividend, divisor)	
dividend	The integer to be divided.
divisor	The integer by which to divide dividend
The integer portion of the quotient. Any fractional portion is discarded. This is equivalent to make_integer(dividend/	
	div(dividend dividend divisor

# make integer, truncate

**Description** The make\_integer function converts a Slang expression to an

integer, forcing truncation if necessary. It is also callable as

truncate.

Syntax make\_integer (operand) truncate (operand)

**Parameters** operand Ine expression, variable, or attribute to be

converted to integer.

Returns An integer version of the expression, variable, or attribute is returned.

Real data is truncated, not rounded.

# mod

Description	The mod function provides an integer modulo operator.			
Syntax	mod (dividen	mod (dividend, divisor)		
Parameters	dividend	The integer to be divided.		
	divisor	The integer by which to divide dividend.		
Returns	The remainder (in	nteger) from dividing dividend by divisor.		

# **10.3 Using External Functions**

External functions can be called from Slang: either existing C functions or new ones created as described in Section 10.3.2.

#### 10.3.1 Existing C functions

There are many reasons to use external C functions. C has a rich library of utility functions that are available. For example, many of the string routines translate directly into C library calls. The C libraries are automatically linked into the Slang runtime without a necessity of explicitly stating the libraries in the serpent command. As another example, when debugging Slang programs, it is often useful to print debug messages in the window from which Serpent was invoked. The simplest way to accomplish this is to use existing C I/O routines. It is possible, for example, to call the C function printf from within a Slang program.

Note that Slang assumes that each external function has a fixed number of parameters; further, each parameter is assumed to have a fixed type. While printf does not traditionally behave in this way, it is still possible to use it in a Slang program. Consider the following Externals section of a Slang program:

```
Externals:
void printf (string, integer);
void puts (string);
```

With these declarations in place, you can now make the following calls in a Slang code snippet:

```
printf ("counter = %d and input_string = ", counter);
puts (input string);
```

Some of the versatility of printf is lost, of course. Since the EXTERNALS declaration specifies that the second parameter to printf is an integer, you can't use printf to display real numbers; if you do, they'll be truncated to integers before printf is actually called. Further, this binding to printf specifies that it expects only two parameters; you cannot call it with more than two parameters in this case.

You can only bind to an external function once. In other words, the following EXTERNALS section is not legal Slang:

```
Externals:
void printf (string, integer);
void printf (string, real);
```

The easiest way around this dilemma is to create your own routines that, in turn, call printf with varying type and varying number of parameters. These routines can then be used from within a Slang dialogue.

Electronic examples of how to use external functions are included in the base Serpent distribution in the subdirectory demos/saw/slang-ref.

### 10.3.2 Creating New External Functions

This section discusses the writing of an external C function to be called from a Slang program.

### 10.3.3 Type Equivalences

Slang Data Tyne

Slang data types map into specific C data types, as outlined in the table below. Types marked with [S] are defined in the "serpent.h" header file (which resides in the "include" subdirectory in your Serpent directory tree); these types are briefly described following the table. Types marked with [M] have special memory allocation requirements which are described in following section.

Corresponding C Data Type

Statig Data Type	Corresponding C Data Type
real	double * (i.e., pointer to double) [M]
integer	int
string	char * [M]
boolean	boolean [S]
id	<pre>iid_id_type [S]</pre>

The boolean type is an integer that can be set to a true or false value. The definition of boolean also supplies a series of true and false constants. A true value can be specified with any one of the following constants:

true TRUE True on

Likewise, a false value can be specified with any one of:

false FALSE False off

The id type is used within Serpent to identify items in the shared database. You are discouraged from writing external functions that manipulate ids; however, in the interests of completeness, the type is included here. Ids are currently typed as long integers in C,

although in future releases of Serpent that representation may change.

The string type maps into a standard C string. That is, a Slang string variable is assumed to be either a NULL pointer or a pointer to a series of characters terminated by a null (i.e., '\0') byte.

### 10.3.4 Memory Allocation Considerations

Inside Serpent, variables of type boolean, id, and integer are stored as immediate data, so no memory allocation is required. That is, if you write a function that returns a boolean, id, or integer, you do not have to allocate memory to return the value; you can return it on the stack, as illustrated by this function to add two integers:

```
int int add (opl, op2)
int op1;
int op2;
return (op1 + op2);
```

However, as the table above indicates, strings and real numbers are stored internally as pointers. Serpent assumes that the memory a string or real pointer refers to has been allocated by a special memory allocation routine called make node ().

The make node () routine is similar to the conventional C malloc () routine: it takes a single parameter specifying the number of bytes to allocate and returns a pointer to the allocated area. The returned pointer should be cast to the appropriate pointer type. To make use of make node (), you must include the following lines in your source file:

```
#define memoryPack
#include "memoryPack.h"
```

(Both lines are necessary; the "#define memoryPack" line must precede the include directive.) It is important that you use make node () to allocate memory, rather than malloc() or some other allocation routine; whenever the Serpent runtime system frees memory, it assumes the memory was allocated with make\_node().

As an illustration, contrast the above function to add two integers with this function to add two Slang real numbers:

```
#include <stdio.h>
#define memoryPack
#include "memoryPack.h"

double *real_add (op1, op2)
double *op1;
double *op2;
{
   double *result;
   if (
        (result = make_node (sizeof (double))) !=
        (double*) NULL )
{
   *result = *op1 + *op2;
}
return (result);
}
```

For example, the code below implements the Slang functionstring upper:

```
#include <stdio.h>
#include <string.h>
#include <ctype.h>
#define memoryPack
#include "memoryPack.h"
char *string_upper (the_string)
char *the_string;
int length;
char *result = NULL;
char *s;
if ( (length = strlen (the string)) > 0 ) {
   if ( (result = (char *) make node (length + 1)) == NULL )
    (void) fprintf (stderr,
     "string_upper: memory allocation error for string %s\n",
     the string);
   else {
    for ( s = result; *the_string != '\0'; s++, the string++)
     if ( islower (*the_string) )*s = toupper (*the string);
```

```
else
          *s = *the_string;
       *s = ' \setminus 0';
 }
return (result);
```

### 10.3.5 Linking External Functions To Slang Programs

If you only use the external functions supplied with Serpent, you can skip this section, since the serpent command automatically searches the Serpent externals library when it links a dialogue. However, if you plan to write your own external functions, this section describes how to link them into a dialogue executable.

After you've written your external function (or functions), you must load them into an archival library (see the documentation for the Unix ar(1) command for more information on archival libraries). For example, suppose your functions reside in file "myfuncs.c". After compiling the file and producing "myfuncs.o", you might load the object file into archival library "mylib.a" with these commands:

```
% ar r mylib.a myfuncs.o
   % ranlib mylib.a
(The "%" is the Unix prompt.)
```

Next, when linking a dialogue that calls one of your functions, you have to tell Serpent to resolve that function reference from""mylib.a". Use the "-L" option on the serpent command to accomplish this. Suppose, for example, the dialogue in file "mydialog.sl" uses a function in "myfunc.c". You would compile and link "mydialog.sl" using the following serpent command:

```
% serpent -cl -L mylib.a mydialog.sl
```

Refer to the manual page for the serpent command for more information on the -L option.

**User-Defined Functions** 

# 11 Runtime System

The Slang runtime system, or dialogue manager, is based on a system production model. That is, Slang statements are interpreted as rules to the runtime system and these rules are triggered whenever a data item is created, deleted, or modified. The runtime system keeps track of those data items that depend on other data items. Whenever the independent data items are created, deleted, or modified, the dependent data items are reevaluated.

The reliance of Slang on dependency is one of the most powerful features of the language. but it has several implications of importance to the dialogue specifier. These are: determination of cycles, the time that data is available to application and toolkits, and avoiding the dependency mechanism.

# 11.1 Cycles

Dependencies among data items are detected at runtime. This allows a dependent data item to depend upon the minimum possible number of independent data items but it also implies that cycles in dependencies can only be detected at runtime. A cyclic dependency occurs when two (or more) variables or object attributes are mutually dependent on each other. The following example illustrates a cyclic dependency:

```
x: y - 1
y: x + 1
```

This dialogue specification causes a cycle that the dialogue manager detects by counting the number of times a particular snippet is executed. Whenever that number exceeds a threshold, a cycle is determined to have occurred, execution is terminated, and an error message generated.

### 11.2 Timing of Data Transfers to Application and **Toolkit**

Activities within the dialogue manager are triggered by an external event. That event is the receipt of data from either the application or one of the toolkits. Once the dialogue manager is triggered, it processes all of the data dependencies that exist until no more data remains unchanged. At this time it informs the application and the toolkits of all changes in their respective shared data. The processing of all data dependencies occurs in a process called a minor cycle.

There are several implications of the fact that the dialogue manager processes all changes prior to informing the application or the toolkit of any changes:

- If a single data item is modified multiple times during a collection of minor cycles, only one change is sent out.
- The end user sees all changes to an interaction object at one time. If the
  dialogue generates some portion of the output and then calls an external
  function prior to generating the rest, the toolkit will not be informed of any
  changes until the external function exits. Thus, looping in an external function
  that returns one line of output at a time will not produce the expected results.

In general, the automatic runtime propagation of data is a very powerful mechanism, but occasionally it produces some behavior that is difficult to understand without a more indepth explanation of the system.

# 11.3 Implications of Dependencies

It is important when writing dialogues to understand when dependencies are automatically propagated and when they are not. In general, computations associated with variable declaration and object attribute declaration are targets of propagation. Computations associated with methods, actions on create, and actions on delete are not targets of propagation. Some implications of this follow.

Counters are handled by declaring them in the variable section, incrementing them in the on create section and decrementing them in the on delete section.

Shared data items cannot be declared to be dependent upon other data items. Thus, shared data items need to be explicitly modified when they should be changed. On the other hand, other data items can be dependent upon shared data items and are automatically recalculated when necessary.

# 12 Slang Preprocessor

Serpent uses the C preprocessor. The C preprocessor is used to make macro substitutions, conditional compilations, and inclusions of named files. All C preprocessor commands begin with the # symbol. The # symbol must be located in column one followed by one of the preprocessor commands. The character following a line break character is considered the first character of the next line.

Preprocessor control lines may also be extended on the following line by inserting a backslash '\" character in the last position in a line. This causes the backslash character to remove itself and the following line break character. Backslash characters in normal Slang text are illegal.

# 12.1 Macros and Conditional Compilation

Slang uses the same preprocessor as the C programming language. This preprocessor is a simple macro processor that processes the source text of a Slang program before the compiler processes the source program.

The preprocessor supports the following commands:

Command	Description
#define identifier token-string	Define a preprocessor macro.
#undef name	Remove a macro definition.
#include "filename"	Insert text from another file.
#if expression	Conditionally perform some action,
	based on the value of a constant expression.
#ifdef identifier	Conditionally include some text, if preprocessor identifier is defined.
#ifndef identifier	Conditionally include some text, if preprocessor identifier is not defined.
#else	Alternately include some text, if the previous #if, #ifdef, or #ifndef test failed.
#endif	Terminate conditional text.
#line constant identifier	Supply a line number for compiler messages.

NOTE: The preprocessor commands must be in lower case. If lowercase letters are not used, the preprocessor will return an error message.

Please refer to A C Reference Manual, Samuel P. Harbison, Guy L. Steele Jr., Second Edition, pages 26-48 or The C Programming Language, Brian W. Kernighan and Dennis M. Ritchie, pages 207-208 for more information about the C preprocessor.

# Appendix A Glossary of Terms

#### application layer

Those components of a software system that implement the "core" application functionality of the system.

#### application shared data

The section of the shared database associated with the application. This data acts as the interface between the functional portion of the application system and Serpent.

#### atomic data item

A shared data component or a variable.

#### attribute

A characteristic of an interaction object that may be defined by the dialogue specifier.

#### bound

Associated with. A view controller instance is *bound* to the shared data instance for which it was created.

#### code snippet

"Islands" of procedural code that are executed at certain defined times in the execution of a dialogue or as a result of changes in the state of the system.

#### creation condition

The conditions under which a view controller template is instantiated.

#### data item

Anything that can be declared or specified in Slang.

#### dialogue

A specification of the presentation of application information to, and interactions with, the end user.

#### dialogue layer

Serpent layer that controls the dialogue between the application and the end user of the application.

#### dialogue manager

Serpent component that executes the dialogue.

#### dialogue model

The dialogue model provides the conceptual basis for dialogue specification. The dialogue model is primarily based on a data-driven, rule-based production model.

#### dialogue shared data

Mechanism that allows a dialogue to create, modify, and destroy instances of data without informing an application or toolkit of the activities.

#### dialogue variables

Variables defined in view controllers within a Slang dialogue.

#### drop-down menu

Menu that consists of a menu bar that contains a number of options. Selecting an option causes a submenu to appear directly below the menu bar.

#### extent

Refers to the period of time for which storage is allocated for a data item.

#### ID

Unique instance identifier of those Slang data items that may have multiple instances.

#### I/O toolkits

Existing hardware/software systems that perform some level of generalized interaction with the user.

#### interaction object

Objects that exist in a given toolkit and can be used to interact with the end user.

#### lexical structure

The characters that may appear in a Slang dialogue and the lexical units or tokens that they may form.

#### method

Provides a way for handling end-user interactions in the dialogue by specifying actions to be performed for specific end-user generated events.

#### path

Description of the location of a data item in the dialogue structure.

#### presentation layer

Serpent layer concerned with low level interaction with the user. This layer consists of the various I/O toolkits.

#### presentation independent

Independent of the user interface of the system.

#### scope

The scope of a data item is the set of statements and expressions in which the declaration of the identifier associated with that data item is valid.

#### shared data

Data that is managed by Serpent except for variables declared within view controller templates.

#### shared database

Data managed by Serpent. The database consists of application data, presentation data, and global dialogue data.

#### shared data definition

A shared data structure that may be instantiated at runtime; may be either a record or a scalar

#### shared data instance

An instance of a shared data element.

#### shared data item

A component of a shared data record instance or a shared data scalar instance.

#### tokens

The smallest lexical units that are recognized by Slang.

#### transaction

A collection of updates to the shared database that is logically processed at one time.

#### user interface

Those components of a software system that specify the presentation of application information to, and interaction with, the end user.

#### view controller

Mechanism for defining control flow and existence of interaction objects in dialogues.

#### view controller instance

An instantiation of a view controller template that is bound to specific application data and interaction objects.

#### view controller template

A view controller specification.

#### visible

A data item is said to be visible if the identifier for that data item can be associated with the value.

#### white space characters

Characters that are used to separate adjacent tokens or format Slang dialogue text. These characters include: blank (space), end of line, vertical tab, form feed, horizontal tab, and comments.

Glossary of Terms

# Appendix B Slang BNF Grammar

This appendix defines the BNF grammar for Slang. The following conventions are used in the specification:

Uppercase letters are used to indicate terminals, as does anything enclosed in single quotes. Uppercase letters are used for reserved words, and single quotes are reserved for punctuation literals.

- Lowercase letters are used to indicate a non-terminal (rule).
- Spaces between items in a rule indicate that they are separate, lexically different terms. A carriage return, line feed, or tab between two items in a rule has the same meaning as a space (except for reserved words).
- A vertical bar (1) separates choices, one of which must be used.
- Items enclosed in square brackets ([]) are optional.
- Items enclosed in curly brackets ({}) may be executed any number of times, including zero.
- · Keywords are in boldface type.

Note: Reserved words consisting of two words can have white space between the words.

```
VOID
parmlist ::=
        {parm ','} parm
parm ::=
               BOOLEAN
               BUFFER
               ID
               INTEGER
               REAL
               STRING
vc ::=
       VC ':' vc_name
        creation_condition
        component_list
        {vc}
       END VC vc name
component_list ::=
        [variables]
        [objects]
        [actions_on_create]
        [actions_on_destroy]
creation_condition ::=
        CREATION CONDITION ':' boolean condition
variables ::=
       VARIABLES ':' {variable_declaration}
variable declaration ::=
        variable_name ':' v_choice
vvchoice ::=
        code_snippet
        | [expression] eos
objects ::=
        OBJECTS `:' object_declaration
        {object_declaration}
object_declaration ::=
        object_name ':' object_type_name '{ '
        [ATTRIBUTES ':' {attribute value}]
        [METHODS ':' {method handler}] ' }'
attribute_value ::=
        attribute_name ':' av_choice
```

```
av choice ::=
         code_snippet
        | expression eos
method handler ::=
        method_name ':' code_snippet
actions on create ::=
        ON CREATE ':' [code_snippet]
actions on destroy ::=
        ON DESTROY ':' [code_snippet]
code_snippet ::=
        '{ '[statements] '}' [eos]
statements ::=
       statement eos {statement eos}
statement ::=
          conditional statement
        | assignment_statement
        | imperative_statement
        | loop_statement
conditional statement ::=
        IF boolean_condition
        THEN statements
        {ELSIF boolean condition THEN statements}
        [ELSE statements]
       END IF
assignment_statement ::=
        qualified name ':=' expression
imperative statement ::=
        function_call
loop statement ::=
       WHILE boolean condition [DO]
        statements
       END WHILE
boolean_condition ::=
        '(' expression ')'
expression ::=
        [expression logical_operator]
        boolean expression
```

```
boolean_expression ::=
        [boolean expression equality operator]
        relational_expression
relational expression ::=
        [relational expression relational operator]
        arithmetic expression
arithmetic expression ::=
        [arithmetic_expression addition_operator] term
term ::=
        [term multiplication_operator]factor
factor ::=
        [factor '**'] signed_id
signed id ::=
        [ unary_operator ] id
id ::=
          qualified name
        | function call
        | '(' expression ')'
        constant
qualified name ::=
        name { '.' name }
function_call ::=
        function name '(' [ expressions ] ')'
expressions ::=
        expression { ',' expression }
logical operator ::=
             AND
        1 '&'
        OR
        1 11
equality operator ::=
        1 '<>'
relational_operator ::=
           `<'
        | '<='
        1 '>'
        \ \>='
```

```
addition_operator ::=
         1 1-1
multiplication_operator ::=
            1 * /
        1 1/1
unary operator ::=
            NOT
        1 1-1
constant ::=
           integer_constant
        | real_constant
        | boolean_constant
        | string_constant
        | UNDEFINED
        NULL
        | SELF
integer_constant ::=
        digit {digit}
real constant ::=
            digit {digit} '.' {digit}
        | '.'digit {digit}
boolean_constant ::=
           TRUE
        FALSE
string_constant ::=
        ` " ' <any valid ASCII text> ' " '
        function name ::= name
name ::=
       alphabetic_character_or_underscore
        [{alpha_or_digit_or_underscore}
        alpha_or_digit {alpha_or_digit}}
eos ::=
        \;' { \;' }
comment ::=
        '/*' <any valid ASCII text> '*/'
       Note: comments are handled by the C
        preprocessor and may occur anywhere in a Slang
       program
```

Slang BNF Grammar

# Appendix C Runtime Conversions

Each of the following tables defines the type results and conversions based on the types (and values) for a specified class of runtime operations. Each table defines the type coercions that are legal and the results of the coercions. Each shared data component and attribute has a type declared at specification time. Each variable value has a type determined at runtime. The first table gives the type of the result when a binary arithmetic operation (+, -, \*, /, \*\*) is performed.

### C.1 Binary Arithmetic

argument 2:	boolean	integer	real	string	id	buffer	undefined
argument 1							
boolean	(4)	(4)	(4)	(4)	(4)	(4)	(4)
integer	(4)	integer	(3)	(1)	(4)	(4)	undefined
real	(4)	(3)	real	(2)	(4)	(4)	undefined
string	(4)	(1)	(2)	(5)	(4)	(4)	undefined
id	(4)	(4)	(4)	(4)	(4)	(4)	(4)
buffer	(4)	(4)	(4)	(4)	(4)	(4)	(4)
undefined	(4)	undefined	undefined	undefined	(4)	(4)	undefined

**Table 12-1 Binary Arithmetic** 

The preceding is valid for all binary arithmetic operators (+, -, \*, /, \*\*) except for division, which has the following exceptions:

- · Dividing by zero results in undefined.
- An integer divided by an integer has a real result.

#### Notes:

1. If the string operand can be converted to integer, do the conversion and proceed with the operation. If the string operand cannot be converted to integer, try to convert it to real. If it can be converted to real, then convert the integer argument to real and the result is real. Otherwise, it is a runtime error.

- 2. If the string operand can be converted to real, do the conversion and proceed with the operation. If the string operand cannot be converted to real, it is a runtime error.
- 3. Convert the integer operand to real and proceed with the operation.
- 4. Runtime error.
- 5. If both string operands can be converted to integer, convert them and then perform the operation. If neither string operand can be converted to integer, try converting to real. If neither can be converted to real, it is a runtime error.

# **C.2** Relational Operations

The following table gives the type of the comparison when a relational operation (>, <) is performed.

argument 2 argument 1	boolean	integer	real	string	id	buffer	undefined
boolean	(3)	(3)	(3)	(3)	(3)	(3)	(3)
integer		integer	real	(1)	(3)	(3)	undefined
real			real	(2)	(3)	(3)	undefined
string				(5)	(3)	(3)	undefined
id					(3)	(3)	(3)
buffer						(3)	(3)
undefined							undefined

**Table 12-2 Relational Operations** 

- 1. If the string operand can be converted to integer, do the conversion and proceed with the operation. If the string operand cannot be converted to integer, try to convert it to real. If it can be converted to real, then convert the integer argument to real and the comparison is real. Otherwise, it is a run time error.
- 2. If the string operand can be converted to real, do the conversion and proceed with the operation. If the string operand cannot be converted to real, it is a runtime error.
- 3. Runtime error.
- 4. If both string operands can be converted to integer, convert them and then perform the operation. If both string operands cannot be converted to integer, try converting them to real. If both cannot be converted to real, it is a runtime error.

# **C.3** Assignment Operations

The following table gives the results of assigning a value to either shared data or an object attribute.

То	boolean	integer	real	string	id	buffer
From						
boolean	valid	(4)	(5)	(8)	invalid	valid
integer	(6)	valid	valid	valid	invalid	valid
rcal	(7)	(1)	valid	valid	invalid	valid
string	(8)	(2)	(3)	valid	invalid	valid
id	invalid	integer	invalid	invalid	valid	valid
buffer	(9)	(9)	(9)	(9)	(9)	valid
undefined	valid	valid	valid	valid	valid	valid

**Table 12-3 Assignment Operations** 

Note: The following conversions only occur with shared data.

- 1. Convert the real operand to integer by truncating the value.
- 2. Valid if the string operand can be converted to integer; otherwise, it is a runtime error.
- 3. If the string operand can be converted to real, do the conversion and then continue with the operation. If the string operand cannot be converted to real, it is a runtime error.
- 4. Boolean is converted to integer value 1 if true and 0 if false.
- 5. Boolean is converted to real value 1.0 if true and 0.0 if false.
- 6. An integer can be converted to a boolean if the value of the integer is 0 (converted to false) or 1 (converted to true). Any other value results in a runtime error.
- 7. A real can be converted to a boolean if the value of the real is 0.0 (converted to false) or 1.0 (converted to true). Any other value results in a run time error.
- 8. True is converted to the string "true," false is converted to the string "false."

  The reverse conversions occur also (the string values are case sensitive). Any other values result in a runtime error.
- 9. If the type of the buffer is a Serpent-defined type and the conversion is defined for that type, then the conversion is done; otherwise it is a runtime error.

## **C.4** Unary Arithmetic Operations

boolean	(2)
integer	integer
real	real
string	(1)
record	(2)
id	(2)
buffer	(2)
undefined	undefined

- 1. If the string operand can be converted to integer or real, do the conversion and proceed with the operation. If the string operand cannot be converted to integer or real, it is a runtime error.
- 2. Runtime error.

**Table 12-4 Unary Arithmetic Operations** 

# **C.5** Equality Operations

The following table gives the type of comparison when applying the equality operator.

	boolean	integer	real	string	id	buffer	undefined
boolean	boolean	(8)	(8)	(8)	(4)	(9)	(5)
integer		integer	(3)	(1)	(4)	(9)	(5)
real			real	(2)	(4)	(9)	(5)
string				string	(4)	(9)	(5)
id					ID	(9)	(5)
buffer						buffer	(5)
undefined						TRUE	

**Table 12-5 Equality Operations** 

- If the string operand can be converted to integer, do the conversion and proceed with the operation. If the string operand cannot be converted to integer, the operands are considered unequal.
- If the string operand can be converted to real, do the conversion and proceed with the operation. If the string operand cannot be converted to real, the operands are considered unequal.

- 3. Convert the integer operand to real and proceed with the operation.
- 4. Runtime error.
- 5. A variable of undefined type is equal to a shared data component of undefined value, regardless of the type of the shared data component.
- 6. A buffer is equal to another type if the buffer can be converted to that type and the values are equal.
- 7. A boolean can be compared to an integer or real value if the value can be converted to boolean.
- 8. If the type of the buffer is one of the Serpent types, the comparisons are done using the Serpent type contained in the buffer. If the buffer type is not a Serpent type, the result is not equal.

**Runtime Conversions** 

# Appendix D Data Access Routines

The data access routines provide a means of accessing and modifying view controllers, variables, and objects within a Slang dialogue. The routines provide access to data items for those portions of the dialogue that are not within scope of the data item. The following is a list and short description of these routines. A more complete description immediately follows:

get\_bound\_sd\_instance

get name

get\_object

get parent vc

get\_variable\_value

get\_vc

put\_variable\_value

Gets the ID of the shared data element bound to a given view controller.

Gets the symbolic name of a view

controller, object, or variable that has the

given ID.

Gets the ID of a named object associated

with a view controller instance.

Gets the ID of the parent view controller of the specified view controller or object.

Gets the value of a specified variable.

controller created for a given shared data

Returns the ID of the named view

element.

Puto o valuo into a voriable.

# $get\_bound\_sd\_instance$

Description	data instance bou	_sd_instance function gets the ID of the shared and to the specified view controller. The view ified through its ID.
Syntax	function get_	_bound_sd_instance( vc_id );
Parameters	vc_id	The ID of the view controller.
Returns	The ID of the sha	ared data instance.

# get\_variable\_value

Description The get\_variable\_value function gets the value for a specified

variable within a view controller instance.

Syntax function get variable\_value (vc\_id , name);

Parameters vc\_id The ID of the view controller instance in

which the variable lives.

name The name of the variable.

**Returns** The value of the specified variable.

# get\_name

Description	The get_name function gets the name of the specified data item			
Syntax	<pre>function get_name( item_id );</pre>			
Parameters	item_id	The ID of the data item whose name is to be retrieved. The data item can be either a view controller, an object, or a variable.		
Returns	The symbolic name of the item whose ID was passed.			

# get\_object

Description	The get_object function returns the ID of object instance of for a specified view controller instance.			
Syntax	function get_o	bject (vc_id , object_name );		
Parameters	vc_id object_name	The ID of the view controller instance.  The name of the object as a string.		
Returns	The ID of the object	et instance.		

# get\_parent\_vc

Description	The get_parent_vc function gets the ID of the parent view controller for the specified view controller or object.
Syntax	<pre>function get_parent_vc (vc_or_object_id);</pre>
Parameters	vc_or_object_id The ID of the view controller or object.
Returns	The ID of the parent view controller. If the argument is the ID of an object instance, the function returns the ID of the surrounding view controller instance. If the argument is the ID of a view controller instance, the function returns the ID of the parent view controller instance.
	Note: if the argument is the ID of the top level view controller, the system aborts.

### **PROCEDURE**

# put\_variable\_value

Description	The put_vari	Lable_value procedure is used to assign a value to a ble.
Syntax	procedure p	ut_variable_value (vc_id , name , value);
Parameters	vc_id	The ID of the view controller instance of the specified variable.
	name	The name of the variable.
	value	The value to be assigned to the variable.

# get\_vc

Description	The get_vc function gets the ID of view controller instance bound to a specified shared data element.		
Syntax	<pre>function get_vc (sd_id , vc_template_name) ;</pre>		
Parameters	sd_id	ID of the shared data element.	
	vc_template_name	Name of the view controller template.	
Retur ns	The ID of the view controller instance.		

# Appendix E Shared Data Routines

Shared data routines are used to create, destroy, and manipulate shared data elements from within a Slang dialogue. The following is a list and short description of these routines. A more complete description immediately follows:

destroy\_sd\_instance Destroys a shared data instance.

get\_sd value Gets the value of a component of a shared data element

instance.

put\_sd\_value Puts a value into a component of a shared data element

instance.

# create\_sd\_instance

Description	The create_sd_instance routine creates an instance for the specified shared data element and returns a unique ID.  function create_sd_instance (element_name , sdd_mailbox );	
Syntax		
Parameters	element_name	The name of the shared data element as a string.
	sdd_mailbox	The name of the mailbox for the shared data definition file in which the element is defined. This name is constructed from the name of the shared data definition file by capitalizing the prefix of the file and adding "_BOX" (for example, app.sdd uses a mailbox named APP_BOX).

Returns

The ID of the newly created shared data instance.

# Procedure

# destroy\_sd\_instance

Description	The destroy_sd_instance routine destroys the specified shared data instance in the shared database.  procedure destroy_sd_instance ( shared_data_id );	
Syntax		
Parameters	shared_data_id	The ID of the shared data instance to be destroyed.

# get\_sd\_value

Description	The get_sd_value function gets the value of a component of a specified shared data element.		
Syntax	<pre>function get_shared_data_value (sd_id, component_name ) ;</pre>		
Parameters	sd_id component_name	The ID of the shared data element.  The name of a component within the shared data element as a string.	
Returns	The value of the spec	ified shared data element	

## Procedure

# put\_sd\_value

Description	The put_sd_value procedure puts the specified value into a component of the specified shared data item.		
Syntax	<pre>put_shared_data_value (sd_id , component_name , value );</pre>		
Parameters	sd_id	The ID of the shared data element instance.	
	component_name	The name of a component within the shared data element.	
	value	Value to be assigned to shared data component.	

**Shared Data Routines** Serpent: Slang Reference Manual (CMU/SEI-91-UG-5) 132

# Appendix F Utility Routines

Utility routines serve special purposes. They are used as functions within a dialogue but are not exclusively for shared data or for data access.

exit Terminates the dialogue manager and sends a

SIGINT signal to all the taps that were started by the

current invocation of the Serpent command.

id\_exists Used to test for the existence of either a shared data

element, a view controller, a variable, or an object.

new Used in a view controller template creation condition

to indicate that an instance of shared data should be considered for causing a new instance of that view

controller.

recording\_on Turns on the Serpent transaction recording function.

recording\_off Turns off the Serpent transaction recording function.

## exit

Description

The exit function terminates execution of a dialogue and any related applications and I/O technologies.

Syntax

procedure exit ();

**Parameters** 

None.

## id exists

#### Description

The id\_exists function tests whether an ID refers to a valid shared data item, view controller, variable, or object.

Syntax

function id exists ( id ) ;

**Parameters** 

id

The ID to test.

#### Returns

TRUE

if the ID specifies a valid shared data item, variable, view controller instance, or object; FALSE otherwise.

#### Example

The following Slang program shows how one might use id\_exists. The shared data definition file is appended to the end of the program.

```
#include "dm.ill"
#include "saw.ill"
+111
VARIABLES:
some id;
is there : false;
OBJECTS:
button : command widget
{ATTRIBUTES:
label_text :
{IF ( is_there ) THEN
label_text := "THERE";
label rtext := "NOT THERE";
END IF;
METHODS:
notify: {
IF ( id_exists (some_id) ) THEN
destroy_sd_instance (some_id);
is_there := false;
ELSE
some id := create sd instance ("some sdd",
```

```
"DM_Box");
is_there := true;
END IF;
}
shared data definition file
<<test>>
some_sd : shared data
some_sdd : record
some_component : integer;
end record;
end shared data;
```

## new

Description	The new function determines the existence of an unbound shared data element in the shared database. The new function can only be used as part of the creation condition for view controllers.	
Syntax	function new (sh	ared_data_item)
Parameters	shared_data_item	The name of a shared data element as a string.
Returns	TRUE	when an unbound shared data element of the appropriate name is found False when either no unbound shared data element is found or the currently bound instance is deleted.

## Procedure

# recording\_on

Description	The recording_on recording function.	procedure turns on the Serpent transaction
Syntax	<pre>procedure recording_on (recording_file header_message);</pre>	
Parameters	recording_file	The name of a UNIX file to which the transactions are written.
	header_message	An identification string included in the recording file.

#### Procedure

# recording\_off

Description	The recording_off procedure turns off the Serpent transaction recording function.
Syntax	<pre>procedure recording_off();</pre>
Parameters	none

# Appendix G Athena Widget Set

Athena Widget Set

## **XawBboard**

#### Serpent Name

XawBboard

include\_file: X11/Xaw/Form.h

widget\_type: widget
class: formWidgetClass

#### **Description**

The XawBboard widget is a form widget that does not perform geometry management for its children. (The XawBboard widget should be used instead of the form widget when creating a background form to parent other widgets.)

Attributes

Serpent

Name X Type Default

after Widget

allowUserMove Boolean false allowUserResize Boolean false

toBottom bottom focus

method MethodName

parent Widget

selectedY Position 0
selectedY Position 0

maintainSize Boolean

managedWhenCreated Boolean true

toTop top widget int

Form Widget Resource Set

Name X Type Default

accelerators Accelerators

ancestorSensitive Boolean

background Pixel white

backgroundPixmap Pixmap

borderColor Pixel black

borderPixmap Pixmap

borderWidth Dimension 1

children WidgetList colormap Colormap

defaultDistance int

depth int

destroyCallback CallbackList
height Dimension

mappedWhenManaged Boolean true

numChildren Cardinal screen Screen

sensitive Boolean true

translations Translations: Shift<Bm1Down>,<Bm1Up>: pick()

Btn1Down>,<Btn1Up>: select()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Ctrl<Btn1Down>,<Btn1Up>: top()
Ctrl<Btn2Down>,<Btn2Up>: bottom()
Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Bm3Down>,<Bm3Motion>,<Bm3Up>: move()

0

width Dimension

y Position
Position

**Constraint Resource Set** 

Name X Type Default

bottom unsigned\_char

fromHoriz Widget NULL

romVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize this widget with the mouse, and sends the widget's x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse, and sends the location of that point to the dialogue in response to a user event (typically a shifted Bm1Down).
top		This method is sent to the dialogue when the widget is raised.
bottom		This method is sent to the dialogue when the widget is lowered.
select	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse, and sends the location of the point to the dialogue.

## **XawBox**

#### **Serpent Name**

XawBox

include\_file: X11/Xaw/Box.h

class: boxWidgetClass widget\_type: widget

#### **Description**

The XawBox widget provides geometry management of arbitrary widgets in a box of a specified dimension. The children are rearranged when resizing events occur either on the XawBox or on one of its children, or when its children are managed or unmanaged. The XawBox widget always attempts to pack its children as tightly as possible within the geometry allowed by its parent

#### **Attributes**

Serpent

Default X Type Name

after Widget

Boolean false allowUserMove Boolean false

allowUserResize toBottom bottom

focus focus Boolean

managedWhenCreated true

MethodName method

Widget **NULL** parent selectedX **Position** 0

**Position** 0 selectedY toTop top int

widget

**Box Widget Resource Set** 

X Type **Default** Name

Accelerators accelerators

Boolean ancestorSensitive

white Pixel anbackground

Pixmap backgroundPixmap

black Pixel borderColor

Pixmap borderPixmap

1 Dimension borderWidth

WidgetList children Colormap colormap

depth int

CallbackList destroyCallback Dimension height Dimension hSpace

Boolean mappedWhenManaged true

Cardinal numChildren String orientation Screen screen

Boolean true sensitive

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Bm2Down>,<Bm2Motion>,<Leave>,<Bm2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Bm3Down>,<Bm3Motion>,<Leave>,<Bm3Up>: move()

Shift<Bm3Down>,<Bm3Motion>,<Bm3Up>: move()

Dimension width

**Position** x

**Position** 

**Constraint Resource Set** 

У

Default <u>Name</u> X Type

bottom unsigned\_char

Widget NULL fromHoriz

**NULL** Widget fromVert

#### Athena Widget Set, XawBox

horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize this widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

## **XawCommand**

#### Serpent Name

XawCommand

include\_file: X11/Xaw/Command.h

class: commandWidgetClass

widget\_type: widget

#### **Description**

The xawCommand widget is an area, often rectangular, that contains a text label or bitmap image. This area, which is selectable, is often referred to as a button. When the pointer cursor is on a button, it becomes highlighted by drawing a rectangle around its perimeter. This highlighting indicates that the button is ready for selection. When pointer button 1 is pressed, the xawCommand widget indicates its selection by reversing its foreground and background colors. When the button is released, the XawCommand widget's notify action will be invoked. If the pointer is moved out of the widget before the button is released, the widget reverts to its normal foreground and background colors, and releasing the button has no effect. This behavior allows the user to cancel an action.

#### **Attributes**

Serpent

Name X Type Default

after Widget

allowUserMove Boolean false allowUserResize Boolean false

toBottom bottom

managedWhenCreated Boolean true

method MethodName

parent Widget NULL

toTop top

selectedX Position 0

selectedY

Position

0

widget

int

**Command Widget Resource Set** 

Name

X Type

**Default** 

accelerators

Accelerators

 $\verb"ancestorSensitive"$ 

backgroundPixmap

Boolean

white

background

Pixel Pixmap

bitmap

Pixmap

borderColor

Pixel

black

borderPixmap

Pixmap

Dimension

borderWidth

CallbackList

Six\_callback

callback colormap

Colormap

corner@cundPercent

Dimension

cursor

Cursor

depth

int

destroyCallback

CallbackList

font

XFontStruct

6x13

foreground

Pixel

black

height

Dimension

highlightThickness

Dimension

insensitiveBorder

Pixmap

internalHeight

Dimension

2

internalWidth

Dimension

unsigned\_char

4

justify

String

mappedWhenManaged

Boolean

true

resize

lacel

Boolean

screen

Screen

\_

sensitive

Boolean

true

shapeStyle

unsigned\_char

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

ETA DUETO DE ATT.

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Bm3Down>,<Bm3Motion>: move()

Shift<Bm3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

Ctrl<Btn1Down>,<Btn1Up>: top()
Ctrl<Btn2Down>,<Btn2Up>: bottom()

<Btn1Down>: set()

Dimension

<Btn1Up>: notify () unset() <EnterWindow>: highlight() <LeaveWindow>: unhighlight()

width

x Position

y Position

#### **Constraint Resource Set**

Consti anni Nesoui ce Sei		
<u>Name</u>	X Type	Default
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0

#### Methods

Methods		
Name	<u>Parameters</u>	Description
move	x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
top		This method is sent to the dialogue when the widget is raised.

#### Athena Widget Set, XawCommand

This method is sent to the dialogue when the widget is lowered.

This method is sent to the dialogue in response to a user event (typically a Btn1Down).

Pick selectedX, selectedY This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

## XawDialog

#### **Serpent Name**

XawDialog

include\_file: X11/Xaw/Dialog.h

class: dialogWidgetClass widget\_type: widget

#### **Description**

An XawDialog widget, which is simply a special case of the Form widget, provides a convenient way to create a preconfigured form. The typical XawDialog widget contains three areas. The first line contains a description of the function of the XawDialog widget (for example, the string Filename); the second line contains an area into which the user types input; the third line contains buttons that allow the user to confirm or cancel the XawDialog input.

#### **Attributes**

Serpent

<u>Name</u>	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
toBottom	bottom	
managedWhenCreated	Boolean	true
method	MethodName	
parent	Widget	
toTcp	top	
selectedX	Position	0
selectedY	Position	0
widget	int	

Form Widget Resource Set

Name X Type

accelerators Accelerators

ancestorSensitive Boolean

background Pixel

backgroundPixmap Pixmap borderColor Pixel

borderPixmap Pixmap

borderWidth Dimension

children WidgetList

colormap Colormap

defaultDistance int

depth int

destroyCallback CallbackList

height Dimension icon Pixmap

labelStringmappedWhenManagedBoolean

mappedWhenManaged Boolean numChildren Cardinal

sensitive Boolean

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

Screen

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Ctrl<Btn1Down>,<Btn1Up>: top()
Ctrl<Btn2Down>,<Btn2Up>: bottom()
Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btm3Down>,<Btm3Motion>,<Btm3Up>: move()

value String

width Dimension
x Position

y Position

screen

Constraint :	Resource Set		
<u>Name</u>		X Type	<u>Default</u>
bottom		unsigned_char	0
fromHoriz		Widget	NULL
fromVert		Widget	NULL
horizDist	ance	int	0
vertDista	nce	int	0
left		unsigned_char	2
resizable		Boolean	false
right		unsigned_char	2
top		unsigned_char	0
Methods			
<u>Name</u>	<u>Parameters</u>	Description	

<u>Parameters</u>	Description
x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
x, y, width, height	This method allows the user to resize this widget with the mouse and sends its x and y location and new width and height to the dialogue.
	This method is sent to the dialogue when the widget is raised.
	This method is sent to the dialogue when the widget is lowered.
selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).
	x, y, horizDistance, vertDistance x, y, width, height

## **XawForm**

#### **Serpent Name**

XawForm

include\_file: X11/Xaw/Form.h

class: formWidgetClass
widget\_type: widget

#### **Description**

The xawform widget can contain an arbitrary number of children, or subwidgets. The xawform provides geometry management for its children, allowing individual control of the position of each child. Any combination of children can be added to an xawform. The initial positions of the children may be computed relative to the positions of other children. When the xawform is resized, it computes new positions and sizes for its children. This computation is based upon information provided when a child is added to the xawform.

#### **Attributes**

Serpent

<del>-</del>		
Name	X Type	<u>Default</u>
after	Widget	
allowUserMove	Boolean	false
allowUserResize	Boolean	false
toBottom	bottom	
focus	focus	
maintainSize	Boolean	true
managedWhenCreated	Boolean	true
method	MethodName	
parent	Widget	NULL
selectedX	Position	0
selectedY	Position	0
toTop	top	

widget

int

Form Widget Resource Set			
<u>Name</u>	X Type	<u>Default</u>	
accelerators	Accelerators		
ancestorSensitive	Boolean		
background	Pixel	white	
backgroundPixmap	Pixmap		
borderColor	Pixel	black	
borderPixmap	Pixmap		
borderWidth	Dimension	1	
children	WidgetList		
colormap	Colormap		
children	WidgetList		
colormap	Colormap		
depth	int		
destroyCallback	CallbackList		
height	Dimension		
mappedWhenManaged	Boolean	true	
numChildren	Cardinal		
sensitive	Boolean	true	
translations Translations:	Shift <btn1down>,<btn1up>: pick() Shift<bm2down>,<btn2motion>: resize() Shift<bm2down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<bm2down>,<btn2motion>,<btn2up>: resize() Ctr!<btn1down>,<btn1up>: top() Ctrl<btn2down>,<btn2up>: bottom() Shift<btn3down>,<btn3motion>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<btn3up>: move() Shift<btn3down>,<btn1up>: select() Dimension</btn1up></btn3down></btn3up></btn3motion></btn3down></btn3up></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></btn2down></btn1up></btn1down></btn2up></btn2motion></bm2down></btn2up></leave></btn2motion></bm2down></btn2motion></bm2down></btn1up></btn1down>		
x	Position		
У_	Position		

Constraint Resource Set		
<u>Name</u>	X Type	<u>Default</u>
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize this widget with the mouse and sends its $x$ and $y$ location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).
top		This method is sent to the dialogue when the widget is raised.
bottom		This method is sent to the dialogue when the widget is lowered.

## XawLabel

#### Serpent Name

Xawlabel

include\_file: X11/Xaw/Label.h

class: labelWidgetClass
widget\_type: widget

#### **Description**

An XawLabel widget is a text string or bitmap displayed within a rectangular region of the screen. The label may contain multiple lines of Latin1 characters. The XawLabel widget will allow its string to be left, right, or center justified. Normally, this widget can be neither selected nor directly edited by the user. It is intended for use as an output device only.

#### **Attributes**

Serpent

X Type <u>Default</u> Name after Widget allowUserMove Boolean false Boolean false allowUserResize bottom toBottom Boolean managedWhenCreated true method MethodName Widget **NULL** parent toTop top **Position** selectedX 0 selectedY **Position** 0 widget int

Label Widget Resource Set	V T	Default
Name	X Type	<u>Default</u>
accelerators	Accelerators	
ancestorSensitive	Boolean	
background	Pixel	white
backgroundPixmap	Pixmap	
bitmap	Pixmap	
borderColor	Pixel	black
borderPixmap	Pixmap	
borderWidth	Dimension	1
colormap	Colormap	
cursor	Cursor	
depth	int	
destroyCallback	CallbackList	
font	XFontStruct	6x13
foreground	Pixel	black
height	Dimension	
in.sensitiveBorder	Pixmap	
internalHeight	Dimension	2
internalWidth	Dimension	4
justify	unsigned_char	1
label	String	
mappedWhenManaged	Boolean	true
resize	Boolean	true
screen	Screen	
sensitive	Boolean	true
translations Translations:	Shift <bm2down>,<bm2motion>: resize() Shift<bm2down>,<bm2motion>,<leave>,<bm2up>: resize() Shift<bm2down>,<bm2motion>,<bm2up>: resize() Ctrl<bm1down>,<btn1up>: top() Ctrl<bm2down>,<btn2up>: bottom() Shift<bm3down>,<btm3motion>: move() Shift<bm3down>,<btm3motion>,<leave>,<btm3up>: move() Shift<btm3down>,<btm3motion>,<btm3up>: move()</btm3up></btm3motion></btm3down></btm3up></leave></btm3motion></bm3down></btm3motion></bm3down></btn2up></bm2down></btn1up></bm1down></bm2up></bm2motion></bm2down></bm2up></leave></bm2motion></bm2down></bm2motion></bm2down>	
width	Dimension  Position	
x	Position	

#### Position

Constraint Resource Set		
<u>Name</u>	X Type	<u>Default</u>
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	type unsigned_char	2
top	unsigned_char	0

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize this widget with the mouse and sends its x and y location and new width and height to the dialogue.
top		This method is sent to the dialogue when the widget is raised.
bottom		This method is sent to the dialogue when the widget is lowered.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse, and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

## **XawMenuButton**

#### **Serpent Name**

XawMenuButton

include\_file: X11/Xaw/MenuButton.h

class: menuButtonWidgetClass

widget\_type: widget

#### **Description**

The XawMenuButton widget is a (typically) rectangular area that contains a text label or bitmap image. When the pointer cursor is on the button, the button becomes highlighted by drawing a rectangle around its perimeter. Highlighting means that the button is ready for selection. When selected, the XawMenuButton will pop up the menu that has been named in the menuName resource.

#### **Attributes**

Serpent

<u>Name</u>	X Type	<u>Default</u>
after	Widget	
allowUserMove	Boolean	false
allowUserResize	Boolean	false
toBottom	bottom	
managedWhenCreated	Boolean	true
method	MethodName	
parent	Widget	NULL
selectedX	Position	0
selectedY	Position	0
toTop	top	
widget	Widget	

Menu Button Resource Set	···	
Name	X Type	<u>Default</u>
accelerators	Accelerators	
ancestorSensitive	Boolean	
background	Pixel	white
backgroundPixmap	Pixmap	
bitmap	Pixmap	
borderColor	Pixel	black
borderPixmap	Pixmap	
borderWidth	Dimension	1
callback	CallbackList	Six_callback
colormap	Colormap	
cornerRoundPercent	Dimension	
cursor	Cursor	
depth	int	
destroyCallback	CallbackList	
font	XFontStruct	6x13
foreground	Pixel	black
height	Dimension	
highlightThickness	Dimension	
insensitiveBorder	Pixmap	
internalHeight	Dimension	2
internalWidth	Dimension	4
justify	unsigned_char	1
label	String	
mappedWhenManaged	Boolean	true
menuName	String	
resize	Boolean	
screen	Screen	
sensitive	Boolean	true
shapeStyle	unsigned_char	
translations Translations:	Shift <btn1down>,<btn1up>: pick() Shift<btn2down>,<btn2motion>: resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<btn2down>,<btn2motion>,<btn2up>: resize() Shift<btn3down>,<btn3motion>: move()</btn3motion></btn3down></btn2up></btn2motion></btn2down></btn2up></leave></btn2motion></btn2down></btn2motion></btn2down></btn1up></btn1down>	

Shift<Bm2Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btm3Down>,<Btm3Motion>,<Btm3Up>: move()

<BtnDown>: reset() notify () PopupMenu()

<EnterWindow>: highlight() <LeaveWindow>: reset()

width Dimension

x Position

#### **Constraint Resource Set**

У

Name	X Type	<u>Default</u>
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0

Position

#### Methods

<u>Parameters</u>	Description
x, y, horizDistance, vertDisttance	This method allows the user to move the widget with the mouse and sends the widget's new $x$ and $y$ location to the dialogue.
x, y, width, height	This method allows the user to resize this widget with the mouse and sends its x and y location and new width and height to the dialogue.
	This method is sent to the dialogue in response to a user event (typically a Btn1Down).
selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).
	x, y, horizDistance, vertDisttance x, y, width, height

## XawMenuShell

#### Serpent Name

XawMenuShell

include\_file: X11//SimpleMenu.h class: simpleMenuWidgetClass

widget\_type: override

#### **Description**

The XawMenuShell widget is an override shell which acts as a container for the menu entries. The XawMenuShell serves as the glue to bind the individual menu entries together into a menu.

#### **Attributes**

Serpent

<u>Name</u> <u>X Type</u> <u>Default</u>

allowUserMove Boolean false

allowUserResize Boolean

method MethodName

parent Widget NULL

widget int

#### Shell

Name X Type

accelerators Translations

ancestorSensitive Boolean

allowShellResize Boolean

background Pixel

backgroundPixmap Pixmap

borderColor Pixel

borderPixmap Pixmap

borderWidth Dimension

### Athena Widget Set, XawMenuShell

bottomMargin	Dimension
children	WidgetList
colormap	Colormap
createPopupChildProc	Boolean
cursor	Cursor
depth	int
destroyCallback	CallbackList
geometry	caddr_t
height	Dimension
label	String
labelClass	WidgetClass
mappedWhenManaged	Boolean
menuOnScreen	Boolean
numChildren	Cardinal
overrideRedirect	Boolean
popdownCallback	CallbackList
popupCallback	CallbackList
popupOnEntry	Widget
rowHeight	Dimension
saveUnder	Boolean
screen	Screen
sensitive	Boolean
topMargin	Dimension
translations Translations:	<enterwindow>: highlight() <leavewindow>: unhighlight() <btnmotion>: highlight() <btnup>: MenuPopdown() notify() unhighlight() Shift<btm2down>,<btm2motion>: resize() Shift<btm2down>,<btm2motion>,<leave>,<btm2up>: resize() Shift<btm2down>,<btm2motion>,<btm2up>: resize() Shift<btm3down>,<btm3motion>: move() Shift<btm3down>,<btm3motion>,<leave>,<btm3up>: move() Shift<btm3down>,<btm3motion>,<leave>,<btm3up>: move() Ctrl<btm1down>,<btm1up>: top() Ctrl<btm2down>,<btm2up>: bottom() Dimension</btm2up></btm2down></btm1up></btm1down></btm3up></leave></btm3motion></btm3down></btm3up></leave></btm3motion></btm3down></btm3motion></btm3down></btm2up></btm2motion></btm2down></btm2up></leave></btm2motion></btm2down></btm2motion></btm2down></btnup></btnmotion></leavewindow></enterwindow>
x	Position

Position

У

Constra	int	Resource	Set

Name	X Type	<u>Default</u>
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0

### **XawPaned**

### **Serpent Name**

XawPaned

include\_file: X11/Xaw/Paned.h

class: panedWidgetClass widget\_type: widget

### **Description**

The XawPaned widget manages children in a vertically or horizontally tiled fashion. The user may dynamically resize the pane by using the grips that appear near the right or bottom edge of the border between two panes.

0

### **Attributes**

Serpent

parent

NameX TypeDefaultallowUserMoveBooleanfalseallowUserResizeBooleanfalsetoBottombottom

focus focus

managedWhenCreated Boolean true

Widget

method MethodName

selectedX Position

selectedY Position 0

toTop top widget int

### Paned Widget Resource Set

<u>Name</u> <u>Type</u> <u>Default</u>

accelerators Accelerators

ancestorSensitive Boolean
background: Pixel
backgroundPixmap Pixmap
betweenCursor Cursor
borderColor Pixel
borderPixmap Pixmap
borderWidth Dimension

borderWidth Dimension
children WidgetList
colormap Colormap

cursor Cursor depth int

destroyCallback CallbackList

gripCursor Cursor
gripIndent Position
gripTranslations Translations

height Dimension

horizontalBetweenCursor Cursor
horizontalGripCursor Cursor
icon Pixmap

internalBorderColor Pixel

internalBorderWidth Dimension

leftCursor Cursor
lowerCursor Cursor
mappedWhenManaged Boolean
numChildren Cardinal
orientation String
refigureMode Boolean

rightCursor Cursor screen Screen

sensitive Boolean

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Bm3Down>,<Bm3Motion>,<Leave>,<Bm3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

### Athena Widget Set, XawPaned

upperCursor	Cursor
verticalBetweenCursor	Cursor
verticalGripCursor	Cursor
width	Dimension
x	Position
У	Position

### **Constraint Resource Set**

Name	X Type
allowResize	Boolean
max	Dimension
min	Dimension
preferredPaneSize	Dimension
resizeToPreferred	Boolean
showGrip	Boolean
skipAdjust	Boolean

### **Constraint Resource Set**

Name	X Type	<u>Default</u>
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0

Methods Name	Parameter	Description
	<u>r urumeter</u>	Description
move	x, y, horizDistance, vertDistance	This method allows the user to move this widget with the mouse and sends the widget's new x and y location to the dialogue.

resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted BmlDown).

# XawScreenObject

**Serpent Name** 

XawScreenObject

**Description** 

The XawScreenObject widget allows for the detection of screen and

display IDs:

Display size contains height and width

Display type contains color or black & white

**Attributes** 

Serpent

Name X Type

color Boolean

display int

height Dimension

screen Screen

width Dimension

### XawScrollbar

### Serpent Name

XawScrollbar

include\_file: X11/Xaw/Scrollbar.h

class: scrollbarWidgetClass

widget\_type: widget

### **Description**

The xawScrollbar is a rectangular area containing a thumb that, when moved along one dimension, will cause the scrolling of a region inside a box widget. The XawScrollbar may be oriented horizontally or vertically. Each pointer button invokes a specific action.

**Default** 

### **Attributes**

Serpent Name

false Boolean allowUserMove Boolean f: ise allowUserResize toBottom bottom  ${\tt managedWhenCreated}$ Boolean true MethodName method NULL Widget parent selectedX **Position** 0 selectedY Position 0 toTop top int widget

X Type

### **Command Widget Resource Set**

Name X Type

accelerators Accelerators

ancestorSensitive Boolean

### Athena Widget Set, XawScrollbar

background Pixel
backgroundPixmap Pixmap
borderColor Pixel
borderPixmap Pixmap
borderWidth Dimension
colormap Colormap

depth int

destroyCallback CallbackList

foreground Pixel

height Dimension

jumpProc CallbackList

length Dimension

mappedWhenManaged Boolean

minimumThumb Dimension

orientation unsigned\_char

screen Screen
scrollDCursor Cursor
scrollHCursor Cursor
scrollLCursor Cursor

scrol]Proc CallbackList

scrollRCursor Cursor
scrollUCursor Cursor
scrollVCursor Boolean
shown float

thickness Dimension

topOfThumb float

translations Translations: Shift<Btm1Down>,<Btm1Up>: pick()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

Ctrl<Btn1Down>,<Btn1Up>: top()
Ctrl<Btn2Down>,<Btn2Up>: bottom()
<Btn1Down>: StartScroll(Forward)

<Btn2Down>: StartScroll(Continuous) MoveThumb()

NotifyThumb()

<Btn3Down>: StartScroll(Backward)

<Btn2Motion>: MoveThumb() NotifyThumb()

<BtnUp>: NotifyScroll(Proportional) EndScroll()

width

Dimension

x

Position

У

**Position** 

Constraint Resource Set		
<u>Name</u>	X Type	<u>Default</u>
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0

Methods		
Name	<u>Parameters</u>	Description
move	x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
top		This method is sent to the dialogue when the widget is raised.
bottom		This method is sent to the dialogue when the widget is lowered.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).

# XawSimpleMenu

### Serpent Name

XawSimpleMenu

include\_file: X11/Xaw/Sme.h

class: smeObjectClass
widget\_type: widget

### **Description**

The XawSimpleMenu widget is a container for menu entries. The XawSimpleMenu serves as the glue to bind the individual menu entries together into a menu.

### **Attributes**

Serpent

Name X Type Default

after Widget

allowUserMove Boolean false allowUserResize Boolean false

managedWhenCreated Boolean true

method MethodName

parent Widget NULL selectedX Position 0 selectedY Position 0

selectedY Position
toBottom bottom
toTop top

toTop top widget int

### Menu

Name X Type Default

ancestorSensitive Boolean

destroyCallback CallbackList

height	Dimension
sensitive	Boolean

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btm3Down>,<Btm3Motion>,<Leave>,<Btm3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up> move()

<BtnDown>: reset() notify () PopupMenu()

<EnterWindow>: highlight() <LeaveWindow>: reset()

width Dimension x Position y

### **Constraint Resource Set**

Name	X Type	<u>Default</u>
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0

### Methods

<u>Name</u>	<u>Parameters</u>	Description
move	x, y, horizDistance vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
nesize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
notify		This method is sent to the dialogue in response to a user event (typically a Btn1Down).

pick

selectedX, selectedY

This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).

# XawSimpleMenuBSB

### Serpent Name

XawSimpleMenuBSB

include\_file: X11//SmeBSB.h class: smeBSBObjectClass widget\_type: widget

### Description

The XawSimpleMenuBSB widget is a container for the menu entries. It differs from a plain menu widget in that it can contain bitmaps on

both sides of a menu entry.

### **Attributes**

Serpent

Name X Type Default

after Widget

allowUserMove Boolean false allowUserResize Boolean false

managedWhenCreated Boolean true

method MethodName

parent Widget NULL selectedX Position 0

selectedY Position 0

selectedY Position 0
toBottom bottom

toTop top widget Widget

**BSB** Object

Name X Type Default

ancestorSensitive Boolean

callback CallbackList Six\_callback

### Athena Widget Set, XawSimpleMenuBSB

destroyCallback	CallbackList	
font	XFontStruct	6x13
foreground	Pixel	black
height	Dimension	
justify	unsigned_char	
label	String	
leftBitmap	Pixmap	
leftMargin	Dimension	4
rightBitmap	Pixmap	
rightMargin	Dimension	4
sensitive	Boolean	
translations Translations:	Shift <bm2down>,<btn2m Shift<bm2down>,<btn2m Shift<bm2down>,<btn2m Shift<bm3down>,<btn3m< td=""><td><pre>lotion&gt;: resize() lotion&gt;,<leave>,<btn2up>: resize() lotion&gt;,<btn2up>: resize() lotion&gt;: move() lotion&gt;,<leave>,<btn3up>: move() lotion&gt;,<btn3up>: move() (otion&gt;,<btn3up>: move() () PopupMenu()</btn3up></btn3up></btn3up></leave></btn2up></btn2up></leave></pre></td></btn3m<></bm3down></btn2m </bm2down></btn2m </bm2down></btn2m </bm2down>	<pre>lotion&gt;: resize() lotion&gt;,<leave>,<btn2up>: resize() lotion&gt;,<btn2up>: resize() lotion&gt;: move() lotion&gt;,<leave>,<btn3up>: move() lotion&gt;,<btn3up>: move() (otion&gt;,<btn3up>: move() () PopupMenu()</btn3up></btn3up></btn3up></leave></btn2up></btn2up></leave></pre>
width	Dimension	
x	Position	
У	Position	

		_	
Constra	int	Resource	Cat

<u>Name</u>	X Type	<u>Default</u>
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
notify		This method is sent to the dialogue in response to a user event (typically a Btn1Down).
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

## **XawSmeLine**

Serpent Name

XawSmeLine

include\_file: X11/Xaw/SmeLine.h n

class: smeLineObjectClass widget\_type: widget

**Description** 

The XawSmeLine widget is an object used to add a horizontal line to

true

0

a menu, acting as a menu separator. This object is not selectable.

**Attributes** 

Serpent

**Default** <u>Name</u> X Type

after Widget

false Boolean allowUserMove Boolean false allowUserResize

Boolean

managedWhenCreated

MethodName method

**NULL** Widget parent **Position** 0 selectedX

selectedY **Position** toBottom bottom toTop top widget int

SmeLine

<u>Name</u> X Type **Default** 

CallbackList destroyCallback

foreuround Pixel black

Dimension height

Dimension 1 lineWidth

Boolean sensitive Pixmap stipple

translations Translations: Shift<Btm1Down>,<Btm1Up>: pick()

Shift<Bm2Down>,<Bm2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Bm3Down>,<Btn3Motion>: move()

Shift<Bm3Down>,<Bm3Motion>,<Leave>,<Bm3Up>: move()

Shift<Bm3Down>,<Btn3Motion>,<Btn3Up>: move()

<BtnDown>: reset() notify () PopupMenu()

<EnterWindow>: highlight() <LeaveWindow>: reset()

Dimension width **Position** х

**Position** У

### **Constraint Resource Set**

Name	X Type	<u>Default</u>
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0
left	unsigned_char	2
resizable	Boolean	false
right	unsigned_char	2
top	unsigned_char	0
top	unsigned_char	0

Methods	ħ	И	e	tl	h	a	d	5
---------	---	---	---	----	---	---	---	---

x, y, horizDistance, This method allows the user to move the widget move with the mouse and sends the widget's new x and y vertDistance

location to the dialogue.

This method allows the user to resize the widget with the resize x, y, width, height

mouse and sends its x and y location and new width and

height to the dialogue.

This method is sent to the dialogue in response to a user notify

event (typically a Btn1Down).

pick

selectedX, selectedY

This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

### **XawText**

### **Serpent Name**

XawText

include\_file: X11/Xaw/AsciiText.h

class: asciiTextWidgetClass

widget\_type: widget

### **Description**

The text widget provides a modifiable, emacs-style, text editor is reface in a widget that is used to allow arbitrary text input. XawText in this widget can also be modified under program control and displayed back to the user.

### **Attributes**

Serpent

<u>Name</u> X Type **Default** after Widget allowUserMove Boolean false allowUserResize Boolean false bottom toBottom Boolean managedWhenCreated true MethodName method Widget parent NULL selectedX**Position** 0 selectedY **Position** 0 sendBuffer Boolean false toTop top widget int

Text Widget Resource Sei		
<u>Name</u>	X Type	<u>Default</u>
ancestorSensitive	Boolean	
autoFill	Boolean	
background	Pixel	white
backgroundFixmap	Pixmap	
borderColor	Pixel	black
borderPixmap	Pixmap	
boraerWidth	Dimension	1
bottomMargin	Position	
callback	CallbackList	
colormap	Colormap	
cursor	Cursor	
dataCompression	Boolean	
depth	int	
destroyCallback	CallbackList	
displayCaret	Boolean	
displayNonprinting	Boolean	
displayPosition	int	
echo	Boolean	
editType	unsigned_char	2
font	FontStruct	6x13
foreground	Pixel	black
height	Dimension	
insensitiveBorder	Pixmap	
insertPosition	int	
leftMargin	Position	
length	int	
mappedWhenManaged	Boolean	true
pieceSize	int	
rightMargin	Position	
screen	Screen	
scrollHorizontal	unsigned_char	false
scrollVertical	unsigned_char	false
selectTypes	TextSelectType_star	

Boolean sensitive true string String textBuffer Widget textSink Widget textSource Position topMargin beginning-of-line() translations Translations: Ctrl<Key>A: Ctrl<Key>B: backward-character() Ctrl<Key>D: delete-next-character() Ctrl<Key>E: end-of-line() Ctrl<Key>F: forward-character() Ctrl<Key>G multiply(Reset) Ctrl<Key>H: delete-previous-character() Ctrl<Key>J: newline-and-indent() Ctrl<Key>K: kill-to-end-of-line() Ctrl<Key>L: redraw-display() Ctrl<Key>M: newline() Ctrl<Key>N: next-line() Ctrl<Key>O: newline-and-backup() Ctrl<Key>P: previous-line() Ctrl<Key>R: search(backward) Ctrl<Key>S: search(forward) Ctrl<Key>T: transpose-characters() Ctrl<Key>U: multiply(4) Ctrl<Key>V: next-page() Ctrl<Key>W: kill-selection() Ctrl<Key>Y: insert-selection(CUT\_BUFFER1) Ctrl<Key>Z: scroll-one-line-up() Meta<Key>B: backward-word() Meta<Key>F: forward-word() Meta<Key>I: insert-file() Meta<Key>K: kill-to-end-of-paragraph() Meta<Key>Q: form-paragraph() Meta<Key>V: previous-page() Meta<Key>Y: insert-selection(PRIMARY,CUT\_BUFFER0) Meta<Key>Z: scroll-one-line-down() Meta<Key>d: delete-next-word() Meta<Key>D: kill-word() Meta<Key>h: delete-previous-word() Meta<Kev>H: backward-kill-word() Meta<Key>\\<: beginning-of-file() Meta<Key>\\>: end-of-file() Meta<Key>]: forward-paragraph() Meta<Key>[: backward-paragraph() ~Shift Meta<Key>Delete: delete-previous-word()

Shift Meta<Key>Delete:

~Shift Meta<Key>BackSpace: delete-previous-word()

backward-kill-word()

Shift Meta<Key>BackSpace: backward-kill-word()

<Key>Right: forward-character() <Key>Left: backward-character()

<Key>Down: next-line() <Key>Up: previous-line()

<Key>Delete: delete-previous-character() <Key>BackSpace: delete-previous-character()

<Key>Linefeed: newline-and-indent()

<Key>Return: newline() <Key>: insert-char() <FocusIn>: focus-in() <FocusOut>: focus-out()

Ctrl<Btn1Down>,<Btn1Up>: top()
Ctrl<Btn2Down>,<Btn2Up>: bottom()
Shift<Btn1Down>,<Btn1Up>: pick()
Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btm2 Jown>,<Btm2Motion>,<Btm2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btm3Down>,<Btm3Motion>,<Leave>,<Btm3\*Jp>: move()

Shift<Btm3Down>,<Btm3Motion>,<Btm3Up>: move()

<Btn1Down>: select-start()
<Btn1Motion>: extend-adjust()

<Btn1Up>: extend-end(PRIMARY, CUT\_BUFFER0)

<Btn2Down>: insert-selection(PRIMARY, CUT\_BUFFER0)

<Btn3Down>: extend-start()
<Btn3Motion>: extend-adjust()

<Btn3Up>: extend-end(PRIMARY, CUT\_BUFFER0)

unsigned\_char

useStringInPlace

Boolean

width

type

Dimension

wrap

unsigned\_char

x

Position

y

Position

### **Constraint Resource Set**

Name	X Type	<u>Default</u>
bottom	unsigned_char	0
fromHoriz	Widget	NULL
fromVert	Widget	NULL
horizDistance	int	0
vertDistance	int	0

left	unsigned_char	2
resizable	Boolean	false
tor	unsigned_char	0

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize this widget with the mouse and sends its: and y location and new width and height to the dialogue.
send	textBuffer	This method is returned in response to the send_buffer flag being set to true by the dialogue or to a translation table action.
pick	selectedX, selecte iY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted LtmlDown).
top		This method is sent to the dialogue when the widget is raised.
bottom		This method is sent to the dialogue when the widget is lowered.

# **XawTextentry**

### Serpent Name

XawTextentry

include\_file: X11/Xaw/AsciiText.h

class: asciiTextWidgetClass

widget\_type: widget

### Description

The XawTextentry widget is similar to the Text widget except a carriage return activates the send method. The XawTextentry widget was created for use in forms so that the text focus can shift automatically from item to item via carriage return.

### **Attributes**

Serpent

<u>Name</u>	X Type	<u>Default</u>
after	Widget	
allowUserMove	Boolean	false
allowUserResize	Boolean	false
toBottom	bottom	
managedWhenCreated	Boolean	true
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
sendBuffer	Boolean	
toTop	top	
widget	int	

Text Widget Resource Set		
<u>Name</u>	X Type	<u>Default</u>
accelerators	Accelerators	
ancestorSensitive	Boolean	
autoFill	Boolean	
background	Pixel	
backgroundPixmap	Pixmap	
borderColor	Pixel	
borderPixmap	Pixmap	
borderWidth	Dimension	
bottomMargin	Position	
callback	CallbackList	
colormap	Colormap	
cursor	Cursor	
dataCompression	Boolean	
depth	int	
destroyCallback	CallbackList	
displayCaret	Boolean	
displayNonprinting	Boolean	
displayPosition	int	
echo	Boolean	
editType	unsigned_char	2
font	FontStruct	6x13
foreground	Pixel	
height	Dimension	
insensitiveBorder	Pixmap	
insertPosition	int	
leftMargin	Position	
length	int	
mappedWhenManaged	Boolean	
pieceSize	int	
rightMargin	Position	
screen	Screen	
scrollHorizontal	unsigned_char	
scrollVertical	unsigned_char	

selectTypes

TextSelectType\_star

sausitive

Boolean

string

String

textBuffer

textSink

Widget

textSource

Widget

topMargin

Position

translations Translations: Ctrl<Key>A: beginning-of-line() Ctrl<Key>B: backward-character()

Ctrl<Key>D: delete-next-character()

Ctrl<Key>E: end-of-line()

Ctrl<Key>F: forward-character() Ctrl<Key>G: multiply(Reset)

Ctrl<Key>H: delete-previous-character()

Ctrl<Key>J: newline-and-indent() Ctrl<Key>K: kill-to-end-of-line() Ctrl<Key>L: redraw-display() Ctrl<Key>M: newline() Ctrl<Key>N: next-line()

Ctrl<Key>O: newline-and-backup()

Ctrl<Key>P: previous-line() Ctrl<Key>R: search(backward) Ctrl<Key>S: search(forward)

Ctrl<Key>T: transpose-characters()

Ctrl<Key>U: multiply(4) Ctrl<Key>V: next-page() Ctrl<Key>W: kill-selection()

Ctrl<Key>Y: insertselection(CUT\_BUFFER1)

Ctrl<Key>Z: scroll-one-line-up() Meta<Key>B: backward-word() Meta<Key>F: forward-word() Meta<Key>I: insert-file()

Meta<Key>K: kill-to-end-of-paragraph()

Meta<Key>Q: form-paragraph() Meta<Key>V: previous-page()

Meta<Key>Y: insertselection (PRIMARY CUT\_BUFFER0)

Meta<Key>Z: scroll-one-line-down() Meta<Key>d: delete-next-word()

Meta<Key>D: kill-word()

Meta<Key>H: backward-kill-word() Meta<Key>\\<: beginning-of-file() Meta<Key>\\>: end-of-file() Meta<Key>]: forward-paragraph() Meta<Key>[: backward-paragraph()

~Shift Meta<Key>Delete: delete previous-word() Shift Meta<Key>Delete: backward-kill word()

~Shift Meta<Key>BackSpace: delete-previous-word()

Shift Meta<Key>BackSpace: backward-kill-word() Shift<Key>Tab: tab() <Key>Right: forward-character() <Key>Left: backward-character() <Key>Down: next-line() <Key>Up: previous-line() <Key>Delete: delete-previous-character() <Key>BackSpace: delete-previous-character() <Key>Linefeed: newline-and-indent() <Key>Return: send() <Key>: insert-char() <FocusIn>: focus-in() <FocusOut>: focus-out() Ctrl<Btn1Down>,<Btn1Up>: top() Ctrl<Btn2Down>,<Btn2Up>: bottom() Shift<Bm1Down>,<Bm1Up>: pick() Shift<Btn2Down>,<Btn2Motion>: resize() Shift<Btm2Down>,<Btm2Motion>,<Leave>,<Btm2Up>: resize() Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize() Shift<Btn3Down>,<Btn3Motion>: move() Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move() Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move() <Btn1Down>: select-start() <Btn1Motion>: extend-adjust() <Btn1Up>: extend-end(PRIMARY, CUT\_BUFFER0) <Btn2Down>: insert-selection(PRIMARY, CUT\_BUFFER0) <Btn3Down>: extend-start() <Btn3Motion>: extend-adjust() <Btn3Up>: extend-end(PRIMARY, CUT\_BUFFER0) unsigned\_char type Boolean useStringInPlace width Dimension unsigned\_char wrap **Position** x **Position** 

### **Constraint Resource Set**

<u>Name</u>	X Type	<u>Default</u>
bottom	unsigned_cha	0
fromHoriz	Widge	NULL
fromVert	Widge	NULL
horizDistance	in	0
vertDistance	in	0

### Athena Winget Set, XawTextentry

left	unsigned_cha	2
resizable	Boolean	false
right	unsigned_cha	2
top	unsigned_cha	0

Methods		
<u>Name</u>	<u>Parameters</u>	<u>Description</u>
move	x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
send	textBuffer	This method is returned in response to the send_buffer flag being set to true by the dialogue or to a translation table action.
tab		This method is sent to the dialogue in response to a shifted tab.
top		This method is sent to the dialogue when the widget is raised.
bottom		This method is sent to the dialogue when the widget is lowered.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# XawToggleButton

### **Serpent Name**

XawToggleButton

include\_file: X11/Xaw/Toggle.h

class: toggleWidgetClass widget\_type: widget

### **Description**

The Toggle widget is an area, often rectangular, containing a text label or bitmap image. This widget maintains a Boolean state (e.g., True/False or On/Off) and changes state whenever it is selected. When the pointer is on the button, the button may become highlighted by a rectangle around its perimeter. This highlighting indicates that the button is ready for selection. When pointer button 1 is pressed and released, the Toggle widget indicates that it has changed state by reversing its foreground and background colors, and its notify action is invoked, calling all functions on its callback list. If the pointer is moved out of the widget before the button is released, the widget reverts to its normal foreground and background colors, and releasing the button has no effect. This allows the user to cancel an action.

### Attributes

Serpent

<u>Name</u>	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
toBottom	bottom	
managedWhenCreated	Boolean	true
method	MethodName	
parent	Widget	NULL
toTop	top	
selectedX	Position	0
selectedY	Position	0

widget

int

Command Widget Resour	ce Set	
<u>Name</u>	X Type	<u>Default</u>
accelerators	Accelerators	
ancestorSensitive	Boolean	
background	Pixel	white
backgroundPizmap	Pixmap	
bitmap	Pixmap	
borderColor	Pixel	black
borderPixmap	Pixmap	
borderWidth	Dimension	1
callback	CallbackList	Six_callback
colormap	Colormap	
cornerRoundPercent	Dimension	
cursor	Cursor	
depth	int	
destroyCallback	CallbackList	
font	XFontStruct	6x13
foreground	Pixel	black
height	Dimension	
highlightThickness	Dimension	
insensitiveBorder	Pixmap	
internalHeight	Dimension	2
internalWidth	Dimension	4
justify	unsigned_char	1
label	String	
mappedWhenManaged	Boolean	true
radioData	caddr_t	
radioGroup	Widget	
resize	Boolean	
screen	Screen	
sensitive	Boolean	true
shapeStyle	unsigned_char	
state	Boolean	

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

Position

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Bm2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize(

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

<Btn1Down>,<Btn1Up>: toggle() notify () <EnterWindow>: highlight(Always) <LeaveWindow>: unhighlight()

width Dimension

x

y Position

Constraint Resource Set			
<u>Name</u>	X Type	<u>Default</u>	
bottom	unsigned_char	0	
fromHoriz	Widget	NULL	
fromVert	Widget	NULL	
horizDistance	int	0	
vertDistance	int	0	
left	unsigned_char	2	
resizable	Boolean	false	
right	unsigned_char	2	
top	unsigned_char	0	

Methods		
<u>Name</u>	<u>Parameters</u>	Description
wone	x, y, horizDistance, vertDistance	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its $x$ and $y$ location and new width and height to the dialogue.
notify		This method is sent to the dialogue in response to a user event (typically a Btn1Down).

pick

selectedX, selectedY

This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# XawTopLevelShell

Serpent Name

XawTopLevelShell

include\_file: X11/Shell.h

class: topLevelShellWidgetClass

widget\_type: shell

**Description** 

Used for normal top level windows (for example, any additional top

level widgets an application needs).

**Attributes** 

TopI evelShell

Name X Type

iconic Boolean

iconName String

iconNameEncoding unsigned\_char

**WMShell** 

Name X Type

baseHeight int

baseWidth int

heightInc int

iconMask Pixmap

iconPixmap Pixmap

iconWindow Window

iconX int

iconY int

initialState int

input Boolean

### Athena Widget Set, XawTopLevelShell

maxAspectX	int
maxAspectY	int
maxHeight	int
maxWidth	int
minAspectX	int
minAspectY	int
minHeight	int
minWidth	int
title	char_star

titleEncoding

unsigned\_char

transient waitForWm Boolean Boolean

widthInc windowGroup int XID

wm.Timeout

int

### **Shell Resource Set**

X Type
Boolean
Boolean
caddr_t
Boolean
caudr_t
caddr_t
Boolean

# XawViewport

### Serpent Name

XawViewport

/include\_file: X11/Xaw/Viewport.h

widget\_type: widget

### **Description**

The xawViewport widget consists of a frame window, one or two scrollbars, and an inner window. The size of the frame window is determined by the viewing size of the data that is to be displayed and the dimensions to which the XawViewport is created. The inner window is the full size of the data that is to be displayed and is clipped by the frame window. The XawViewport widget controls the scrolling of the data directly. No application callbacks are required for scrolling.

### **Attributes**

Serpent

<u>Name</u>	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
toBottom	bottom	
focus	focus	
managedWhenCreated	Boolean	true
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
toTop	top	
widget	int	

Paned	Widget	Resource	Set
1 aucu	WIUZCL	IVC2OFF CE	Ser

Name X Type Default

accelerators Accelerators

ancestorSensitive Boolean allowHoriz Boolean

allowVert Boolean backgroun Pixel

backgroundPixmap Pixmap

borderColor Pixel borderPixmap Pixmap

borderWidth Dimension
children WidgetList
cclormap Colormap

depth int

destroyCallback CallbackList

forceBars

height

Dimension

mappedWhenManaged

numChildren

Screen

Boolean

Cardinal

Screen

sensitive Boolean

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Ctrl<Btn1Down>,<Btn1Up>: top()
Ctrl<Btn2Down>,<Btn2Up>: bottom()
Shift<Btn3Down>,<Btn3Motion>: move()d

Shift<Btm3Down>,<Btm3Motion>,<Leave>,<Btm3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

useBottom Boolean

useRight Boolean width Dimension

Position

y Position

# Constraint Rescurce Set

<u>Name</u>	X Type	<u>Default</u>
bottom	unsigned_cha	0
fromHoriz	Widge	NULL
fromVert	Widge	NULL
horizDistance	in	0
vertDistance	in	0
left	unsigned_cha	2
resizable	Boolea	false
right	unsigned_cha	2
top	unsigned_cha	0

## Methods

horizDistance,	This method allows the user to move the widget with the
vertDistance	mouse and sends the widget's new x and y location to the dialogue.
x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
	This method is sent to the dialogue when the widget is raised.
	This method is sent to the dialogue when the widget is lowered.
selectedX, selectedY	This method allows the user to select a point on the widget with the mouse, and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).
	vertDistance x, y, width, height

# Appendix H Motif Widget Set

Motif Widget Set Serpent: Slang Reference Manual (CMU/SEI-91-UG-5) 206

# **XmArrowButton**

# Serpent Name

XmArrowButton

include\_file: Xm/ArrowB.h

class: ArrowButtonWidgetClass

widget\_type: widget

# **Description**

The XmarrowButton widget consists of a directional arrow surrounded by a border shadow. When it is selected, the shadow moves to give the appearance that XmarrowButton has been pressed in. When XmarrowButton is not selected, the shadow moves to give the appearance that XmarrowButton has been released, or is out.

#### **Attributes**

Serpent

Name X Type Default
allowUserMove Boolean false

allowUserMove Boolean false allowUserResize Boolean false

method MethodName

parent Widget

selectedX Position 0
selectedY Position 0

widget int

armCallback CallbackList

arrowDirection unsigned\_char ARROW\_UP

disarmCallback CallbackList

**Primitive Resource Set** 

Name X Type Default

bottomShadowColor Pixel

# Motif Widget Set, XmArrowButton

Pixmap UNSPECIFIED\_PIXMAP bottomShadowPixmap

**Pixel** foreground

CallbackList helpCallback

black Pixel highlightColor false Boolean highlightOnEnter

**Pixmap** highlightPixmap

0 highlightThickness short 2 shadowThickness short

**Pixel** topShadowColor

UNSPECIFIED\_PIXMAP Pixmap topShadowPixmap

Boolean false traversalOn unsigned\_char **PIXELS** unitType

NULL caddr\_t userData

**Core Resource Set** 

X Type **Default** Name

Accelerators accelerators

Boolean ancestorSensitived Pixel background backgroundPixmap Pixmap

Pixel borderColor **Pixmap** borderPixmap

**Dimension** 1 borderWidth

colormap Colormap Cardinal depth

CallbackList destroyCallback Dimension height mappedWhenManaged Boolean

Screen screen Boolean sensitive Dimension width

**Position** x **Position** 

У

208

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

<Btn1Down> Arm()

<Bm1Up>: Activate() Disarm() <Key>Return: ArmAndActivate() <Key>space: ArmAndActivate()

<EnterWindow>: Enter()
<LeaveWindow>: Leave()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Bm2Down>,<Btn2Motion>,<Leave>,<Btn2Up>:

resize()

Shift<Btm2Down>,<Btm2Motion>,<Btm2Up>: resize()

Shift<Bm3Down>,<Bm3Motion>: move()

Shift<Bm3Down>,<Bm3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btm3Down>,<Btm3Motion>,<Btm3Up>: move()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	<b>x</b> , <b>y</b>	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
notify		This method is sent to the dialogue in response to a user event (typically a Btn1Down).
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# **XmBulletinBoard**

# Serpent Name

XmBulletinBoard

include\_file: Xm/BulletinB.h

class: BulletinBoardWidgetClass

widget\_type: widget

## **Description**

XmBulletinBoard is a composite widget that provides simple geometry management for children widgets. It does not force positioning on its children, but can be set to reject geometry requests that would result in overlapping children. XmBulletinBoard is the base widget for most dialogue widgets and is also used as a general container widget.

false

0

#### **Attributes**

Serpent

focus

<u>Name</u> X Type Default allowUserMove Boolean false

allowUserResize

focus

Boolean

method MethodName

parent Widget

**Position** 0 selectedX **Position** selectedY

widget int

#### **BulletinBoard Resource Set**

Name X Type **Default** 

Boolean allowOverlap Boolean autoUnmanage

buttonFontList **FontList** 

#### Motif Widget Set, XmBulletinBoard

cancelButton Widget
defaultButton Widget
defaultPosition Boolean

dialogStyle unsigned\_char

dialogTitle String

focusCallback
labelFontList
mapCallback

CallbackList

CallbackList

marginHeight short
marginWidth short
noResize Boolean

resizePolicy unsigned\_char shadowType unsigned\_char stringDirection StringDirection

textFontList FontList
textTranslations
unmapCallback
CallbackList

Manager Resource Set

Name X Type Default

bottomShadowColor Pixel

bottomShadowPixmap Pixmap UNSPECIFIED\_PIXMAP

foreground Pixel

helpCallback CallbackList

highlightColor Pixel black

highlightPixmap Pixmap shadowThickness short topShadowColor Pixel

topShadowPixmap Pixmap UNSPECIFIED\_PIXMAP

unitType unsigned\_char PIXELS

userData caddr\_t NULL

Composite Resource Set		
<u>Name</u>	X Type	<u>Default</u>
insertPosition	OrderProc	
accelerators	Accelerators	
ancestorSensitive	Boolean	
background	Pixel	
backgroundPixmap	Pixmap	
borderColor	Pixel	
borderPixmap	Pixmap	
borderWidth	Dimension	1
colormap	Colormap	
depth	Cardinal	
destroyCallback	CallbackList	
height	Dimension	
mappedWhenManaged	Boolean	
screen	Screen	
sensitive	Boolean	
width	Dimension	
x	Position	
У	Position	
translations Translations:	Shift <btn1down>,<btn1up>: pick() <btn1down>,<btn1up>: select() Shift<btn2down>,<btn2motion>: resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<btn2down>,<btn2motion>,<btn2up>: resize() Shift<btn3down>,<btn3motion>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<btn3up>: move()</btn3up></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></btn2motion></btn2down></btn2up></leave></btn2motion></btn2down></btn2motion></btn2down></btn1up></btn1down></btn1up></btn1down>	

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	х, у	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.

select	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# **XmCascadeButton**

# Serpent Name

XmCascadeButton

include\_file: Xm/CascadeB.h

class: CascadeButtonWidgetClass

widget\_type: widget

#### Description

The XmCascadeButton widget links two MenuPanes or a MenuBar to a MenuPane. It is used in menu systems and must have a RowColumn parent with its rowColumnType resource set to MENU\_BAR, MENU\_POPUP, or MENU\_PULLDOWN. It is the only widget that may have a pulldown MenuPane attached to it as a submenu. The submenu is displayed when this widget is activated within a MenuBar, a PopupMenu, or a PulldownMenu. Its visuals can include a label or pixmap and a cascading indicator when it is in a Popup or Pulldown MenuPane; when it is in a MenuBar, it can include only a label or a pixmap.

#### Serpent

<u>Name</u>	<u>X Type</u>	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	

#### **ArrowButton**

<u>Name</u>	X Type	<u>Default</u>
activateCallback	CallbackList	Six_callback
cascadePixmap	Pixmap	
cascadingCallback	CallbackList	

mappingDelay

int

subMenuId

Widget

Label Resource Set

Name X Type

String accelerator String acceleratorText

unsigned\_char alignment

**FontList** fontList Pixmap labelInsensitivePixmap **Pixmap** labelPixmap labelString String

unsigned\_char labelType

short marginBottom marginHeight short marginLeft short marginRight short marginTop short marginWidth short char mnemonic Boolean recomputeSize

StringDirection stringDirection

**Primitive Resource Set** 

Name X Type **Default** 

**Pixel** bottomShadowColor

bottomShadowPixmap Pixmap UNSPECIFIED\_Pixmap

foreground **Pixel** 

helpCallback CallbackList

highlightColor **Pixel** black false

Boolean highlightOnEnter

highlightPixmap Pixmap

highlightThickness short 0

shadowThickness short

# Motif Widget Set, XmCascadeButton

topShadowColor	Pixel	
topShadowPixmap	Pixmap	UNSPECIFIED_Pixmap
traversalOn	Boolean	false
unitType	unsigned_char	PIXELS
userData	caddr_t	NULL
accelerators	Accelerators	
ancestorSensitive	Boolean	
background	Pixel	
backgroundPixmap	Pixmap	
borderColor	Pixel	
borderPixmap	Pixmap	
borderWidth	Dimension	1
colormap	Colormap	
depth	Cardinal	
destroyCallback	CallbackList	
height	Dimension	
mappedWhenManaged	Boolean	
screen	Screen	
sensitive	Boolean	
width	Dimension	
x	Position	
У	Position	
translations Translations:	<pre> <btmdown>: MenuBarSelect()  <enterwindow>: MenuBarEnter()  <leavewindow>: MenuBarLeave()  <btmup>: DoSelect()  <key>Return: KeySelect()  <key>Escape: CleanupMenuBar()  Shift<btm1down>,<btm1up>: pick()  Shift<btm2down>,<btm2motion>: resize()  Shift<btm2down>,<btm2motion>,<leave>,<btm2up>: resize() </btm2up></leave></btm2motion></btm2down></btm2motion></btm2down></btm1up></btm1down></key></key></btmup></leavewindow></enterwindow></btmdown></pre>	

Shift<Btm3Down>,<Btm3Motion>,<Btm3Up>: move()

Shift<Btn2Down>,t<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btn3Down>,<Btn3Motion>: move()

<b>Methods</b>		
<u>Name</u>	<u>Parameters</u>	<u>Description</u>
move	х, у	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
notify		This method is sent to the dialogue in response to a user event (typically a Bm1Down).
pisk	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse, and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# **XmCommand**

# **Serpent Name**

XmCommand

include\_file: Xm/Command.h
class: CommandWidgetClass

widget\_type: widget

# **Description**

The xmCommand widget is a special-purpose, composite widget for command entry that provides a built-in mechanism for displaying command histories. xmCommand includes a field for input from the command line, a command line prompt, and a region for displaying the command history list.

#### **Attributes**

Serpent

Name X Type Default
allowUserMove Boolean false

allowUserResize Boolean false

method MethodName

parent Widget

selectedX Position 0

selectedY Position 0

widget int

#### Command

Name X Type Default

command String

commandChangedCallback CallbackList commandEnteredCallback CallbackList

historyItems StringTable

-

historyItemCount i

historyMaxItems

int

historyVisibleItemCount int

promptString

String

SelectionBox Resource Set

<u>Name</u>

X Type

Default

applyCallback

CallbackList

applyLabelString

String

cancelCallback

CallbackList

cancelLabelString

String

dialogType

unsigned\_char

helpLabelString

String

listItemCount

int

listItems

StringList

listLabelString

String

listVisibleItemCount

int

minimizeButtons

Boolean

mustMatch

Boolean

noMatchCallback

CallbackList

okCallback

CallbackList

okLabelString

String

selectionLabelString

String

textAccelerators

**Translations** 

textColumns

int

textValue

String

**BulletinBoard Resource Set** 

Name

X Type

**Default** 

allowOverlap

Boolean

autoUnmanage

Boolean

buttonFontList

FontList

cancelButton

Widget

defaultButton

Widget

defaultPosition

Boolean

# Motif Widget Set, XmCommand

dialogStyle unsigned\_char

dialogTitle String

focusCallback CallbackList
labelFontList FontList

mapCallback CallbackList

marginHeight short
marginWidth short
noResize Boolean

resizePolicy unsigned\_char shadowType unsigned\_char stringDirection StringDirection

textFontList FontList
textTranslations
unmapCallback CallbackList

Manager Resource Set

Name X Type Default

bottomShadowColor Pixel

bottomShadowPixmap Pixmap UNSPECIFIED\_Pixmap

foreground Pixel

helpCallback CallbackList

highlightColor Pixel black

highlightPixmap Pixmap shadowThickness short topShadowColor Pixel

topShadowPixmap Pixmap UNSPECIFIED\_Pixmap

unitType unsigned\_char PIXELS userData caddr\_t NULL

**Composite Resource Set** 

Name X Type

insertPosition OrderProc

Core Resource Set		
Name	X Type	<u>Default</u>
accelerators	Accelerators	
ancestorSensitive	Boolean	
background	Pixel	
backgroundPixmap	Pixmap	
borderColor	Pixel	
borderPixmap	Pixmap	
horderWidth	Dimension	1
colormap	Colormap	
depth	Cardinal	
destroyCallback	CallbackList	
height	Dimension	
mappedWhenManaged	Boolean	
screen	Screen	
sensitive	Boolean	
width	Dimension	
x	Position	
У	Position	
translations Translations:	Shift <bm1down>,<bm1up>: pick() Shift<bm2down>,<bm2motion>: resize() Shift<bm2down>,<bm2motion>,<leave>,<bm2up>: resize() Shift<bm2down>,<bm2motion>,<bm2up>: resize() Shift<bm3down>,<bm3motion>: move() Shift<bm3down>,<bm3motion>,<leave>,<bm3up>: move() Shift<bm3down>,<bm3motion>,<leave>,<bm3up>: move()</bm3up></leave></bm3motion></bm3down></bm3up></leave></bm3motion></bm3down></bm3motion></bm3down></bm2up></bm2motion></bm2down></bm2up></leave></bm2motion></bm2down></bm2motion></bm2down></bm1up></bm1down>	

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	ж, у	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize this widget with the mouse and sends its x and y location and new width and height to the dialogue.

pick

selectedX, selectedY

This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# **XmDrawingArea**

# Serpent Name

XmDrawingArea

include\_file:Xm /DrawingA.h class: DrawingAreaWidgetClass

widget\_type: widget

# **Description**

The XmDrawingArea widget is an empty widget that is easily adaptable to a variety of purposes. It does no drawing and defines no behavior except for invoking callbacks. Callbacks notify the application when graphics need to be drawn (exposure events or widget resize) and when the widget receives input from the keyboard or mouse. Applications are responsible for defining appearance and behavior as needed in response to XmDrawingArea callbacks.

#### **Attributes**

Serpent

Default Name X Type Boolean false allowUserMove Boolean false allowUserResize MethodName method Widget parent **Position** 0 selectedX 0 **Position** 

widget int

## **DrawingArea**

selectedY

X Type Default Name

CallbackList exposeCallback CallbackList inputCallback short marginHeight

#### Motif Widget Set, XmDrawingArea

marginWidth

short

resizeCallback

CallbackList

resizePolicy

unsigned\_char

Manager Resource Set

<u>Name</u>

X Type

**Default** 

bottomShadowColor

**Pixel** 

D'----

 ${\tt bottomShadowPixmap}$ 

Pixmap

UNSPECIFIED\_Pixmap

 ${\tt foreground}$ 

Pixel

helpCallback

Pixel

CallbackList

black

highlightColor highlightPixmap

Pixmap

Diaci

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

**NULL** 

**Default** 

1

Composite Resource Set

Name

X Type

insertPosition

OrderProc

Core Resource Set

<u>Name</u>

X Type

Accelerators

accelerators ancestorSensitive

Boolean

background

Pixel

backgroundPixmap

Pixmap

borderColor

Pixel

borderPixmap

LIXEI

borderWidth

Pixmap Dimension

colormap

Colormap

depth

Cardinal

destroyCallback

CallbackList

height	Dimension
mappedWhenManaged	Boolean
screen	Screen
sensitive	Boolean
width	Dimension
x	Position
У	Position
translations Translations:	Shift <btn1down>,<btn1up>: pick() Shift<btn2down>,<btn2motion>: resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<btn2down>,<btn2motion>,<btn2up>: resize() Shift<btn3down>,<btn3motion>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<btn3up>: move() <shiftown>: Arm()</shiftown></btn3up></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></btn2motion></btn2down></btn2up></leave></btn2motion></btn2down></btn2motion></btn2down></btn1up></btn1down>

<Btn1Up>: Activate()
<EnterWindow>: Enter()
<FocusIn>: FocusIn()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	<b>x</b> , <b>y</b>	This method allows the user to move the widget with the mouse and sends the widget's new $x$ and $y$ location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# **XmDrawnButton**

# Serpent Name

XmDrawnButton

include\_file: Xm/DrawnB.h class: DrawnButtonWidgetClass

widget\_type: widget

# **Description**

The XmDrawnButton widget consists of an empty widget window surrounded by a shadow border. It provides the application developer with a graphics area in which PushButton input semantics may be used.

#### **Attributes**

Serpent

**Default** <u>Name</u> X Type Boolean allowUserMove false Boolean false allowUserResize MethodName method Widget parent **Position** selectedX 0 **Position** 0 selectedY widget int

#### **DrawnButton**

Name X Type Default

activateCallback CallbackList Sixcallback

armCallback CallbackList

disarmCallback CallbackList

exposeCallback CallbackList

pushButtonEnabled Boolean

resizeCallback

CallbackList

shadowType

unsigned\_char

**Resource Set** 

Name

X Type

accelerator

String

acceleratorText

String

alignment

unsigned\_char

fontList

**FontList** 

labelInsensitivePixmap

Pixmap

labelPixmap

Pixmap

labelString

String

labelType

unsigned\_char

marginBottom

short

marginHeight

short

marginLeft

short

marginRight

short

marginTop

marginWidth

short short

mnemonic

char

recomputeSize

Boolean

stringDirection

StringDirection

Primitive Resource Set

Name

X Type

**Default** 

bottomShadowColor

**Pixel** 

bottomShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

foreground

Pixel

helpCallback

CallbackList

highlightColor

Pixel

black

highlightOnEnter

Boolean

false

highlightPixmap

**Pixmap** 

short

0

shadowThickness

highlightThickness

short

2

#### Motif Widget Set, XmDrawnButton

topShadowColor

**Pixel** 

topShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

traversalOn

Boolean

false

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

**NULL** 

#### **Core Resource Set**

Name

X Type

**Default** 

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixel

backgroundPixmap

Pixmap

borderColor

Pixel

borderPixmap

**Pixmap** 

borderWidth

**Dimension** 

1

colormap

Colormap

depth

Cardinal

destroyCallback

CallbackList

height

Dimension

mappedWhenManaged

sensitive

Boolean

screen

Screen Boolean

width

Dimension

x

**Position** 

У

**Position** 

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Bm2Down>,<Bm2Motion>,<Bm2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

<Btn1Down>: Arm()

<Btn1Up>: Activate() Disarm() <Key>Return: ArmAndActivate() <Key>space: ArmAndActivate()

<EnterWindow>: Enter() <LeaveWindow>: Leave()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	х, у	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
notify		This method is sent to the dialogue in response to a user event (typically a Btn1Down).
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).

# **XmErrorDialog**

# Serpent Name

XmErrorDialog

include\_file: XM/MessageB.h
class: MessageBoxWidgetClass

widget\_type: widget

# **Description**

The XmErrorDialog widget is a MessageBox created with a convenience routine. This dialogue is used to warn a user about problem situations. The dialogue box comes with three buttons: OK, Cancel, and Help. The default symbol is an octagon with a diagonal slash.

## **Attributes**

Serpent

Name	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
deactivate	Boolean	false
isComposite	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	
MessageBox	CallbackList	
cancelLabelString	String	
defaultButtonType	unsigned_char	
dialogType	unsigned_char	
helpLabelString	String	
messageAlignment	unsigned_char	

messageString

String

minimizeButtons

Boolean

okCallback

CallbackList

okLabelString

String

symbolPixmap

Pixmap

### I ulletinBoard Resource Set

Name

X Type

allowOverlap

Boolean

autoUnmanage

Boolean

buttonFontList

FontList

cancelButton

Widget

 ${\tt defaultButton}$ 

Widget

defaultPosition

Boolean

dialogStyle

unsigned\_char

dialogTitle

String

focusCallback

CallbackList

labelFontList

FontList

mapCallback

CallbackList

marginHeight

short

marginWidth

short

noResize

Boolean

resizePolicy

unsigned\_char

shadowType

unsigned\_char

stringDirection

StringDirection

textFontList

FontList

textTranslations

**Translations** 

unmapCallback

CallbackList

#### Manager Resource Set

Name

X Type

**Default** 

bottomShadowColor

Pixel

bottomShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

foreground

Pixel

#### Motif Widget Set, XmErrorDialog

helpCallback

CallbackList

highlightColor

Pixel

Pixmap

black

highlightPixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

**NULL** 

### **Composite Resource Set**

Name

X Type

insertPosition

OrderProc

accelerators

Accelerators

ancestorSensitive

Boolean

background

**Pixel** 

backgroundPixmap

Pixmap

borderColor

Pixel

borderrixmap

Pixmap

borderWidth

Dimension

1

colormap

Colormap

depth

Cardinal

destroyCallback

mappedWhenManaged

CallbackList

height

Dimension

Boolean

screen

Screen Boolean

sensitive

width

Dimension

x

**Position** 

У

**Position** 

translations Translations: <EnterWindow>Enter()

<FocusIn>: FocusIn()

Shift<Btn1Down>,<Btn1Up>: pick()

<Btn1Down>: Arm()

<Btn1Up>: Activate()

<Key>F1: Help()

<Key>Return: Return()

<Key>KP\_Enter: Return()

Shift<Bm2Down>,<Bm2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Bm3Down>,<Bm3Motion>: move()

Shift<Bm3Down>,<Bm3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# **XmFileSelectionBox**

# Serpent Name

XmFileSelectionBox

include\_file: Xm/FileSB.h

class: FileSelectionBoxWidgetClass

widget\_type: widget

check\_routine: check\_FSB

# **Description**

The XmFileSelectionBox widget traverses directories, views the files in them, and then selects a file. An XmFileSelectionBox widget has four main areas:

• a directory mask that includes a filter label and a directory mask input field used to specify the directory that is to be examined

D - C- -- 14

- a scrollable list of file names
- a text input field for directly typing in a file name
- a group of PushButtons. OK, Filter, Cancel, and Help

#### **Attributes**

### Serpent

Name	X Type	Default
allowUserMove	Boolean	false
allowUserResize	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	

#### **FileSelectionBox**

<u>Name</u>	X Type
dirMask	String

dirSpec

String

fileSearchProc

Proc

filterLabelString

String

listUpdated

Boolean

#### SelectionBox Resource Set

Name

X Type

applyCallback

CallbackList

applyLabelString

String

cancelCallback

CallbackList

cancelLabelString

String

dialogType

unsigned\_char

helpLabelString

String

listItemCount

int

listItems

StringList

listLabelString

String

int

listVisibleItemCount minimizeButtons

Boolean

mustMatch

Boolean

noMatchCallback

okLabelString

CallbackList

okCallback

CallbackList

selectionLabelString

String String

textAccelerators

**Translations** 

textColumns

int

textValue

String

#### BulletinBoard Resource Set

Name

X Type

allowOverlap

Boolean

autoUnmanage

Boolean

buttonFontList

**FontList** 

cancelButton

Widget

defaultButton

Widget

#### Motif Widget Set, XmFileSelectionBox

defaultPosition

Boolean

dialogStyle

unsigned\_char

dialogTitle

String

focusCallback

CallbackList

labelFontList

**FontList** 

mapCallback

CallbackList

 ${\tt marginHeight}$ 

short

marginWidth

short

noResize

Boolean

resizePolicy

unsigned\_char

shadowType

unsigned\_char

stringDirection

StringDirection

textFontList

**FontList** 

textTranslations

Translations

unmapCallback

CallbackList

# Manager Resource Set

<u>Name</u>

X Type

**Default** 

black

bottomShadowColor

Pixel

bottomShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

foreground

Pixel

helpCallback

CallbackList

highlightColor

Pixel

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

NULL

## **Composite Resource Set**

<u>Name</u>

X Type

Default

insertPosition

**OrderProc** 

**Core Resource Set** 

Name X Type Default

accelerators Accelerators

ancestorSensitive Boolean

background Pixel

backgroundPixmap Pixmap borderColor Pixel

borderPixmap Pixmap

borderWidth Dimension 1

colormap Colormap depth Cardinal

destroyCallback CallbackList

height Dimension

mappedWhenManaged Boolean screen Screen

sensitive Boolean

width Dimension
x Position
y Position

translations Translations: <EnterWindow>:Enter()

<FocusIn>: FocusIn()

Shift<Btn1Down>,<Btn1Up>: pick()

<Btn1Down>: Arm()
<Btn1Up>: Activate()
<Key>F1: Help()
<Key>Return: Return()
<Key>KP\_Enter: Return()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Bm2Down>,<Btm2Motion>,<Btm2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

Methods

Name Parameters Description

move x, y This method allows the user to move the widget with the

mouse and sends the widget's new x and y location to the

dialogue.

## ${\bf Motif\ Widget\ Set}, {\tt XmFileSelectionBox}$

resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

## **XmForm**

## Serpent Name

XmForm

include\_file: Xm/Form.h
class: FormWidgetClass
widget\_type: widget

## **Description**

The XmForm widget is a container widget with no input semantics of its own. Constraints are placed on children of xmForm to define attachments for each of the child's four sides. These attachments can be to XmForm, to another child widget or gadget, to a relative position within XmForm, or to the initial position of the child. The attachments determine the layout behavior of xmForm when resizing occurs.

Attributes		
Name	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
focus	focus	
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	

Form	
NT	

Name X Type Default

fractionBase int
horizontalSpacing int
rubberPositioning Boolean

verticalSpacing int

#### Form Constraint

Name X Type
allowOverlap Boolean

bottomAttachment unsigned\_char

bottomOffset int bottomPosition int

bottomWidget Widget

leftAttachment unsigned\_char

leftOffset int leftPosition int

leftWidget Widget resizable Boolean

rightAttachment unsigned\_char

rightOffset int
rightPosition int
rightWidget Widget

topAttachment unsigned\_char

topOffset int
topPosition int
topWidget Widget

## BulletinBoard Resource Set

Name X Type
allowOverlap Boolean
autoUnmanage Boolean
buttonFontList FontList
cancelButton Widget
defaultButton Widget

defaultPosition Boolean

dialogTitle String

focusCallback

labelFontList

mapCallback

CallbackList

CallbackList

unsigned\_char

dialogStyle

marginHeight

short

marginWidth

short

noResize

Boolean

resizePolicy

unsigned\_char

shadowType

unsigned\_char

stringDirection

StringDirection

textFontList

**FontList** 

textTranslations

Translations

unmapCallback

CallbackList

Manager Resource Set

Name

X Type

**Default** 

bottomShadowColor

Pixel

bottomShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

foreground

Pixel

helpCallback

CallbackList

highlightColor

Pixel

black

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

NULL

**Composite Resource Set** 

Name

X Type

insertPosition

OrderProc

Core Resource Set

Name

X Type

Default

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixel

backgroundPixmap

Pixmap

## Motif Widget Set, XmForm

borderColor	Pixel
borderPixmap	Pixmap
borderWidth	Dimension 1
colormap	Colormap
depth	Cardinal
destroyCallback	CallbackList
height	Dimension
mappedWhenManaged	Boolean
screen	Screen
sensitive	Boolean
width	Dimension
x	Position
У	Position
translations Translations:	Shift <btm1down>,<btm1up>: pick() <btm1down>,<btm1up>: select() Shift<btm2down>,<btm2motion>: resize() Shift<btm2down>,<btm2motion>,<leave>,<btm2up>: resize() Shift<btm2down>,<btm2motion>,<btm2up>: resize() Shift<btm3down>,<btm3motion>: move() Shift<btm3down>,<btm3motion>,<leave>,<btm3up>: move() Shift<btm3down>,<btm3motion>,<btm3up>: move()</btm3up></btm3motion></btm3down></btm3up></leave></btm3motion></btm3down></btm3motion></btm3down></btm2up></btm2motion></btm2down></btm2up></leave></btm2motion></btm2down></btm2motion></btm2down></btm1up></btm1down></btm1up></btm1down>

Methods		
<u>Name</u>	<u>Parameter</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

## **XmFrame**

## **Serpent Name**

XmFrame

include\_file: Xm/Frame.h
class: FrameWidgetClass

widget\_type: widget

## **Description**

The XmFrame widget is a very simple manager used to enclose a single child in a border drawn by XmFrame. It uses the Manager class resources to draw borders and performs geometry management such that its size will always match its child's size plus the margins defined for it.

#### **Attributes**

Serpent

NameX TypeDefaultallowUserMoveBooleanfalseallowUserResizeBooleanfalse

method MethodName

parent Widget selectedX Position

selectedXPosition0selectedYPosition0

widget int

Frame

Name X Type marginWidth short

marginHeight short

shadowType unsigned\_char

**Resource Set** 

Name X Type Default

bottomShadowColor Pixel

bottomShadowPixmap Pixmap UNSPECIFIED\_Pixmap

foreground Pixel

helpCallback CallbackList

highlightColor Pixel black

highlightPixmap Pixmap shadowThickness short topShadowColor Pixel

topShadowPixmap Pixmap UNSPECIFIED\_Pixmap

unicType unsigned\_char PIXELS

userData caddr\_t NULL

**Composite Resource Set** 

Name X Type

insertPosition OrderProc

Core Resource Set

Name X Type Default

accelerators Accelerators

ancestorSensitive Boolean
background Pixel
backgroundPixmap Pixmap

borderColor Pixel
borderPixmap Pixmap
borderWidth Dimension
colormap Colormap

depth Cardinal

destroyCallback CallbackList
height Dimension

mappedWhenManaged Boolean

screen Screen sensitive Boolean

width		Dimension
x		Position
У		Position
translations	Translations:	Shift <bin1down>,<bin1up>: pick() Shift<bin2down>,<bin2motion>: resize() Shift<bin2down>,<bin2motion>,<leave>,<bin2up>: resize() Shift<bin2down>,<bin2motion>,<bin2up>: resize() Shift<bin3down>,<bin3motion>: move() Shift<bin3down>,<bin3motion>,<leave>,<bin3up>: move() Shift<bin3down>,<bin3motion>,<leave>,<bin3up>: move() Shift<bin3down>,<bin3motion>,<bin3up>:move() <enterwindow>: Enter() <focusin>: FocusIn() <bin1down>: Arm() <bin1up>: Activate()</bin1up></bin1down></focusin></enterwindow></bin3up></bin3motion></bin3down></bin3up></leave></bin3motion></bin3down></bin3up></leave></bin3motion></bin3down></bin3motion></bin3down></bin2up></bin2motion></bin2down></bin2up></leave></bin2motion></bin2down></bin2motion></bin2down></bin1up></bin1down>

Methods		
<u>Move</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# **XmInformationDialog**

## **Serpent Name**

XmInformationDialog

include\_file: Xm/MessageB.h

class: xmMessageBoxWidgetClass

widget\_type: widget

## **Description**

The XmInformationDialog widget is a XmMessageBox created with a convenience routine. This dialogue is used to provide a user with information. The dialogue box comes with three buttons: OK, Cancel, and Help. The default symbol is a lower case i.

#### **Attributes**

Serpent

Name	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserkesize	Boolean	false
deactivate	Boolean	false
isComposite	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	
MessageBox	CallbackList	
cancelLabelString	String	
defaultButtonType	unsigned_char	
dialogType	unsigned_char	
helpLabelString	String	
messageAlignment	unsigned_char	
messageString	String	

minimizeButtons

Boolean

okCallback

CallbackList

okLabelString

String

symbolPixmap

Pixmap

#### BulletinBoard Resource Set

<u>Name</u>

X Type

allowOverlap

Boolean

autoUnmanage

Boolean

buttonFontList

FontList

cancelButton

Widget

defaultButton

Widget

defaultPosition

Boolean

dialogStyle

unsigned\_char

dialogTitle

String

focusCallback

CallbackList

labelFontList

**FontList** 

mapCallback

CallbackList

 ${\tt marginHeight}$ 

short

marginWidth

short

noResize

Boolean

resizePolicy

unsigned\_char

shadowType

unsigned\_char

stringDirection

 ${\bf String Direction}$ 

textFontList

unmapCallback

Translations

**FontList** 

textTranslations

CallbackList

#### Manager Resource Set

Name

X Type

Default

bottomShadowColor

Pixel

bottomShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

foreground

**Pixel** 

 $\verb|helpCallback|$ 

CallbackList

#### Motif Widget Set, XmInformationDialog

highlightColor

Pixel

black

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

**Composite Resource Set** 

Name

X Type

insertPosition

OrderProc

Core Resource Set

Name

X Type

Default

1

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixel

backgroundPixmap

Pixmap

borderColor

Pixel

borderPixmap

Pixmap

borderWidth

Dimension

colormap

Colormap

depth

Cardinal

destroyCallback

CallbackList

height

Dimension

mappedWhenManaged

Boolean

screen

Screen

sensitive

Boolean

width

Dimension

x

**Position** 

**Position** 

translations Translations: <EnterWindow>: Enter()

<FocusIn>: FocusIn()

Shift<Btn1Down>,<Btn1Up>: pick()

<Bm1Down>: Arm()

<Btn1Up>: Activate()
<Key>F1: Help()
<Key>Return: Return()
<Key>KP\_Enter: Return()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Bm2Down>,<Bm2Motion>,<Leave>,<Bm2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Bm3Down>,<Btm3Motion>,<Leave>,<Btm3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

Methods		
<u>Name</u>	X Type	<u>Default</u>
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).
notify		This method is sent to the dialogue in response to a user event (typically a Btn1Down).

## **XmLabel**

## **Serpent Name**

XmLabel

include\_file: Xm/Label.h class: LabelWidgetClass

widget\_type: widget

## **Description**

The XmLabel widget is an instantiable widget and is also used as a superclass for other button widgets, such as PushButton and ToggleButton. The XmLabel widget does not accept any button or key input, and the help callback is the only callback defined. XmLabel also receives enter and leave events. It can contain either text or a Pixmap; its text is a compound string.

#### Attributes

Serpent

widget

Name X Type Default allowUserMove Boolean false Boolean false allowUserResize MethodName method parent Widget **Position** 0 selectedX **Position** selectedY 0 int

#### Label Resource Set

Name X Type accelerator String acceleratorText String

unsigned\_char alignment

**FontList** fontList

labelInsensitivePixmap Pixmap

**Pixmap** labelPixmap

String labelString

unsigned\_char labelType

marginBottom short marginHeight short short marginLeft short marginRight short marginTop marginWidth short

mnemonic char

Boolean recomputeSize StringDirection

**Primitive Resource Set** 

stringDirection

Default X Type Name

**Pixel** bottomShadowColor

**Pixmap** UNSPECIFIED\_Pixmap bottomShadowPixmap

Pixel foreground

CallbackList helpCallback

Pixel black highlightColor false Boolean highlightOnEnter

highlightPixmap **Pixmap** 

highlightThickness 0 short 2 shadowThickness short

Pixel topShadowColor

**Pixmap** UNSPECIFIED\_Pixmap topShadowPixmap

Boolean traversalOn false **PIXELS** unitType unsigned\_char

**NULL** caddr\_t userData

**Core Resource Set** 

accelerators Accelerators

Boolean ancestorSensitive

## Motif Widget Set, XmLabel

background	Pixel	
backgroundPixmap	Pixmap	
borderColor	Pixel	
borderPixmap	Pixmap	
borderWidth	Dimension 1	
colormap	Colormap	
depth	Cardinal	
destroyCallback	CallbackList	
height	Dimension	
mappedWhenManaged	Boolean	
screen	Screen	
sensitive	Boolean	
width	Dimension	
ж	Position	
У	Position	
translations Translations:	Shift <btn1down>,<btn1up>: pick() Shift<btn2down>,<btn2motion>: resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<btn2down>,<btn2motion>,<btn2up>: resize() Shift<btn3down>,<btn3motion>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<btn3up>: move() <enterwindow>: Enter() <leavewindow>: Leave()</leavewindow></enterwindow></btn3up></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></btn2motion></btn2down></btn2up></leave></btn2motion></btn2down></btn2motion></btn2down></btn1up></btn1down>	

Methods		
<u>Name</u>	<u>Parameter</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted BmlDown).

## **XmList**

## Serpent Name

XmList

include\_file: Xm/List.h
class: ListWidgetClass
widget\_type: widget

## Description

The XmList widget allows a user to select one or more items from a group of choices. Items are selected from the list in a variety of ways, with both the pointer and the keyboard. XmList operates on an array of strings that are defined by the application. Each string becomes an item in XmList, with the first string becoming the item in position 1, the second string becoming the item in position 2, and so on.

#### **Attributes**

Serpent

NameX TypeDefaultallowUserMoveBooleanfalseallowUserResizeBooleanfalse

method MethodName parentWidget selectedX Position 0

selectedY Position 0

widget int

#### List

Name X Type
automaticSelection Boolean
browseSelectionCallback CallbackList

defaultActionCallback CallbackList

doubleClickInterval int

extendedSelectionCallbackCallbackList

## Motif Widget Set, XmList

fontList

**FontList** 

itemCount

int

items

StringTable

listMarginHeight

Dimension

listMarginWidth

Dimension

listSpacing

short

 $\verb|multipleSelectionCallback| Callback List|$ 

selectedItemCount

int

selectedItems

StringTable

selectionPolicy

unsigned\_char

 $\verb|singleSelectionCallback| CallbackList|$ 

stringDirection

StringDirection

visibleItemCount

int

## ScrolledList

Name

X Type

horizontalScrollBar

Widget

listSizePolicy

unsigned\_char

scrollBarDisplayPolicy

unsigned\_char

scrollBarPlacement

unsigned\_char

scrolledWindowMarginHeightDimension

scrolledWindowMarginWidthDimension

spacing

Dimension

verticalScrollBar

Widget

#### **Primitive Resource Set**

Name

X Type

**Default** 

bottomShadowColor

Pixel

bottomShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

foreground

Pixel

helpCallback

CallbackList

highlightColor

Pixel

black

highlightOnEnter

Boolean

false

highlightPixmap

Pixmap

highlightThickness short 0
shadowThickness short 2

topShadowColor Pixel

topShadowPixmap Pixmap UNSPECIFIED\_Pixmap

traversalOn Boolean false
unitType unsigned\_char PIXELS

userData caddr\_t NULL

**Core Resource Set** 

Name X Type Default

accelerators Accelerators

ancestorSensitive Boolean

background Pixel
backgroundPixmap Pixmap

borderColor Pixel
borderPixmap Pixmap

borderWidth Dimension 1

colormap Colormap depth Cardinal

destroyCallback CallbackList

height Dimension

mappedWhenManaged Boolean

screen Screen sensitive Boolean

width Dimension

x Position
y Position

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Bm3Down>,<Bm3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>:

move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>:move()

Button1<Motion>: ListButtonMotion()

Shift Ctrl ~Meta<Btn1Down>: ListShiftCtrlSelect()

Shift Ctrl ~Meta<Btn1Up>: ListShiftCtrlUnSelect() Shift Ctrl ~Meta<keyDown>space: ListKbdShiftCtrlSelect() Shift Ctrl ~Meta<KeyUp>space: ListKbdShiftCtrlUnSelect() Shift Ctrl ~Meta<KeyDown>Select: ListKbdShiftCtrlSelect() Shift Ctrl ~Meta<KeyUp>Select: ListKbdShiftCtrlUnSelect() Shift ~Ctrl ~Meta<Btn1Down>: ListShiftSelect() Shift ~Ctrl ~Meta<Btn1Up>: ListShiftUnSelect() Shift ~Ctrl ~Meta<KeyDown>space: ListKbdShiftSelect() Shift ~Ctrl ~Meta<KeyUp>space: ListKbdShiftUnSelect() Shift ~Ctrl ~Meta<KeyDown>Select: ListKbdShiftSelect() Shift~Ctrl ~Meta<KeyUp>Select: ListKbdShiftUnSelect() Ctrl ~Shift ~Meta<Btn1Down>: ListCtrlSelect() Ctrl ~Shift ~Meta<Btn1Up>: ListCtrlUnSelect() Ctrl ~Shift ~Meta<KeyDown>space: ListKbdCtrlSelect() Ctrl ~Shift ~Meta<KeyUp>space: ListKbdCtrlUnSelect() Ctrl ~Shift ~Meta<KeyDown>Select: ListKbdCtrlSelect() Ctrl ~Shift ~Meta<KeyUp>Select: ListKbdCtrlUnSelect() ~Shift ~Ctrl ~Meta<Btn1Down>: ListElementSelect() ~Shift ~Ctrl ~Meta<Btn1Up>: ListElementUnSelect() ~Shift ~Ctrl ~Meta<KeyDown>space: ListKbdSelect() ~Shift ~Ctrl ~Meta<KeyUp>space: ListKbdUnSelect() ~Shift ~Ctrl ~Meta<KeyDown>Select: ListKbdSelect() ~Shift ~Ctrl ~Meta<KeyUp>Select: ListKbdUnSelect() Shift Ctrl ~Meta<Key>Up: ListShiftCtrlPrevElement() Shift Ctrl ~Meta<Key>Down: ListShiftCtrlNextElement() Shift ~Ctrl ~Meta<Key>Up: ListShiftPrevElement() Shift ~Ctrl ~Meta<Key>Down: ListShiftNextElement() ~Shift Ctrl ~Meta<Key>Up: ListCtrlPrevElement() ~Shift Ctrl ~Meta<Key>Down: ListCtrlNextElement() ~Shift ~Ctrl ~Meta<Key>Up: ListPrevElement() ~Shift ~Ctrl ~Meta<Key>Down: ListNextElement() <Enter>: ListEnter() <Leave>: ListLeave() <FocusIn>: ListFocusIn() <FocusOut>: ListFocusOut() <Unmap>: PrimitiveUnmap() Shift<Key>Tab: PrimitivePrevTabGroup() Ctrl<Key>Tab: PrimitiveNextTabGroup() <Key>Tab: PrimitiveNextTabGroup() <Key>Home: PrimitiveTraverseHome()

Methods		
<u>Name</u>	<u>Parameter</u>	Description
move	х, у	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.

resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

## **XmMainWindow**

## Serpent Name

xmMainWindow

include\_file: Xm/MainW.h

class: MainWindowWidgetClass

widget\_type: widget

check\_routine: check\_MainW

## **Description**

The XmMainWindow widget provides a standard layout for the primary window of an application. This layout includes an MenuBar, an CommandWindow, a work region, and ScrollBars. Any or all of these areas are optional. The work region and prog in the XmMainWindow behave identically to the work region and ScrollBars in the ScrolledWindow widget. (The user can think of the XmMainWindow as an extended ScrolledWindow with an optional MenuBar and optional CommandWindow.)

#### **Attributes**

Serpent

Name	<u>X Type</u>	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	

#### MainWindow

Name X Type commandWindow Widget

mainWindowMarginHeight

Dimension

mainWindowMarcinWidth

Dimension

menuBar

Widget

showSeparator

Boolean

#### ScrolledWindow Resource Set

Name

X Type

clipWindow

Widget

horizontalScrollBar

Widget

scrollBarDisplayPolicy

unsigned\_char

scrollBarPlacement

unsigned\_char

scrolledWindowMarginHeightDimension  ${\tt scrolledWindowMarginWidth} {\bf Dimension}$ 

scrollingPolicy

unsigned\_char

spacing

int

verticalScrollBar

Widget

visualPolicy

unsigned\_char

workWindow

Widget

## Manager Resource Set

Name

X Type

Default

bottomShadowColor

**Pixel** 

bottomShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

foreground

Pixel

helpCallback

CallbackList

highlightColor

Pixel

black

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

**NULL** 

Composite Resource Set

Name X Type Default

insertPosition OrderProc

Core Resource Set

Name X Type Default

accelerators Accelerators

ancestorSensitive Boolean

background Pixel backgroundPixmap Pixmap

borderColor Pixel

borderPixmap Pixmap

DorderWidth Dimension 1

colormap
depth
Cardinal

destroyCallback CallbackList

height Dimension

mappedWhenManaged Boolean screen Screen

sensitive Boolean width Dimension

x Position
y Position

Translations Translations Shift<Btn1Down>,<Btn1Up>: pick()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shirt<Btn3Down>,<Btn3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

Methods

Name Parameters Description

move x, y This method allows the user to move the wid

This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the

dialogue.

resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted BmlDown).

## XmMenubar

## **Serpent Name**

XmMenubar

include\_file: Xm/RowColumn.h
class: RowColumnWidgetClass

widget\_type: widget

## **Description**

The XmMenuBar widget is a specially configured RowColumn widget created with a convenience routine. It is used to build a pulldown menu.

#### Attributes

Serpent

Name X Type Default Boolean false allowUserMove false Boolean allowUserResize MethodName method Widget parent **Position** 0 selectedX **Position** 0 selectedY

int

## RowColumn

widget

Name X Type

adjustLast Boolean

adjustMargin Boolean

entryAlignment unsigned\_char

entryBorder short

entryCallback CallbackList

entryCallback CallbackList entryClass WidgetClass

## Motif Widget Set, XmMenubar

Boolean isAligned Boolean isHomogeneous

String labelString

mapCallback CallbackList Dimension marginHeight Dimension marginWidth

String menuAccelerator Widget menuHelpWidget Widget menuHistory mnemonic char short numColumns

unsigned\_char orientation unsigned\_char packing

popupEnabled Boolean Boolean radioAlwaysOne Boolean radioBehavior Boolean resizeHeight resizeWidth Boolean

unsigned\_char rowColumnType

short spacing Widget subMenuId unmapCallback CallbackList unsigned\_int whichButton

RowColumn Special Menu

<u>Name</u> X Type menuCursor String

Manager Resource Set

Name X Type **Default** 

bottomShadowColor Pixel

Pixmap UNSPECIFIED\_Pixmap bottomShadowPixmap

Pixel foreground

CallbackList helpCallback

#### Motif Widget Set, XmMenubar

highlightColor

Pixel

black

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

unitType

unsigned\_char

PIXELS

userData

caddr\_t

NULL

#### **Composite Resource Set**

Name

X Type

insertPosition

OrderProc

#### Core Resource Set

Name

X Type

Default

1

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixel

backgroundPixmap

Pixmap

borderColor

Pixel

 ${\tt borderPixmap}$ 

Pixmap

borderWidth

Dimension

colormap

Colormap

depth

Cardinal

destroyCallback

CallbackList

height

Dimension

mappedWhenManaged

Boolean

screen

Screen

sensitive

Boolean

width

Dimension

x

Position

У

Position

Translations Translations

<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Bm3Down>,<Bm3Motion>,<Leave>,<Bm3Up>: move()

## Shift<Bm3Down>,<Btn3Motion>,<Btn3Up>: move()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its $x$ and $y$ location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

## **XmMenuShell**

Serpent Name

XmMenuShell

include\_file: Xm/MenuShell.h
class: MenuShellWidgetClass

widget\_type: override

**Description** 

The XmMenuShell widget is a custom OverrideShell widget. An OverrideShell widget bypasses the window manager when displaying itself. It is designed specifically to contain Popup or

Pulldown MenuPanes.

**Attributes** 

Serpent

Name X Type Default

allowUserMove Boolean false allowUserResize Boolean false

parent Widget

method MethodName

Shell

Name X Type Default

Name

allowShellResize Boolean

createPopupChildProc Boolean

geometry caddr\_t

overrideRedirect Boolean

popdownCallback CallbackList

popupCallback CallbackList

saveUnder Boolean

**Composite Resource Set** 

Name X Type

insertPosition OrderProc

**Core Resource Set** 

Name X Type Default

accelerators Accelerators

ancestorSensitive Boolean

background Pixel

backgroundPixmap Pixmap

borderColor Pixel
borderPixmap Pixmap

borderWidth Dimension 1

colormap Colormap depth Cardinal

destroyCallback CallbackList

height Dimension

mappedWhenManaged Boolean

screen Screen sensitive Boolean

width Dimension

x Position
y Position

translations Translations: Shift<Btn2Down>,<Btn2Motion>:resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

<BtnDown>: ClearTraversal()

<Key>Escape: MenuShellPopdownDone() <BtnUp>:

MenuShellPopdownDone()

Methods		
<u>Name</u>	<u>Parameters</u>	<u>Description</u>
move	х, у	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.

# **XmMessageBox**

## Serpent Name

XmMessageBox

include\_file: Xm/MessageB.h
class: MessageBoxWidgetClass

widget\_type: widget

## **Description**

The XmMessageBox widget is a dialogue class widget used for creating simple message dialogues. Convenience dialogues based on XmMessageBox are provided for several common interaction tasks, including giving information, asking questions, and reporting errors.

#### **Attributes**

Serpent

<u>Name</u> **Default** X Type Boolean false allowUserMove Boolean false allowUserResize Boolean false isComposite MethodName method Widget parent **Position** selectedX 0 **Position** 0 selectedY widget int

#### MessageBox

Name X Type

cancelCallback CallbackList

cancelLabelString String

defaultButtonType unsigned\_char dialogType unsigned\_char

#### Motif Widget Set, XmMessageBox

helpLabelString

String

messageAlignment

unsigned\_char

messageString

String

minimizeButtons

Boolean

okCallback

CallbackList

okLabelString

String

symbolPixmap

Pixmap

## **BulletinBoard Resource Set**

Name

X Type

allowOverlap

Boolean

autoUnmanage

Boolean

buttonFontList

FontList

cancelButton

....

Widget

defaultButton

Widget Boolean

defaultPosition

unsigned\_char

dialogStyle
dialogTitle

String

focusCallback

tCallbackList

labelFontList

FontList

mapCallback

CallbackList

marginHeight

short

marginWidth

short

noResize

Boolean

resizePolicy

unsigned\_char

shadowType

unsigned\_char

stringDirection

StringDirection

textFontList

**FontList** 

textTranslations

**Translations** 

unmapCallback

CallbackList

## Manager Resource Set

Name

X Type

**Default** 

bottomShadowColor

Pixel

bottomShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

foreground

Pixel

helpCallback

CallbackList

highlightColor

Pixel

black

highlightPixmap shadowThickness Pixmap short

topShadowColor

SHOLL

topShadowPixmap

Pixel Pixmap

UNSPECIFIED\_Pixmap

unitType

unsigned\_char

**FIXELS** 

userData

caddr\_t

**NULL** 

**Composite Resource Set** 

Name

X Type

insertPosition

OrderProc

**Core Resource Set** 

Name

X Type

**Default** 

1

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixel

backgroundPi:map

Pixmap

borderColor

Pixel

borderPixmap

Pixmap

borderWidth

Dimension

colormap

Colormap

depth

Cardinal

destroyCallback

CallbackList

height

Dimension

mappedWhenManaged

Boolean

screen

Screen

sensitive

Boolean

width

Dimension

x

Position

у

**Position** 

## Motif Widget Set, XmMessageBox

translations Translations:	<enterwindow>:Enter() <focusin>: FocusIn() <btn1down>: Arm() <btn1up>: Activate() <key>F1: Help() <key>Return: Return() <key>KP_Enter: Return() Shift<btn1down>,<btn1up>: pick() Shift<btn2down>,<btn2motion>: resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<btn3down>,<btn3motion>; move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<btn3up>: move()</btn3up></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></leave></btn2motion></btn2down></btn2motion></btn2down></btn1up></btn1down></key></key></key></btn1up></btn1down></focusin></enterwindow>
----------------------------	--

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1 Down)

# XmMessageDialog

## **Serpent Name**

XmMessageDialog

include\_file Xm/MessageB.h

class: xmMessageBoxWidgetClass

widget\_type: widget

## Description

The xmMessageDialog widget is a MessageBox created with a convenience routine. This convenience routine creates a MessageBox parented to a dialogue shell.

## Attributes

minimizeButtons

Serpent

<u>Name</u>	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
deactivate	Boolean	faise
isComposite	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	Widget	
MessageBox	CallbackList	
cancelLabelString	String	
defaultButtonType	unsigned_char	
dialogType	unsigned_char	
helpLabelString	String	
messageAlignment	unsigned_char	
messageString	String	

Boolean

#### Motif Widget Set, XmMessageDialog

okCallback

CallbackList

okLabelString

String

symbolPixmap

Pixmap

#### **BulletinBoard Resource Set**

Name

X Type

allowOverlap

Boolean

autoUnmanage

Boolean

buttonFontList

FontList

cancelButton
defaultButton

Widget

defaultPosition

Widget Boolean

dialogStyle

unsigned\_char

dialogTitle

String

focusCallback

CallbackList

labelFontList

FontList

mapCallback

CallbackList

marginHeight

short

marginWidth

short

noResize

Boolean

resizePolicy

unsigned\_char

shadowType

unsigned\_char

 ${\tt stringDirection}$ 

StringDirection

textFontList

**FontList** 

textTranslations

**Translations** 

unmapCallback

CallbackList

#### Manager Resource Set

Name

X Type

**Default** 

bottomShadowColor

Pixel

bottomShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

foreground

Pixel

helpCallback

CallbackList

highlightColor

**Pixel** 

black

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

unitType

unsigned\_char

PIXELS

userData

caddr\_t

**NULL** 

Composite Resource Set

Name

X Type

insertPosition

OrderProc

**Core Resource Set** 

Name

X Type

**Default** 

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixe!

backgroundPixmap

Pixmap

borderColor

Pixel

borderPixmap

**Pixmap** 

borderWidth

Dimension

1

colormap

Colormap

depth

Cardinal

destroyCallback

mappedWhenManaged

CallbackList

height

Dimension

Boolean

screen

Screen

sensitive

Boolean

width

Dimension

х

**Position** 

У

**Position** 

translations Translations: EnterWindow>:Enter()

<FocusIn>: FocusIn()

Shift<Btn1Down>,<Btn1Up>: pick()

<Bm1Down>: Arm() <Bm1Up>: Activate()

<Key> F1: Help()

<Key>Return: Return()
<Key>KP\_Enter: Return()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Bm2Down>,<Bm2Motion>,<Leave>,<Bm2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btm3Down>,<Btm3Motion>,<Leave>,<Btm3Up>: move()

Shift<Btm3Down>,<Btm3Motion>,<Btm3Up>: move()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedY, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

## **XmOption**

#### Serpent Name

XmOption

include\_file: Xm/RowColumn.h class. RowColumnWidgetClass

widget\_type: widget

convenience\_routine: CreateOptionMenu

#### **Description**

The Xmoption widget provides the application with the means for obtaining the widget ID for the internally created CascadeButtonGadget. Once the application has obtained the widget ID, it has the ability to adjust the visuals for the CascadeButtonGadget.

#### **Attributes**

Serpent

Name X Type **Default** allowUserMove Boolean false Boolean false allowUserResize Boolean true isComposite Boolean manage true MethodName method Widget parent **Position** 0 selectedX selectedY **Position** int widget

#### RowColumn

Name X Type
adjustLast Boolean
adjustMargin Boolean

#### Motif Widget Set, xmOption

entryAlignment unsigned\_char

entryBorder short

entryCallback CallbackList
entryClass WidgetClass
isAligned Boolean

isHomogeneous Boolean labelString String

mapCallback CallbackList
marginHeight Dimension
marginWidth Dimension

menuAccelerator String
menuHelpWidget Widget
menuHistory Widget
mnemonic char
numColumns short

crientation unsigned\_char packing unsigned\_char

popupEnabled Boolean
radioAlwaysOne Boolean
radioBehavior Boolean
resizeHeight Boolean
resizeWidth Boolean

rowColumnType unsigned\_char

spacing short

subMenuId Widget

unmapCallback CallbackList
whichButton unsigned\_int

#### RowColumn Special Menu

Name X Type
menuCursor String

Manager Resource Set

Name X Type Default

bottomShadowColor Pixel

bottomShadowPixmap Pixmap UNSPECIFIED\_Pixmap

foreground Pixel

helpCallback CallbackList

highlightColor Pixel black

highlightPixmap Pixmap shadowThickness short topShadowColor Pixel

topShadowPixmap Pixmap UNSPECIFIED\_Pixmap

unitType unsigned\_char PIXELS
userData caddr\_t NULL

**Composite Resource Set** 

Name X Type
insertPosition OrderProc

Core Resource Set

Name X Type Default

accelerators Accelerators
ancestorSensitive Boolean
background Pixel

backgroundPixmap Pixmap
borderColor Pixel
borderPixmap Pixmap

borderWidth Dimension 1

colormap Colormap depth Cardinal

destroyCallback CallbackList
height Dimension
mappedWhenManaged Boolean
screen Screen

sensitive Boolean

#### Motif Widget Set, XmOption

width		Dimension
x		Position
У		Position
translations	Translations:	Shift <btn1down>,<btn1up>: pick() Shift<bm2down>,<btn2motion>: resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<btn2down>,<btn2motion>,<btn2up>: resize() Shift<btn3down>,<btn3motion>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<btn3up>: move()</btn3up></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></btn2motion></btn2down></btn2up></leave></btn2motion></btn2down></btn2motion></bm2down></btn1up></btn1down>

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	х, у	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

### **XmPanedWindow**

#### Serpent Name

XmPanedWindow

include\_file: Xm/PanedW.h

class: PanedWindowWidgetClass

widget\_type: widget

#### **Description**

The XmPanedWindow widget is a composite widget that lays out children in a vertically tiled format. Children appear in top-to-bottom fashion, with the child that is inserted first appearing at the top of XmPanedWindow and the child inserted last appearing at the bottom. XmPanedWindow will grow to match the width of its widest child and all other children are forced to this width. The height of XmPanedWindow will be equal to the sum of the heights of all of its children, the spacing between them, and the size of the top and bottom margins.

#### Attributes

Serpent

<u>Name</u>	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	

#### **PanedWindow**

Name X Type marginHeight short

#### Motif Widget Set, XmPanedWindow

marginWidth

short

refigureMode

Boolean

sashHeight

Dimension

sashIndent

Position

sashShadowThickness

int

sashWidth

Dimension

separatorOn

Boolean

spacing

int

#### PanedWindow Constraint

Name

X Type

allowResize

Boolean

maximum

int

minimum

int

skipAdjust

Boolean

#### Manager Resource Set

Name

X Type

**Default** 

bottomShadowColor

Pixel

bottomShadowrixmap

Pixmap

UNSFECIFIED\_Pixmap

foreground

**Pixel** 

helpCallback

CallbackList

highlightColor

Pixel

black

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

unitType

unsigned\_char

PIXELS

userData

caddr\_t

NULL

#### Core Resource Set

<u>Name</u>

X Type

**Default** 

accelerators

Accelerators

ancestorSensitive

Boolean

h	Pixel
background	
backgroundPixmap	Pixmap
borderColor	Pixel
borderPimmap	Pixmap
borderWidth	Dimension 1
colormap	Colormap
depth	Cardinal
destroyCallback	CallbackList
height	Dimension
mappedWhenManaged	Boolean
screen	Screen
sensitive	Boolean
width	Dimension
x	Position
У	Position
translations Translations:	Shift <btn1down>,<btn1up>: pick() Shift<btn12down>,<btn2motion>: resize() Shift<btn12down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<btn12down>,<btn12motion>,<btn12up>: resize() Shift<btn12down>,<btn13motion>: move() Shift<btn13down>,<btn13motion>,<leave>,<btn13up>: move() Shift<btn13down>,<btn13motion>,<btn13up>: move() <hr/> Shift<btn13down>,<btn13motion>,<btn13up>: move() <hr/> <hr< td=""></hr<></btn13up></btn13motion></btn13down></btn13up></btn13motion></btn13down></btn13up></leave></btn13motion></btn13down></btn13motion></btn12down></btn12up></btn12motion></btn12down></btn2up></leave></btn2motion></btn12down></btn2motion></btn12down></btn1up></btn1down>

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	х, у	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted BmlDown).

# **XmPopup**

### Serpent Name

XmPopup

include\_file: Xm/RowColumn.h
class: RowColumnWidgetClass

widget\_type: widget

#### **Description**

XmPopUp is a convenience routine which creates a RowColumn

widget configured as an XmPopup menu.

#### Attributes

Serpent

Name	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
isComposite	Boolean	true
manage	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	

#### **RowColumn**

<u>Name</u>	X Type
adjustLast	Boolean
adjustMargin	Boolean
entryAlignment	unsigned_char
	1

entryBorder short

entryCallback CallbackList

entryClass

WidgetClass

isAligned

Boolean

isHomogeneous

Boolean

labelString

String

mapCallback

CallbackList

marginHeight

Dimension

marginWidth

Dimension

menuAccelerator

String

menuHelpWidget

Widget

menuHistory

Widget

mnemonic

char

numColumns

short

orientation

unsigned\_char

packing

unsigned\_char

popupEnabled

Boolean

radioAlwaysOne

Boolean

radioBehavior

Boolean

resizeHeight

Boolean

resizeWidth

Boolean

rowColumnType

unsigned\_char

spacing

short

subMenuId

Widget

unmapCallback

CallbackList

whichButton

unsigned\_int

#### RowColumn Special Menu

Name

X Type

menuCursor

String

Manager Resource Set

Name

X Type

**Default** 

bottomShadowColor

**Pixel** 

bottomShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

foreground

Pixel

#### Motif Widget Set, XmPopup

helpCallback

CallbackList

highlightColor

Pixel

black

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

**NULL** 

Composite Resource Set

Name

X Type

insertPosition

OrderProc

**Core Resource Set** 

Name

X Type

**Default** 

1

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixel

backgroundPixmap

Pixmap

borderColor

**Pixel** 

borderPixmap

Pixmap

borderWidth

Dimension

colormap

Colormap

depth

Cardinal

destroyCallback

CallbackList

height

Dimension

mappedWhenManaged

Boolean

screen

Screen

sensitive

Boolean

width

Dimension

x

**Position Position** 

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Bm2Down>,<Bm2Motion>,<Leave>,<Bm2Up>: resize() Shift<Bm2Down>,<Bm2Motion>,<Bm2Up>: resize() Shift<Bm3Down>,<Bm3Motion>: move() Shift<Bm3Down>,<Bm3Motion>,<Leave>,<Bm3Up>: rove() Shift<Bm3Down>,<Bm3Motion>,<Bm3Up>: move()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).

### **XmPulldown**

Serpent Name

XmPulldown

include\_file: /RowColumn.h
class: RowColumnWidgetClass

widget\_type: widget

**Description** 

The XmPulldown widget is a convenience routine that creates a

RowColumn widget configured as an Popup menu.

**Attributes** 

Serpent

NameX TypeDefaultallowUserMoveBooleanfalseallowUserResizeBooleanfalseisCompositeBooleantruemanageBooleanfalse

MethodName

method

parent Widget
selectedX Position 0
selectedY Position 0
widget int

RowColumn

Name X Type
adjustLast Boolean
adjustMargin Boolean
entryAlignment unsigned\_char

entryBorder short

entryCallback CallbackList

entryClass WidgetClass

isAligned Boolean
isHomogeneous Boolean
labelString String

mapCallback CallbackList
marginHeight Dimension
marginWidth Dimension
menuAccelerator String
menuHelpWidget Widget
menuHistory Widget

mnemonic char
numColumns short

orientation unsigned\_char packing unsigned\_char

popupEnabled Boolean
radioAlwaysOne Boolean
radioBehavior Boolean
resizeHeight Boolean
resizeWidth Boolean

rowColumnType unsigned\_char

spacing short
subMenuId Widget
unmapCallback Callback

unmapCallback CallbackList whichButton unsigned\_int

RowColumn Special Menu

Name X Type
menuCursor String

Manager Resource Set

Name X Type Default

bottomShadowColor Pixel

bottomShadowPixmap Pixmap UNSPECIFIED\_Pixmap

foreground Pixel

#### Motif Widget Set, XmPulldown

helpCallback

CallbackList

highlightColor

Pixel

black

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

UNSPECIFIED\_Pixmap

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

Pixmap

**NULL** 

**Composite Resource Set** 

Name

X Type

insertPosition

OrderProc

Core Resource Set

Name

X Type

Default

1

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixel

backgroundPixmap

Pixmap

borderColor

**Pixel** 

borderPixmap

Pixmap

borderWidth

Dimension

colormap

Colormap

depth

Cardinal

destroyCallback

CallbackList

height

Dimension

mappedWhenManaged

Boolean

screen

Screen

sensitive

Boolean

width

Dimension

x

**Position** 

У

**Position** 

translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Bm3Down>,<Bm3Motion>,<Leave>,<Btn3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).

### **XmPushButton**

#### **Serpent Name**

XmPushButton

include\_file: /PushB.h

class: PushButtonWidgetClass

widget\_type: widget

#### **Description**

The XmPushButton widget issues commands within an application. It consists of a text label or Pixmap surrounded by a border shadow. When XmPushButton is selected, the shadow moves to give the appearance that it has been pressed in. When XmPushButton is not selected, the shadow moves to give the appearance that it is out.

#### **Attributes**

Serpent

Name X Type Default

after Widgel

allowUserMove Boolean
allowUserResize Boolean
managedWhenCreated Boolean

method MethodName

parent Widget

selectedX Position 0

selectedY Position 0

widget int

#### **PushButton**

Name X Type Default
activateCallback CallbackList Sixcallback

armCallback CallbackList

armColor Pixel

armPixmap

Pixmap

disarmCallback

CallbackList

fillOnArm

Boolean

showAsDefault

short

#### **Label Resource Set**

Name

X Type

accelerator

String

acceleratorText

String

alignment

unsigned\_char

fontList

**FontList** 

labelInsensitivePixmap

Pixmap

labelPixmap

**Pixmap** 

labelString

String

labelType

unsigned\_char

marginBottom

short

marginHeight

short

marginLeft

short

marginRight

short

marginTop

short

marginWidth

short

mnemonic

char

recomputeSize

Boolean

stringDirection

StringDirection

#### **Primitive Resource Set**

Name

X Type

Default

bottomShadowColor

Pixel

bottomShadowPixmap

**Pixmap** 

UNSPECIFIED\_Pixmap

foreground

Pixel

helpCallback

CallbackList

highlightColor

Pixel

black

highlightOnEnter

Boolean

false

highlightPixmap

**Pixmap** 

#### Motif Widget Set, XmPushButton

highlightThickness	short	0
shadowThickness	short	2

topShadowColor Pixel

topShadowPixmap Pixmap UNSPECIFIED\_Pixmap

traversalOn Boolean false
unitType unsigned\_char PIXELS
userData caddr\_t NULL

**Core Resource Set** 

Name X Type <u>Default</u>

accelerators Accelerators
ancestorSensitive Boolean
background Pixel
backgroundPixmap Pixmap
borderColor Pixel
borderPixmap Pixmap

borderWidth Dimension 1

Colormap colormap Cardinal depth CallbackList destroyCallback Dimension height Boolean mappedWhenManaged screen Screen Boolean sensitive Dimension width

y Position
translations Translations: Shift<Btn1Down>,<Btn1Up>: pick()

**Position** 

De la Caraciana de la Caracian

<Btn1Down>:Arm()<Btn1Up>: Activate()Disarm()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

Shift<Bm3Down>,<Bm3Motion>,<Leave>,<Bm3Up>: move()

<Key>Return: ArmAndActivate() <Key>space: ArmAndActivate()

x

<EnterWindow>: Enter()
<LeaveWindow>: Leave()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	<b>x</b> , <b>y</b>	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
notify		This method is sent to the dialogue in response to a user event (typically a Btn1Down).
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# **XmQuestionDialog**

#### Serpent Name

XmQuestionDialog

include\_file: Xm/MessageB.h class: MessageBoxWidgetClass

widget\_type: widget

#### **Description**

The XmQuestionDialog widget is a MessageBox created with a convenience routine. This dialogue is used to get an answer to a question from a user. The dialogue box comes with three buttons: OK, Cancel, and Help. The default symbol is a question mark.

#### **Attributes**

Serpent

Name X Type **Default** Boolean false allowUserMove allowUserResize Boolean false Boolean false deactivate Boolean false isComposite MethodName method Widget parent **Position** 0 selectedX **Position** selectedY

widget

int

MessageBox

CallbackList

cancelLabelString

String

defaultButtonType

unsigned\_char

dialogType

unsigned\_char

helpLabelString

String

messageAlignment

unsigned\_char

messageString

String

minimizeButtons

Boolean

okCallback

CallbackList

okLabelString

String

symbolPixmap

Pixmap

#### **BulletinBoard Resource Set**

Name X Type

allowOverlap Boolean autoUnmanage Boolean

buttonFontList FontList

cancelButton Widget

defaultButton Widget defaultPosition Boolean

dialogStyle unsigned\_char

dialogTitle String

focusCallback
labelFontList

CallbackList
FontList

mapCallback CallbackList

marginHeight short marginWidth short

noResize Boolean

resizePolicy unsigned\_char
shadowType unsigned\_char
stringDirection StringDirection

textFontList FontList
textTranslations
unmapCallback CallbackList

Manager Resource Set

Name X Type Default

bottomShadowColor Pixel

bottomShadowPixmap Pixmap UNSPECIFIED\_PIXMAP

foreground Pixel

helpCallback CallbackList

#### Motif Widget Set, XmQuestionDialog

highlightColor

Pixel

black

highlightPixmap

Pixmap

shadowThickness

short

topShadowCclor

Pixel

topShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

**NULL** 

Composite Resource Set

Name

X Type

insertPosition

OrderProc

**Core Resource Set** 

Name

X Type

<u>Default</u>

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixel

backgroundPixmap

Pixmap

borderColor

Pixel

borderPixmap

Pixmap

borderWidth

Dimension

colormap

Colormap

depth

Cardinal

destroyCallback

CallbackList

height

Dimension

mappedWhenManaged

Boolean

screen

Screen

sensitive

Boolean

width

Dimension

х

Position

**Position** 

translations Translations: <EnterWindow>: Enter()

<FocusIn>: FocusIn()

Shift<Btn1Down>,<Btn1Up>: pick()

<Btn1Down>: Arm()

<Btn1Up>: Activate() <Key>F1: Help() <Key>Return: Return() <Key>KP\_Enter: Return()

Shift<Bm2Down>,<Btm2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Bm3Down>,<Bm3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Bm3Down>,<Bm3Motion>,<Bm3Up>: move()

Methods		
<u>Name</u>	X Type	<u>Default</u>
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).

### **XmRowColumn**

#### Serpent Name

XmRowColumn

include\_file: /RowColumn.h
class: RowColumnWidgetClass

widget\_type: widget

#### **Description**

The widget is a general purpose XmRowColumn manager capable of containing any widget type as a child. In general, XmRowColumn requires no special knowledge of how its children function and provides nothing beyond support for several different layout styles. However, XmRowColumn can be configured as a menu, in which case, it expects only certain children and it configures to a particular layout. The menus supported are: MenuBar, Pulldown, or Popup

MenuPanes and OptionMenu.

#### **Attributes**

Serpent

<u>Name</u>	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
isComposite	Boolean	true
managedWhenCreated	Boolean	true
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	

RowColumn

NameX TypeadjustLastBooleanadjustMarginBoolean

entryAlignment unsigned\_char

entryBorder short

entryCallback CallbackList
entryClass WidgetClass
isAligned Boolean
isHomogeneous Boolean
labelString String

mapCallback CallbackList
marginHeight Dimension
marginWidth Dimension
menuAccelerator String
menuHelpWidget Widget

menuHistory Widget
mnemonic char
numColumns short

orientation unsigned\_char packing unsigned\_char

popupEnabled Boolean
radioAlwaysOne Boolean
radioBehavior Boolean
resizeHeight Boolean
resizeWidth Boolean

rowColumnType unsigned\_char

spacing short

subMenuId Widget

unmapCallback CallbackList

whichButton unsigned\_int

RowColumn Special Menu

Name X Type

menuCursor String

Manager Resource Set

Name X Type Default

bottomShadowColor Pixel

bottomShadowPixmap Pixmap UNSPECIFIED\_Pixmap

foreground Pixel

helpCallback CallbackList

highlightColor Pixel black

highlightPixmap Pixmap shadowThickness short topShadowColor Pixel

topShadowPixmap Pixmap UNSPECIFIED\_Pixmap

unitType unsigned\_char PIXELS

userData caddr\_t NULL

**Composite Resource Set** 

Name X Type
insertPosition OrderProc

Core Resource Set

302

Name X Type Default

accelerators Accelerators ancestorSensitive Boolean

background Pixel
backgroundPixmap Pixmap
borderColor Pixel
borderPixmap Pixmap

borderWidth Dimension 1

colormap Colormap depth Cardinal

destroyCallback CallbackList

height	Dimension
mappedWhenManaged	Boolean
screen	Screen
sensitive	Boolean
width	Dimension
x	Position
У	Position
translations Translations:	Shift <btn1down>,<btn1up>: pick() Shift<btn2down>,<btn2motion>:resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>:resize() Shift<btn2down>,<btn2motion>,<btn2up>:resize() Shift<btn3down>,<btn3motion>:move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>:move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>:move() Shift<btn3down>,<btn3motion>,<btn3up>:move() <unmap>: MenuUnmap() <focusin>: MenuFocusIn() <focusout>:MenuFocusOut() <enterwindow>: MenuEnter() <key>Left: MenuGadgetTraverseLeft() <key>Right: MenuGadgetTraverseRight() <key>Up: MenuGadgetTraverseUp() <key>Down: MenuGadgetTraverseDown()</key></key></key></key></enterwindow></focusout></focusin></unmap></btn3up></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></btn2motion></btn2down></btn2up></leave></btn2motion></btn2down></btn2motion></btn2down></btn1up></btn1down>

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

### **XmScale**

#### Serpent Name

XmScale

include\_file: /Scale.h

class: ScaleWidgetClass

widget\_type: widget

#### **Description**

The xmscale widget is used by an application to indicate a value from within a range of values, and it allows the user to input or modify a value from the same range. Xmscale has an elongated, rectangular region similar to that of scrollBar. Inside this region is a slider that indicates the current value of Xmscale. The user can also modify the value of Xmscale by moving the slider within the rectangular region. Xmscale can also include a set of labels located outside the scale region. These can indicate the relative value at various positions along the scale.

#### **Attributes**

Serpent

Name	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	

#### Separator

<u>Name</u>	<u>X Type</u>
decimalPoints	short

dragCallback CallbackList
fontList FontList
highlightOnEnter Boolean
highlightThickness short

maximum int minimum int

orientation unsigned\_char
processingDirection unsigned\_char
scaleHeight Dimension
scaleWidth Dimension
showValue Boolean
titleString String
traversalOn Boolean

value int

Manager Resource Set

Name X Type Default

bottomShadowColor Pixel

bottomShadowPixmap Pixmap UNSPECIFIED\_Pixmap

foreground Pixel

helpCallback CallbackList

highlightColor Pixel black

shadowThickness short

topShadowPixmap Pixmap UNSPECIFIED\_Pixmap

unitType unsigned\_char PIXELS

userData caddr\_t NULL

**Composite Resource Set** 

Name X Type

insertPosition OrderProc

Core Resource Set			
<u>Name</u>	X Type	<u>Default</u>	
accelerators	Accelerators		
ancestorSensitive	Boolean		
background	Pixel		
backgroundPixmap	Pixmap		
borderColor	Pixel		
borderPixmap	Pixmap		
borderWidth	Dimension	1	
colormap	Colormap		
depth	Cardinal		
destroyCallback	CallbackList		
height	Dimension		
mappedWhenManaged	Boolean		
screen	Scieen		
sensitive	Boolean		
width	Dimension		
x	Position		
У	Position		
Translations: Shift <btn1down>,<btn1up>: pick() Shift<btn2down>,<btn2motion>: resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>: r Shift<btn2down>,<btn2motion>,<btn2up>: resize() Shift<btn3down>,<btn3motion>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: r Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: r Shift<btn3down>,<btn3motion>,<btn3up>: move() <btn1down>: Arm() <btn1up>: Activate() <enterwindow>: Enter() <focusin>: FocusIn()</focusin></enterwindow></btn1up></btn1down></btn3up></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></btn2motion></btn2down></btn2up></leave></btn2motion></btn2down></btn2motion></btn2down></btn1up></btn1down>		Motion>: resize() Motion>, <leave>,<btn2up>: resize() Motion&gt;,<btn2up>: resize() Motion&gt;: move() Motion&gt;,<leave>,<btn3up>: move()</btn3up></leave></btn2up></btn2up></leave>	

Methods		
Name	<u>Parameters</u>	Description
value_changed		This method is sent to the dialogue in response to a user event (typically moving a slider).
move	х, у	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.

This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.

Pick selectedX, selectedY This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event

(typically a shifted Btn1Down).

# **XmScreenObject**

Serpent Name

XmScreenObject

Description

The xmscreenObject widget allows for the detection of screen display IDs: Display size includes height and width. Display type

includes color or black & white.

**Attributes** 

Serpent

Name X Type

color Boolean

display int

height Dimension

screen Screen

width Dimension

### **XmScrollBar**

#### **Serpent Name**

XmScrollBar

include\_file: Xm/ScrollBar.h

class: xmScrollBarWidgetClass

widget\_type: widget

#### **Description**

The xmscrollBar widget gives the user a means of viewing data that would not otherwise fit into the available space. The xmscrollbar is typically located adjacent to some viewing region. The scrollbar consists of two rectangular regions—a large one called the scroll region and a small one called the slider—and two arrows. When the slider is moved, directly or through the arrows, the viewable data is scrolled through the viewing region.

#### **Attributes**

Serpent

Name X Type **Default** Boolean false allowUserMove Boolean false allowUserResize MethodName method Widget parent **Position** 0 selectedX selectedY **Position** 0

int

ScrollBar

widget

Name X Type

decrementCallback CallbackList

dragCallback CallbackList

increment int

#### Motif Widget Set, XmScrollBar

incrementCallback CallbackList

initialDelay int maximum int minimum int

orientation unsigned\_char pageDecrementCallback CallbackList

pageIncrement int

repeatDelay int

showArrows Boolean

sliderSize int

toBottomCallback CallbackList toTopCallback CallbackList

value int

#### **Primitive Resource Set**

Name X Type Default

bottomShadowColor Pixel

bottomShadowPixmap Pixmap UNSPECIFIED\_PIXMAP

foreground Pixel

helpCallback CallbackList

highlightColor Pixel black highlightOnEnter Boolean false

highlightPixmap Pixmap

highlightThickness short 0
shadowThickness short 2

topShadowColor Pixel

topShadowPixmap Pixmap UNSPECIFIED\_PIXMAP

traversalOn Boolean false
unitType unsigned\_char PIXELS
userData caddr t NULL

userData caddr\_t
accelerators Accelerators

ancestorSensitive Boolean

310

background	Pixel
backgroundPixmap	Pixmap
borderColor	Pixel
borderPixmap	Pixmap
borderWidth	Dimension 1
colormap	Colormap
depth	Cardinal
destroyCallback	CallbackList
height	Dimension
mappedWhenManaged	Boolean
screen	Screen
sensitive	Boolean
width	Dimension
x	Position
У	Position
translations Translations:	Shift <btm1down>,<btm1up>: pick() Shift<btm2down>,<btm2motion>: resize() Shift<btm2down>,<btm2motion>,<leave>,<btm2up>: resize() Shift<btm2down>,<btm2motion>,<btm2up>: resize() Shift<btm3down>,<btm3motion>: move() Shift<btm3down>,<btm3motion>,<leave>,<btm3up>: move() Shift<btm3down>,<btm3motion>,<btm3up>: move()</btm3up></btm3motion></btm3down></btm3up></leave></btm3motion></btm3down></btm3motion></btm3down></btm2up></btm2motion></btm2down></btm2up></leave></btm2motion></btm2down></btm2motion></btm2down></btm1up></btm1down>

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	х, у	This method allows the user to move this widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).
value_changed		This method is sent to the dialogue in response to a user event (typically moving a slider).

# **XmScrolledWindow**

#### Serpent Name

XmScrolledWindow

include\_file: Xm/ScrolledW.h

class: xmScrolledWindowWidgetClass

widget\_type: widget

#### **Description**

The xmscrolledwindow widget combines one or more ScrollBar widgets and a viewing area to implement a visible window onto some other (usually larger) data display. The visible part of the window can be scrolled through the larger display by the use of ScrollBars.

#### **Attributes**

Serpent

<u>Name</u>	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	

#### ScrolledWindow Resource Set

<u>Name</u>	X Type
clipWindow	Widget
horizontalScrollBar	Widget
garollBarDianlamBalian	uncianed ch

scrollBarPlacement unsigned\_char scrollBarPlacement unsigned\_char scrolledWindowMarginHeightDimension

scrolledWindowMarginWidthDimension

scrollingPolicy

unsigned\_char

spacing

int

verticalScrollBar

Widget

visualPolicy

unsigned\_char

workWindow

Widget

Manager Resource Set

Name

X Type

Default

bottomShadowColor

Pixel

 $\verb|bottomShadowPixmap|$ 

Pixmap

UNSPECIFIED\_PIXMAP

foreground

Pixel

helpCallback

CallbackList

highlightColor Pixel

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowFixmap

Pixmap

UNSPECIFIED\_PIXMAP

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

NULL

black

**Composite Resource Set** 

Name

X Type

insertPosition

OrderProc

Core Resource Set

Name

X Type

Default

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixel

backgroundPixmap

Pixmap

borderColor

Pixel

borderPixmap

Pixmap

borderWidth

Dimension

1

## Motif Widget Set, XmScrolledWindow

colormap	Colormap
depth	Cardinal
destroyCallback	CallbackList
height	Dimension
mappedWhenManaged	Boolean
screen	Screen
sensitive	Boolean
width	Dimension 1
x	Position
У	Position
translations Translations:	Shift <btn1down>,<btn1up>: pick() Shift<btn2down>,<btn2motion>: resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<btn2down>,<btn2motion>,<btn2up>: resize() Shift<btn3down>,<btn3motion>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move()</btn3up></leave></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></btn2motion></btn2down></btn2up></leave></btn2motion></btn2down></btn2motion></btn2down></btn1up></btn1down>

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	х, у	This method allows the user to move this widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize this widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

# **XmSeparator**

**Serpent Name** 

XmSeparator

include\_file: Xm/Separator.h

class: XmSeparatorWidgetClass

widget\_type: widget

**Description** 

The XmSeparator widget is a primitive widget that separates items

in a display. Several different line drawing styles are provided, as well

as horizontal and vertical orientation.

**Attributes** 

Serpent

Name X Type

X Type Default
Boolean false

allowUserMove

\_\_\_\_\_

\_\_\_\_

allowUserResize

Boolean

false

method

MethodName

serpdef

parent

Widget

Position

0

selectedX selectedY

**Position** 

0

widget

int

Separator

short

orientation

unsigned\_char

separatorlype

unsigned\_char

**Primitive Resource Set** 

Name

X Type

**Default** 

bottomShadowColor

Pixel

bottomShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

foreground

Pixel

### Motif Widget Set, XmSeparator

helpCallback	CallbackList	
highlightColor	Pixel	black
highlightOnEnter	Boolean	false
highlightPixmap	Pixmap	
highlightThickness	short	0
shadowThickness	short	2
topShadowColor	Pixel	
topShadowPixmap	Pixmap	UNSPECIFIED_PIXMAP
traversalOn	Boolean	false
unitType	unsigned_char	PIXELS
userData	caddr_t	NULL
accelerators	Accelerators	
ancestorSensitive	Boolean	
background	Pixel	
backgroundPixmap	Pixmap	
borderColor	Pixel	
borderPixmap	Pixmap	
borderWidth	Dimension	1
colormap	Colormap	
depth	Cardinal	
destroyCallback	CallbackList	
height	Dimension	
mappedWhenManaged	Boolean	
screen	Screen	
sensitive	Boolean	
width	Dimension	
x	Position	
У	Position	
translations Translations:	Shift <btn1down>,<btn1up>: pick() Shift<btn2down>,<btn2motion>: resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<btn2down>,<btn2motion>,<btn2up>: resize() Shift<btn3down>,<btn3motion>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move()</btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></btn2motion></btn2down></btn2up></leave></btn2motion></btn2down></btn2motion></btn2down></btn1up></btn1down>	

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

## **XmText**

#### Serpent Name

XmText

include\_file: Xm/Text.h
class: TextWidgetClass
widget\_type: widget

check\_routine: check\_MText

### Description

The xmText widget provides a single and multi-line text editor for customizing both user and program interfaces. It can be used for single-line string entry, forms entry with verification procedures, and full-window editing. It provides an application with a consistent editing system for textual data. The screen's textual data adjusts to the application writer's needs.

#### **Attributes**

Serpent

 Name
 X Type
 Default

 allowUserMove
 Boolean
 false

 allowUserResize
 Boolean
 false

 method
 MethodName

 parent
 Widget

 sendBuffer
 Boolean

selectedX Position 0
selectedY Position 0

widget int

#### **Text**

Name X Type

activateCallback CallbackList

autoShowCursorPosition Boolean

cursorPosition TextPosition
editable Boolean

editMode int

focusCallback CallbackList
losingFocusCallback CallbackList

marginHeight short marginWidth short int

modifyVerifyCallback CallbackList
motionVerifyCallback CallbackList
topPosition TextPosition
value String

valueChangedCallback CallbackList

**Text Input** 

Name X Type
pendingDelete Boolean
selectionArray Pointer
selectThreshold int

**Text Output** 

Name

Name

X Type
blinkRate

columns

columns

short

cursorPositionVisible

fontList

resizeHeight

FontList

resizeWidth

Boolean

rows short wordWrap Boolean

**Text Scrolled Text** 

Name X Type scrollHorizontal Boolean

#### Motif Widget Set, XmText

scrollLeftSide

Boolean

scrollTopSide

Boolean

scrollVertical

Boolean

**Primitive Resource Set** 

<u>Name</u>

X Type

**Default** 

bottomShadowColor

**Pixel** 

bottomShadowPixmap

Pixmap

UNSPECIFIED\_Pixmap

foreground

Pixel

helpCallback

CallbackList

black

highlightColor highlightOnEnter Pixel

false

highlightPixmap

Boolean **Pixmap** 

highlightThickness

short

0

shadowThickness

short

2

topShadowColor

topShadowPixmap

**Pixel** 

**Pixmap** 

UNSPECIFIED\_Pixmap

traversalOn

Boolean

false

Techdef unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

**NULL** 

**Core Resource Set** 

Name

X Type

Default

1

accelerators

Accelerators

ancestorSensitive

Boolean

background

**Pixel** 

backgroundPixmap

Pixmap

borderColor

Pixel

borderPixmap

Pixmap

borderWidth

Dimension

colormap

depth

Colormap

Cardinal

destroyCallback

CallbackList

Dimension height Boolean mappedWhenManaged screen Screen Boolean sensitive Dimension width **Position** x Position У translations Translations: Shift<Key>Tab: tab() Ctrl<Key>Tab:next-tab-group() <Key>Tab:next-tab-group() <Key>Up:traverse-prev() <Key>Down:traverse-next() <Key>Home:traverse-home() Ctrl<Key>Right:forward-word() Shift<Key>Right: key-select(right) <Key>Right:forward-character() Ctrl<Key>Left:backward-word() Shift<Key>Left:key-select(left) <Key>Left:backward-character() Shift<Key>Delete: delete-previous-word() <Key>Delete:delete-previous-character() Shift<Key>Linefeed:delete-next-word() <Key>Linefeed:delete-next-character() Shift<Key>F13:delete-next-word() <Key>F13:delete-next-character() Shift<Key>BackSpace:delete-previous-word() <Key>BackSpace:delete-previous-character() <Key>Return:activate() send() ~Ctrl <Key>:self-insert() Shift<Btn1Down>,<Btn1Up>: pick() Shift<Btn2Down>,<Btn2Motion>: resize() Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize() Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize() Shift<Btn3Down>,<Btn3Motion>: move() Shift<Btn3Down>.<Btn3Motion>.<Leave>.<Btn3Up>: move() Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move() <Btn1Down>: grab-focus() Button1<PtrMoved>: extend-adjust() <Btn1Up>: extend-end() <Btn2Down>: secondary-start() Button2<PtrMoved>: secondary-adjust() Ctrl<Btn2Up>: move-to() secondary-end-and-kill() <Btn2Up>: copy-to() secondary-end() <ClientMessage>: secondary-stuff() remote-kill-selection() <LeaveWindow>: leave()

<FocusIn>: focusIn()
<FocusOut>: focusOut()
<Unmap>: unmap()

Methods		
<u>Name</u>	<u>Parameter</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
send	value	This method is returned when the send_buffer flag is set to true by the dialogue, or when there is a translation table action.
tab		This method is sent to the dialogue in response to a shifted tab.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).

# **XmToggleButton**

#### **Serpent Name**

XmToggleButton

include file: ToggleB.h

class xmToggleButtonWidgetClass

widget\_type: widget

#### **Description**

The XmToggleButton widget presents a choice of values (such as yes or no) to the user. When the user selects a toggle button, its value remains in use until another choice is toggled. Usually this widget consists of an indicator (square or diamond) with either text or a pixmap to its right. However, it can also consist of just text or a pixmap without the indicator.

#### **Attributes**

Serpent

Name X Type **Default** allowUserMove Boolean false allowUserResize Boolean false MethodName method Widget parent **Position** 0 selectedX **Position** selectedY 0 widget int CallbackList ToggleButton CallbackList disarmCallback fillOnSelect Boolean Boolean indicatorOn indicatorType unsigned\_char Pixel selectColor selectPixmap **Pixmap** 

#### Motif Widget Set, XmToggleButton

set

Boolean

spacing

short

valueChangedCallback

CallbackList

toggle\_callback

visibleWhenOff

Boolean

#### **Label Resource Set**

Name

X Type

accelerator

String

acceleratorText

String

alignment

unsigned\_char

fontList

**FontList** 

labelInsensitivePixmap

**Pixmap** 

labelPixmap

Pixmap

labelString

String

labelType

unsigned\_char

marginBottom

short

marginHeight

short

marginLeft

short

marginRight

short

marginTop

short

marginWidth

short

mnemonic

char

recomputeSize

Boolean

stringDirection

StringDirection

#### **Primitive Resource Set**

Name

X Type

**Default** 

bottomShadowColor

**Pixel** 

bottomShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

foreground

**Pixel** 

helpCallback

CallbackList

highlightColor

Pixel

black

highlightOnEnter

Boolean

false

highlightPixmap

**Pixmap** 

highlightThickness	short	0
shadowThickness	short	2
topShadowColor	Pixel	
topShadowPixmap	Pixmap	UNSPECIFIED_PIXMAP
traversalOn	Boolean	false
unitType	unsigned_char	PIXELS
userData	caddr_t	NULL
accelerators	Accelerators	
ancestorSensitive	Boolean	
background	Pixel	
backgroundPixmap	Pixmap	
borderColor	Pixel	
borderPixmap	Pixmap	
borderWidth	Dimension	1
colormap	Colormap	
depth	Cardinal	
destroyCallback	CallbackList	
height	Dimension	
mappedWhenManaged	Boolean	
screen	Screen	
sensitive	Boolean	
width	Dimension	
x	Position	
У	Position	
translations Translations:	Shift <bm1down>,<bm1up>: pick() Shift<bm2down>,<bm2motion>: resize() Shift<bm2down>,<bm2motion>,<leave>,<bm2up>: resize() Shift<bm2down>,<bm2motion>,<bm2up>: resize() Shift<bm3down>,<bm3motion>: move() Shift<bm3down>,<bm3motion>,<leave>,<bm3up>: move() Shift<bm3down>,<bm3motion>,<leave>,<bm3up>: move() Shift<bm3down>,<bm3motion>,<bm3up>: move() <bt 1down="">: Arm() <bt 1down="">: Arm() <key>Return: ArmAndActivate() <key>space: ArmAndActivate() <enterwindow>: Enter()</enterwindow></key></key></bt></bt></bm3up></bm3motion></bm3down></bm3up></leave></bm3motion></bm3down></bm3up></leave></bm3motion></bm3down></bm3motion></bm3down></bm2up></bm2motion></bm2down></bm2up></leave></bm2motion></bm2down></bm2motion></bm2down></bm1up></bm1down>	

<LeaveWindow>: Leave()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location, and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).
toggle	set	This method sends the new value of the toggle button to the user when the button is pressed.

# **XmTopLevelShell**

#### **Serpent Name**

XmTopLevelShell

include\_file X11/Shell.h

class: applicationShellWidgetClass

widget\_type: shell

#### **Description**

The XmTopLevelShell widget is the standard user shell. It is used for normal top-level windows and mediates the interaction between the widgets and the window manager.

#### **Attributes**

### TopLevelShell

Name

iconic

X Type

rcourc

Boolean

iconName

String

VendorShell

 $unsigned\_char$ 

keyboardFocusPolicy

unsigned\_char

mwmDecorations

int

mwmFunctions

int

mwmInputMode

int

mwmMenu

String

shellUnitType

unsigned\_char

WMShell

int

iconMask

Pixmap

iconPixmap

Pixmap

iconWindow

Window

iconX

int

iconY

int

initialState

int

input

Boolean

### Motif Widget Set, XmTopLevelShell

maxAspectX	int
maxAspectY	int
maxHeight	int
maxWidth	int
minAspectX	int
minAspectY	int
minHeight	int
minWidth	int

title char\_star
transient Boolean
waitForWm Boolean
widthInc int
windowGroup XID
wmTimeout int

#### **Shell Resource Set**

Name	X Type
allowShellResize	Boolean
createPopupChildProc	Boolean
geometry	caddr_t
overrideRedirect	Boolean
popdownCallback	caddr_t
popupCallback	caddr_t
saveUnder	Boolean

## Composite Resource Set

Name	X Type
insertPosition	OrderProc
accelerators	Accelerators
ancestorSensitive	Boolean
background	Pixel
backgroundPixmap	Pixmap
borderColor	Pixel
borderPixmap	Pixmap

borderWidth	Dimension 1
colormap	Colormap
depth	Cardinal
destroyCallback	CallbackList
height	Dimension
mappedWhenManaged	Boolean
screen	Screen
sensitive	Boolean
width	Dimension
x	Position
У	Position
translations Translations:	Shift <btn2down>,<btn2motion>: resize() Shift<btn2down>,<btn2motion>,<leave>,<btn2up>: resize() Shift<btn2down>,<btn2motion>,<btn2up>: resize() Shift<btn3down>,<btn3motion>: move() Shift<btn3down>,<btn3motion>,<leave>,<btn3up>: move() Shift<btn3down>,<btn3motion>,<btn3up>: move()</btn3up></btn3motion></btn3down></btn3up></leave></btn3motion></btn3down></btn3motion></btn3down></btn2up></btn2motion></btn2down></btn2up></leave></btn2motion></btn2down></btn2motion></btn2down>

Methods		
<u>Name</u>	<u>Parameters</u>	Default
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize this widget with the mouse and sends its x and y location and new width and height to the dialogue.

# **XmWarningDialog**

#### Serpent Name

XmWarningDialog

include\_file: Xm/MessageB.h

class: xmMessageBoxWidgetClass

widget\_type: widget

#### **Description**

The XmwarningDialog widget is a MessageBox created with a convenience routine. This dialogue is used to warn a user of the consequences of some action. The dialogue box comes with three buttons: OK, Cancel, and Help. The default symbol is an exclamation point.

#### **Attributes**

Serpent

Name X Type **Default** allowUserMove Boolean false Boolean false allowUserResize Boolean false deactivate isComposite Boolean true MethodName method Widget parent **Position** 0 selectedX selectedY **Position** widget int CallbackList MessageBox cancelLabelString String defaultButtonType unsigned\_char unsigned\_char dialogType String helpLabelString messageAlignment unsigned\_char

messageString

String

minimizeButtons

Boolean

okCallback

CallbackList

okLabelString

String

symbolPixmap

Pixmap

**BulletinBoard Resource Set** 

Name

X Type

allowOverlap autoUnmanage Boolean

buttonFontList

Boolean

Date official se

FontList

cancelButton

Widget

defaultButton

Widget

defaultPosition

Boolean

dialogStyle

unsigned\_char

dialogTitle

String

focusCallback

CallbackList

labelFontList

FontList

mapCallback

CallbackList

marginHeight

short

marginWidth

short

noResize

Boolean

resizePolicy

unsigned\_char

shadowType

unsigned\_char

stringDirection

StringDirection

textFontList

FontList

textTranslations

Translations

unmapCallback

CallbackList

Manager Resource Set

Name

X Type

**Default** 

bottomShadowColor

Pixel

bottomShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

foreground

Pixel

#### Motif Widget Set, XmWarningDialog

helpCallback

CallbackList

highlightColor

Pixel

black

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowFixmap

Pixmap

UNSPECIFIED\_PIXMAP

unitType

unsigned\_char

PIXELS

userData

caddr\_t

NULL

#### Composite Resource Set

Name

X Type

insertPosition

OrderProc

#### **Core Resource Set**

Name

X Type

Default

1

accelerators

Accelerators

ancestorSensitive

Boolean

background

Pixel

backgroundPixmap

Pixmap

borderColor

Pixel

borderPixmap

Pixmap

borderWidth

Dimension

colormap

Colormap

depth

Cardinal

destroyCallback

CallbackList

height

Dimension

mappedWhenManaged

Boolean

screen

Screen

Boolean

sensitive

Dimension

width x

**Position** 

У

**Position** 

translations Translations: <EnterWindow>: Enter()

<FocusIn>: FocusIn()

Shift<Bm1Down>,<Bm1Up>: pick()

<Btn1Down>: Arm()
<Btn1Up>: Activate()
<Key>F1: Help()
<Key>Return: Return()
<Key>KP\_Enter: Return()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Leave>,<Btn2Up>: resize()

Shift<Bm2Down>,<Bm2Motion>,<Bm2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Bm3Down>,<Bm3Motion>,<Leave>,<Bm3Up>: move()

Shift<Btn3Down>,<Btn3Motion>,<Btn3Up>: move()

Methods		_
Name	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Btn1Down).

# **XmWorkingDialog**

#### Serpent Name

XmWorkingDialog

include\_file: Xm/MessageB.h

class: xmMessageBoxWidgetClass

widget\_type: widget

#### **Description**

The xmworkingDialog widget is a MessageBox created with a convenience routine. This dialogue is used to notify a user about a time-consuming operation in progress. The dialogue box comes with three buttons: OK, Cancel, and Help. The default symbol is an hourglass.

#### **Attributes**

Serpent

_		
<u>Name</u>	X Type	<u>Default</u>
allowUserMove	Boolean	false
allowUserResize	Boolean	false
deactivate	Boolean	false
isComposite	Boolean	false
method	MethodName	
parent	Widget	
selectedX	Position	0
selectedY	Position	0
widget	int	
MessageBox	CallbackList	
cancelLabelString	string	
defaultButtonType	unsigned_char	
dialogType	unsigned_char	
helpLabelString	String	
messageAlignment	unsigned_char	

messageString

String

minimizeButtons

Boolean

okCallback

CallbackList

okLabelString

String

symbolPixmap

Pixmap

#### **BulletinBoard Resource Set**

Name

X Type

allowOverlap

Boolean

autoUnmanage

Boolean

buttonFontList

FontList

cancelButton

Widget

defaultButton

Widget

 ${\tt defaultPosition}$ 

Boolean

dialogStyle

unsigned\_char

dialogTitle

String

focusCallback

CallbackList

labelFontList

**FontList** 

mapCallback

CallbackList

marginHeight

short

marginWidth

short

noResize

Boolean

resizePolicy

unsigned\_char

shadowType

unsigned\_char

stringDirection

StringDirection

textFontList

FontList |

textTranslationsa

Translations

unmapCallback

CallbackList

#### Manager Resource Set

**Name** 

X Type

**Default** 

bottomShadowColor

Pixel

bottomShadowPixmap

Pixmap

UNSPECIFIED\_PIXMAP

foreground

Pixel

#### Motif Widget Set, XmWorkingDialog

helpCallback

CallbackList

highlightColor

Pixel black

highlightPixmap

Pixmap

shadowThickness

short

topShadowColor

Pixel

topShadowPixmap

UNSPECIFIED\_PIXMAP

unitType

unsigned\_char

**PIXELS** 

userData

caddr\_t

Pixmap

NULL

Composite Resource Set

Name

X Type

insertPosition

OrderProc

Core Resource Set

Name

X Type

Default

accelerators

Accelerators

ancestorSensitive

Boolean

background

**Pixel** 

backgroundPixmap

Pixmap

borderColor

Pixel

borderPixmap

Pixmap

borderWidth

**Dimension** 

colormap

Colormap

depth

Cardinal

destroyCallback

CallbackList

height

Dimension

mappedWhenManaged

Boolean

screen

Screen

sensitive

Boolean

width

Dimension

x

**Position** 

У

336

**Position** 

translations

Translations: <EnterWindow>: Enter()

<FocusIn>: FocusIn()

Shift<Btn1Down>,<Btn1Up>: pick()

<Btn1Down>: Arm()
<Btn1Up>: Activate()
<Key>F1: Help()
<Key>Return: Return():

<Key>KP\_Enter: Return()

Shift<Btn2Down>,<Btn2Motion>: resize()

Shift<Bm2Down>,<Btm2Motion>,<Leave>,<Btm2Up>: resize()

Shift<Btn2Down>,<Btn2Motion>,<Btn2Up>: resize()

Shift<Btn3Down>,<Btn3Motion>: move()

Shift<Btn3Down>,<Btn3Motion>,<Leave>,<Btn3Up>: move()

Shift<Bm3Down>,<Bm3Motion>,<Bm3Up>: move()

Methods		
<u>Name</u>	<u>Parameters</u>	Description
move	x, y	This method allows the user to move the widget with the mouse and sends the widget's new x and y location to the dialogue.
resize	x, y, width, height	This method allows the user to resize the widget with the mouse and sends its x and y location and new width and height to the dialogue.
pick	selectedX, selectedY	This method allows the user to select a point on the widget with the mouse and sends the location of the point to the dialogue in response to a user event (typically a shifted Bm1Down).

Index	Logical AND and OR operators 53 Loop statement 61
A	-
Actions "on create" 69	M
Application shared data 47	make_integer, truncate 91
Arithmetic operators 56	Methods 45, 64
Assignment statement 60	mod 92
Attributes 44, 63	
	0
В	Object instances 44
Base types 37	Object type 36
board 143	n
	R
C	Relational operators 55
Character Set 29	Routines 43
Code snippet 59	S
Comments 29	_
constants 32	Shared data 45
identifiers 31	string_append 78
reserved words 31	string_count_chars 79
Conditional statement 60	string_delete 80
Constant 43	string_index 81
Context 39	string_insert 82
D.	string_is_integer 83
D	string_is_real 84
Data elements 46	string_length 85
Declared data 43	string_lower 86
Definition file 46	string_upper 87
Dependency 37	substring 88
Scope 39	U
Dependency considerations 70	
Dialogue shared data 46	Unary operators 58 Undefined values 53
div 90	Oliderfiled values 33
Documentation 2	V
E	View controllers 67
	Visible 39
Equality operators 54	V Brote 37
Extent 42	X
F	XawBboard 143
Function call 59	XawBox 146
i unction can 37	XawCommand 149
I	XawDialog 153
Identifiers 31	XawForm 156
Implications of dependencies 100	XawLabel 159
Instances 43	XawMenuButton 162

#### XmWorkingDialog 334

XawMenuShell 165

XawPaned 168

XawScreenObject 203

XawScrollbar 173

XawSimpleMenu 176

XawSimpleMenuBSB 165

XawSmeLine 182

XawText 185

XawTextentry 185

XawToggleButton 195

XawTopLevelShel 199

XawViewport 201

XmArrowButton 207

XmBulletinBoard 210

XmCascadeButton 214

XmCommand 218

XmDrawingArea 223

XmDrawnButton 226

XmErrorDialog 230

XmFileSelectionBox 234

XmForm 239

XmFrame 243

XmInformationDialog 246

XmLabel 250

XmList 253

XmMainWindow 258

XmMenubar 262

XmMenuShell 266

XmMessageBox 269

XmMessageDialog 273

XmOption 277

XmPanedWindow 281

XmPopup 284

XmPulldown 288

XmPushButton 292

XmQuestionDialog 296

XmRowColumn 300

XmScale 304

XmScreenObject 308

XmScrollDar 309

XmScrolledWindow 312

XmSeparator 315

XmText 318

XmToggleButton 323

XmTopLevelShell 327

XmWarningDialog 330

REPORT DOCUMENTATION PAGE							
14. REPORT SE Unclassifie	curity classif	ICATION		16. RESTRICTIVE N None	MARKINGS		
2a. SECURITY CLASSIFICATION AUTHORITY N/A		Approved for	3. DISTRIBUTION/AVAILABILITY OF REPORT Approved for Public Release				
2b. DECLASSIFICATION/DOWNGRADING SCHEDULJ: N/A		Distribution Unlimited					
4. PERFORMIN	G ORGANIZATIO	N REPORT NUMBER	R(S	5. MONTTORING O	RGANIZATION REI	PORT NUMBER	R(S)
CMU/SEI-	91-UG-5			CMU/SEI-91-	UG-5		
		6b. OFFICE SYMBOL (if applicable) SEI	[	7a. NAME OF MONTTORING ORGANIZATION SEI Joint Program Office			
6. ADDRESS (City, State and ZIP Code) Carnegie Mellon University Pittsburgh PA 15213		7b. ADDRESS (City, ESD/AVS Hanscom Air					
ORGANIZAT	8a NAME OFFUNDING/SPONSORING ORGANIZATION (if applicable) SEI Joint Program Office ESD/AVS		(if applicable)	9. PROCUREMENT F1962890C00		NTIFICATION	NUMBER
8c. ADDRESS (C	City, State and ZIP C	Code)	·	10. SOURCE OF FUN	OING NOS.		
Carnegie M Pittsburgh	Carnegie Mellon University Pittsburgh PA 15213		PROGRAM ELEMENT NO 63752F	PROJECT NO. N/A	TASK NO N/A	WORK UNIT NO. N/A	
	de Security Classific Slang Revere					<del></del>	
12 PERSONAL SEI User II	AUTHOR(S) nterface Proj	ect					
13a. TYPE OF REPORT 13b. TIME COVERED FINAL FROM TO		14. DATE OF REPORT (Yr., Mo., Day)  15. PAGE COUNT  ~350					
16. SUPPLEME	NTARY NOTATIO	N					
17. COSATI CODES 18. SUBJECT TERMS (I		Continue on reverse of necessary and identify by block number)					
FIELD	GROUP	SUB. GR.	7	6, user interface management system, user			
			interface generators, Slang, dialogue				
19. ABSTRACT (Continue on reverse if necessary and identify by block number)  Serpent is a user interface management system (UIMS) that supports the development and implementation of user interfaces, providing an editor to specify the user interface and a runtime system that enables communication between the application and the end user. This manual describes the model, syntax, and semantics of the Slang dialogue language, the language within Serpent used for the specification of user interfaces. Readers should be familiar with general UIMS concepts, have a working knowledge of programming languages, and understand the concepts described in Serpent Overview and Serpent: System Guide.							
ידיומו פרופות מ	ION/AVAII ARII FI	TY OF ARSTDACT	· <del></del>	1 ARSTDACTOR	CIDITY CI Accura	CATION	(please tum over)
	20. DISTRIBUTION/AVAILABILITY OF ABSTRACT  UNCLASSIFIED/UNLIMITED SAME AS RPT DTIC USERS Unclassified, Unlimited Distribution						
22a. NAME OF RESPONSIBLE INDIVIDUAL John S. Herman, Capt, USAF			225. TELEPHONE 1 (412) 268-76	NUMBER (Include A	area Code)	22c. OFFICE SYMBOL ESD/AVS (SEI JPO)	

ABSTRACT —continued from page one, block 19		(
•	1	
l	1	
[		
		•
\$		
<b>1</b>		
İ		
1		
1		
Į		
	i	
		_
		•
	ĺ	
	l l	
	Į.	
	1	
	i	